## RTE. SECTION COUNTY TOTAL SHEETS NO. 301 (2HB)M WINNEBAGO 13 3

TO STA.\_\_\_\_ STA. \_\_\_\_\_ TO STA.\_\_\_\_\_
FED. ROAD DIST. NO. \_ ILLINOIS FED. AID PROJECT

## **GENERAL NOTES**

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 2A shall be used, except in front of properties where the grass will be mowed, then use Seeding, Class 1. Class 2A shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches. This work will be included in the contract unit price per Lump Sum for MOBILIZATION.

Fertilizer shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding or placement of sod at the rate specified in Sections 250 and 252 of the Standard Specifications. This work shall be included in the cost of MOBILIZATION.

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the MOBILIZATION.

The following Mixture Requirements are applicable for this project:

Mixture Uses(s): Surface PG 64-22 Design Air Voids 4.0 0 N50 Mixture Composition IL 9.5 or 12.5 (Gradation Mixture) Friction Aggregate D 2.1 20 Year ESAL 112 lbs/sy/in Mix Unit Weight

Install a "TO ACTIVATE SIGNAL" sign for the traffic signal detector loops. The detail of this sian is included in the plans. This work will be included in the cost of TRAFFIC CONTROL AND PROTECTION STANDARD 701321.

This structure will retain the same number 101-0094.

At bridge expansion joints, if temporary expansion joint bulkheads are attached to adjacent deck slabs or abutments for support, the Contractor shall cut the attachments as soon as the concrete has set to prevent joint damage due to horizontal contraction or expansion.

> General Notes Montague Road over US 20 FAP 301 (US 20) Section (2HB)M <u>Winnebago County</u> Structure Number 101-0094