General Notes

The final top 100 mm (four inches) of soll in any right-of-way area disturbed by the Contractor must be capable of supporting vegetation. The soll must be from the A horizon (zero to 2' deep) of soll profiles of local soils.

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 2A shall be used, except in front of properties where the grass will be mowed, then use Seeding, Class 1. Class 2A shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches. This work will be included in the contract unit price per Square Foot for PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH).

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH).

Install a "TO ACTIVATE SIGNAL" sign for the traffic signal detector loops. The detail of this sign is included in the plans. This work will be included in the cost of TRAFFIC CONTROL AND PROTECTION STANDARD 701321.

This structure will retain the same number 037-0071.

The contractor shall submit four copies of the required shop drawings for review and approval to the Bureau of Bridges and Structures, 2300 South Dirksen Parkway, Springfield, IL 62764. After approval of initial submittal, the contractor shall submit one set of shop drawings to Dave Lippert, Engineer of Materials, 126 East Ash Street, Springfield, IL 62706, and eight (8) sets of shop drawings to be distributed to:

District 2 District Engineer (1) Fabricator (1) Contractor (2) Resident Engineer (2) District 2 Bureau of Materials (2)

DATE = Wed Jun 20 10:47:19 2007 VANE = D.br.VCADD plansVHarry C SCALE = 50.0000 '/ IN. NAME = linkdj

PLOT F1LE PLOT USER Culvert & bridge flows must be maintained throughout the project. Normal flow shall be allowed to pass at the rate it enters the jobsite. High flows shall be allowed to pass without causing damage to upstream properties.

					• *
			CONTRACT	NO. 64	D73
<u></u>	F.A.P. RTE	SECTION	COUNTY	TOTAL	SHEET NO.
	638	(129BR-1)D	Henry	8	3
	STA.		TO STA	·	1.0
	FED. ROAD	DIST. NO ILLI	NOIS FED. AID	PROJECT	

<u>General Notes</u> <u>FAP Route 638 (IL 82)</u> <u>Section (129BR-1)D</u> <u>Henry County</u> <u>Illinois Route 82 over the Green River</u> <u>Structure No. 037-0071</u>