F	A.I. TE.	SECTION		COUNT	Y SHEETS	SHEET NO.
	55	*		**	13	2
S	TA		то	STA		
CI	n onen	DIST NO	te i imate	cen /	ITO DOO ISCT	

- D-6 MEDIAN PROTECTION 2007
 - MACOUPIN, MONTGOMERY, SANGAMON,
 AND LOGAN COUNTIES

LIST OF STANDARDS:
630001-07 635011-01
630301-04 701101-01
631011-03 701106-01
631031-06 701400-02
635006-02 701406-04
702001-06

Route	*		
Koute		 4.14	
Section			
C	·	 	
County	***************************************	 	

EXAMINED May 2	20 27
WRZ	
PROGRAM IMPLEMENTATION ENGINE	ER
EXAMINED May 8	20 07
W.R.	
PROGRAM DEVELOPMENT ENGINEER	

	• *
DISTRICT SIX	
EXAMINED Nay 2 OPERATIONS ENGINEER	o <u>07</u>

ILLINOIS DEPARTMENT OF TRANSPORTAT	VS I	REVISION	
ILLINOIS DEPARTMENT OF TRANSPORTA	DATE	NAME	
GENERAL NOTES			
E41 EE			

FAI 55
SECTION D-6 MEDIAN PROTECTION 2007
MACOUPIN, MONTGOMERY,
SANGAMON, LOGAN COUNTIES

GENERAL NOTES:

- 1. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.
- 2. NO EXCAVATION IS ANTICIPATED ON THIS PROJECT WHICH WOULD AFFECT UTILITIES. SHOULD NOTIFICATION BE NECESSARY, THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING J.U.L.I.E. A MINIMUM OF 48 HOURS PRIOR TO COMMENCING WORK (800) 892-0123.
- 3. THE CONTRACTOR WILL BE REQUIRED TO CONTACT THE OPERATIONS ENGINEER (217) 782-7314 AT LEAST 72 HOURS PRIOR TO DRIVING ANY POSTS. TO MAKE SURE STATE OWNED UTILITIES ARE NOT IN THE WAY.
- 4. THE CONTRACTOR WILL BE REQUIRED TO REPAIR ANY AREAS OF TURF THAT ARE DAMAGED DURING THE EXECUTION OF THIS CONTRACT. THIS WORK WILL NOT BE MEASURED FOR PAYMENT AND WILL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 5. ALL GUARDRAIL SHALL HAVE A PRELIMINARY LAYOUT.
 GUARDRAIL POSTS SHALL BE ADJUSTED SO AS TO MISS ANY
 SHOULDER DRAINS, INLETS, PIPE CULVERTS, STORM SEWER OR
 ANY OTHER HAZARD THAT MAY INTERFERE WITH GUARDRAIL
 CONSTRUCTION.