CONTRACT NO. 72803

			-		701 140	. 12003
F.A.I. RTE.	SECTIO	4	COUNT	Υ	TOTAL	SHEET NO.
72			**		12	2
STA	TO STA.					
FED. ROA	D DIST. NO.	ILLINO	S FED.	AID	PROJECT	ŕ

\* - D-6 MEDIAN PROTECTION 2007-1

\*\* - ADAMS, NORGAN, PIKE,
SANGAMON AND SCOTT COUNTIES

INDEX OF SHEETS: LIST OF STANDARDS: 1. COVER SHEET 630001-07 635011-01 630301-04 2. GENERAL NOTES 701101-01 3. SUMMARY OF QUANTITIES 631011-03 701106-01 4-7. SCHEDULES 631031-06 701400-02 8. PLAN SHEETS 635006-02 701406-04 9-12. DETAILS 702001-06

## GENERAL NOTES:

1. ANY REFERENCE TO THE STANDARDS THROUGHT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN HE PLANS.

12A. TRAFFIC BARRIER TERMINAL, TYPE 1

- 2. NO EXCAVATION IS ANTICIPATED ON THIS PROJECT WHICH WOULD AFFECT UTILITIES. SHOULD NOTIFICATION BE NECESSARY, THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING J.U.L.I.E. A MINIMUM OF 48 HOURS PRIOR TO COMMENCING WORK (800) 892-0123.
- 3. THE CONTRACTOR WILL BE REQUIRED TO CONTACT THE OPERATIONS ENGINEER (217) 782-7314 AT LEAST 72 HOURS PRIOR TO DRIVING ANY POSTS. TO MAKE SURE THAT STATE OWNED UTILITIES ARE NOT CONFLICTING.
- 4. THE CONTRACTOR WILL BE REQUIRED TO REPAIR ANY AREAS OF TURF THAT ARE DAMAGED DURING THE EXECUTION OF THIS CONTRACT. THIS WORK WILL NOT BE MEASURED FOR PAYMENT AND WILL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 5. ALL GUARDRAIL SHALL HAVE A PRELIMINARY LAYOUT.
  GUARDRAIL POSTS SHALL BE ADJUSTED SO AS TO MISS ANY
  SHOULDER DRAINS, INLETS, PIPE CULVERTS, STORM SEWER OR
  ANY OTHER HAZARD THAT MAY INTERFERE WITH GUARDRAIL
  CONSTRUCTION.

Route		
Section	2.3	
County	 1 + 21 1 + 31	

	WRIT	67
ſ	PROGRAM IMPLEMENTATION ENGINEER	
<u> </u>	EXAMINED May 8 20	
1	PROGRAM DEVELOPMENT ENGINEER	

DISTRICT SIX	
EXAMINED May 9  OPERATIONS ENGINEER	20 67

REVISIO	NS.
NAME	DATE
~~~~~~	
·····	
	1

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

FAI 72
SECTION D-6 MEDIAN PROTECTION 2007-1
ADAMS, MORGAN, PIKE, SANGAMON
AND SCOTT COUNTIES

1.07 DATE = 5/10/2007 ilE NAME = c:\Projects\d653007\shtsoc COT SCALE = 105.8624 '/ Bk

D6 PROJECT: d653007 FILE: shtsoq.dgn

Rev.