STATE OF ILLINOIS


DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

PROPOSED HIGHWAY PLANS

FAP ROUTE 793 (IL 143) SECTION 112BR-2 PROJECT: BHF-0793(019) SUPERSTRUCTURE REPLACEMENT **BOND COUNTY**

C-98-055-07



FOUR SPAN PPC DECK BEAM SUPERSTRUCTURE TO BE REPLACED IN KIND OVER BEAVER CREEK SN 003-0035 206' - 8 1/2" BK TO BK ABUTMENTS

DEPARTMENT OF TRANSPORTATION

LOCATION OF SECTION INDICATED THUS: - -

PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

MICROFILMED REEL NUMBER AWARDED RESIDENT ENGINEER AS BUILT CHANGES WERE MADE ON THE FOLLOWING SHEETS

FOR INDEX OF SHEETS, SEE SHEET NO. 2

FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD

ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION 1--800--892--0123

CONTRACT NO. 76897

SECTION 112BR-2

FAP ROUTE 793

DESIGN DESIGNATION

LAT = 38.77038 LONG = 89.40447

GROSS LENGTH NET LENGTH

0.039 MI 0.039 M

D-98-037-05

SECTION

112BR-2

COUNTY

(")

(618) 346 - 3179

(618) 346 - 3209PATTI LeBEAU

CONTACT: ARTHUR MUEHLFELD

PROJECT ENGINEER:

SQUAD

INDEX OF SHEETS

- **COVER SHEET**
- INDEX OF SHEETS, HIGHWAY STANDARDS, **GENERAL NOTES & COMMITMENTS**
- **SUMMARY OF QUANTITIES**
- TYPICAL SECTIONS - 5
- 6-7 **SCHEDULES OF QUANTITIES**
- TIE POINTS & BENCHMARKS
- PLAN AND PROFILE SHEETS 9-10
- WIDE LOAD SIGNING 11 STAGE CONSTRUCTION
- STORM WATER POLLUTION PREVENTION PLAN 16-17
- **EROSION CONTROL** 18-19
- 20-23 PLAT OF HIGHWAYS
- TEMPORARY USE PERMIT EXHIBIT 23A
- **MISCELLANEOUS DETAILS** 24-26A
- **PAVEMENT MARKING SHEETS** 27-28
- 29-43 **BRIDGE PLANS**

12-15

- 43A **EXISTING STRUCTURE PLAN**
- **MAINLINE CROSS SECTIONS** 44-48
- **UNDER BRIDGE CROSS SECTIONS** 49
- 50 **ENTRANCE CROSS SECTIONS**
- 51-52 ENTRANCE STA 672+25 LT CROSS SECTIONS
- TRAFFIC BARRIER TERMINAL TYPE & DETAIL 52 A.

HIGHWAY STANDARDS

00000104	635006-02	701311-02
280001-03	63501101	70132108
515001-02	666001	701326-02
63000107	701011-01	70200106
630301-04	701301-02	704001-03
631032-03	701306-01	78000101
		781001-02

GENERAL NOTES:

- 1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
- 2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
- 3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - * BOND MADISON WATER COMPANY
 - * CENTERPOINT ENERGY
 - AT&T (COMMUNICATIONS)
 - * SOUTHWESTERN ELECTRIC COOPERATIVE, INC. MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY *. NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
- 4. RIGHT OF WAY MARKERS SHALL BE SET SO THE BACK OF THE POST IS TWELVCE INCHES (12") INSIDE THE RIGHT OF WAY BOUNDARY. RIGHT OF WAY PROPERTY CORNERS ARE MARKED BY A 5/8" IRON ROD WITH IDOT ALUMINUM CAP AND SHALL NOT BE REMOVED OR DAMAGED WHEN SETTING THE RIGHT OF WAY MARKERS.
- 5. THE CONTRACTOR SHALL PROVIDE TWO SIGNAL HEADS (EACH) FOR THE ENTRANCES LOCATED WITHIN THE STAGE CONSTRUCTION AT STA 668+09.78 RT AND STA 673+88.84 RT. THE SIGNALS, DETECTOR LOOPS, AND THE NUMBER OF TURNS OF WIRE IN THE LOOPS SHALL BE AS DETERMINED
- "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT THE BEGINNING AND ENDING OF THE PROJECT AND ALL INTERSECTING SIDE ROADS AND WILL BE INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLOURESCENT ORANGE.
- 7. ALL SIGNS THAT INTERFERE WITH CONSTRUCTION OPERATIONS SHALL BE REMOVED, STORED AND RE-ERECTED ACCORDING TO ARTICLE 107.25 OF THE STANDARD SPECIFICATIONS.
- 8. ANY DAMAGE TO SIGNS CAUSED BY CONSTRUCTION ACTIVITIES SHALL BE REPLACED AT THE CONTRACTOR'S
- 9. ALL SAW CUTTING FOR REMOVAL ITEMS SHALL BE FULL DEPTH AND SHALL BE INCLUDED IN THE COST
- 10. NO TRENCHES OR OPEN PITS WILL BE PERMITTED ADJACENT TO A TRAFFIC LANE DURING NON-WORKING HOURS. ALL WIDENING TRENCHES SHALL BE BACKFILLED DURING THE SAME WORKING DAY IT WAS
- 11. THE COST FOR GRADING AND SHAPING ALONG THE PROPOSED WIDENING SHALL BE INCLUDED IN THE COST OF "EARTH EXCAVATION (WIDENING)".
- 12. THE TRAFFIC CONTROL MEASURES SHOWN ON PLANS FOR STAGE I AND II SHALL SUPPLEMENT AND BE IN ACCORDANCE WITH TRAFFIC CONTROL STANDARD 701321.
- 13. THE COST OF "BARRICADES, TYPE III" USED DURING STAGE CONSTRUCTION SHALL BE INCLUDED IN THE COST OF "TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)".
- 14. A QUANTITY OF 800 FEET OF "TEMPORARY PAVEMENT MARKING LINE 6 INCHES" WHITE HAS BEEN INCLUDED IN THE PLANS FOR PAINTING THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER.
- 15. THE BARRIER UNIT AT EACH END OF THE TRAFFIC CONTROL INSTALLATION SHALL BE SECURED TO THE PAVEMENT OR SHOULDER USING ALL SIX ANCHORING PINS FOR F-SHAPE BARRIER OR ALL SIX DOWEL BARS FOR NEW JERSEY SHAPE BARRIER.
- 16. THE TEMPORARY CONCRETE BARRIER (STATE OWNED) IS LOCATED AT THE CARLYLE MAINTENANCE YARD, CONTACT JASON ROECKENHAUS AT (618) 594-3001 PRIOR TO PICK UP. THE CONTRACTOR SHALL PICK UP THE BARRIER AND RETURN THE BARRIER TO THE SAME LOCATION UPON COMPLETION OF THE PROJECT. ANY DAMAGED BARRIER WILL NOT HAVE TO BE REPLACED. THE CONTRACTOR SHALL DISPOSE OF DAMAGED CONCRETE BARRIER IN AN APPROVED DUMP SITE. THE CONNECTOR PINS SHALL BE FURNISHED BY THE CONTRACTOR AND THE COST SHALL BE INCLUDED WITH THE COST OF "TEMPORARY CONCRETE BARRIER (STATE OWNED)".

COMMITMENTS

PRIOR TO COMMENCEMENT OF ANY WORK INVOLVING IN-STREAM ACTIVITY, THE RESIDENT ENGINEER SHALL VERIFY WITH THE DISTRICT HYDRAULICS ENGINEER, FRANK OPFER, THAT THE NATIONWIDE 404 PERMIT HAS BEEN ISSUED AND IS IN EFFECT FOR THIS PROJECT.

ANY DISTURBED WETLAND AREA OUTSIDE THE CONSTRUCTION LIMITS SHALL BE SEEDED WITH REDTOP (AGROTIS ALBA) AT 10 LBS PER ACRE AT THE CONTRACTOR'S EXPENSE.

AN ENTRANCE SHALL BE CONSTRUCTED AT STA 672+25 LT FOR PARCEL 8607002. THIS ENTRANCE SHALL BE CONSTRUCTED DURING STAGE II AND OPENED UPON REMOVAL OF THE STAGE CONSTRUCTION.

THE PIPE CULVERT UNDER THE FIELD ENTRANCE AT STA 665+55.16 LT WILL BE REMOVED AND REPLACED WITH THIS PROJECT. THE PIPE SHALL BE REPLACED AS A PRE-STAGE TO STAGE CONSTRUCTION OF THE STRUCTURE. THE PROPERTY OWNERS SHALL BE NOTIFIED ONE WEEK PRIOR TO ANY WORK ON THIER ENTRANCE.

DANIEL ZITTA 654-1400 ROGER SCHRAGE 654-1434

ILLINOIS DEPARTMENT OF TRANSPORTATION INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES AND COMMITMENTS FAP ROUTE 793 SECTION 112BR-2

BOND COUNTY SN 003-0035

THOSE DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

	SUMMARY OF QUANTITIES	C		CONS	TRUCTION TYPE	CODE
	SUMMART OF QUANTITIE		TOTAL	X080-2A		
CODE NO	ITEM	UNIT	QUANTITIES		-	
35600717	HOT-MIX ASPHALT BASE COURSE WIDENING, 10 1/4"	SQ YD	262	262		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	244	244		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	336	336		
20200100	EARTH EXCAVATION	CU YD	350	350		
20200500	EARTH EXCAVATION (WIDENING)	CU YD	50	50	į.	
20300100	CHANNEL EXCAVATION	CU YD	690	690		
20400800	FURNISHED EXCAVATION	CU YD	4100	4100		
25000200	SEEDING, CLASS 2	ACRE	1	1		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90		
25100115	MULCH, METHOD 2	ACRE	1	1		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	300	300		
28000300	TEMPORARY DITCH CHECKS	EACH	2	2		
28000400	PERIMETER EROSION BARRIER	FOOT	820	820		
28100109	STONE RIPRAP, CLASS A5	SQ YD	3500	3500		
28200200	FILTER FABRIC	SQ YD	3500	3500		
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	<i>II</i>	. 11		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2	0.2		
40600300	AGGREGATE (PRIME COAT)	TON	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	213	213		
40600990	TEMPORARY RAMP	SQ YD	72	72		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX	TON	54	54		
42001300	"D", NTO PROTECTIVE COAT	50.40	753	753		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	13	13		
50101500 50105220	REMOVAL OF EXISTING SUPERSTRUCTURES PIPE CULVERT REMOVAL	EACH FOOT	1	1 40		
50300260	BRIDGE DECK GROOVING	SQ YD	705	705		
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	6769	6769		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	9450	9450		
50800515	BAR SPLICERS	EACH	207	207		
50901050	STEEL RAILING, TYPE SM	FOOT	413	413		
51500100	NAME PLATES	EACH	1	1		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	66	66		
542D1063 <i>542.01915</i> 63000000	PIPE CULVERTS, CLASS D, TYPE 2 18" PIPE CULVERTS, CLASS D, TYPE 3 30" STEEL PLATE BEAM GUARD RAIL, TYPE A	F00T F00T F00T	70 60 212.5	70 <i>60</i> 212.5		
	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1		

	OLIVER OF OUR AUTITIES			CONS	TRUCTION TYPE (CODE	1
	SUMMARY OF QUANTITIES		TOTAL	X080-2A			
CODE N) ITEM	UNIT	QUANTITIES	7000 ZA			
6310008	7 TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4			
6310016	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	5	5		; 	
6320031	O GUARDRAIL REMOVAL	FOOT	580	580			
6660010	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	11	11			
6700040	O ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	15	15			
6710010	0 MOBILIZATION	L SUM	1	1			
7010046	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			
7010050	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	LSUM	. 1	1	:		
7010120	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1			
7010660	TEMPORARY BRIDGE TRAFFIC SIGNALS (STATE FURNISHED CONTROLLER)	EACH	1	1			
7010670	TEMPORARY RUMBLE STRIP	EACH	6	6			
7030016	SHORT-TERM PAVEMENT MARKING	FOOT	72	72			
703002	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1919	1919			
703002	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	800	800			
703010	WORK ZONE PAVEMENT MARKING REMOVAL.	SQ FT	664	664			
704005	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	410	410	:		
704006	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	390	390			
780002	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1455	1455			
780082	O POLYUREA PAVEMENT MARKING TYPE I LINE 4"	FOOT	464	464			
781001	O RAISED REFLECTIVE PAVEMENT MARKER	EACH	2	2			
781001	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2			
781003	OO REPLACEMENT REFLECTOR	EACH	6	6	1		
782004	O GUARDRAIL MARKERS, TYPE A	EACH	12	12			
782005	BARRIER WALL MARKERS, TYPE C	EACH	6	6			
782010	TERMINAL MARKER - DIRECT APPLIED	EACH	5	5			
783001	DO PAVEMENT MARKING REMOVAL	SQ FT	554	554			
783002	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10	10			
X03253	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	82	82			
X50303	CONCRETE WEARING SURFACE, 5"	SQ YD	753	753			
X63301	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	2	2			
L			· · · · · · · · · · · · · · · · · · ·	***************************************	<u> </u>		

* SPECIALTY ITEMS

PLOT DATE = 5/1/2887 FILE NAME = orpho-jacts/ed03785/plan/pln83785a.dgr PLOT SCALE = 49.5999 '/ IM. REFERENCE = 4REF4

Rov

| CONTRACT NO. 76897
F.A.P.	SECTION	COUNTY	SHEETS	NO.
793	112BR-2	BOND	52	4
STA.	TO STA.			
FD. ROAD DIST. NO.	ILLINOIS	FED. AID	PROJECT	


ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CONC		
CONS	TRUCTION TYPE O	CODE
v000 04		
XU8U-ZA		
1		
96		
2		
2		
- ×	1 96 2	1 96 2

	SIIMMARY	OF QUANTI	TIFS		CONS	TRUCTION TYPE	CODE
CODE NO	JOIMINATO	ITEM	UNIT	TOTAL QUANTITIES	X080-2A		
JODE NO		1 (517)					
					!		
		¥					
						1	
				E.			
			:	1			
			:				
		es.					
	İ		<u>.</u>				
				1			
		* w					
				:			
	1		[1	

31 DATE = 5/1/2007 E NAME = cityprojects/ed03705\plan\plnB3785\propto 17 SCALE = 49,9999 '/ IN.






- 1 EXISTING PAVEMENT
- ② EXISTING BASE COURSE WIDENING 9"
- 3 EXISTING BINDER COURSE 2 1/2"
- 4 EXISTING SURFACE COURSE 1"
- 5 EXISTING AGGREGATE WEDGE
- 6 EXISTING GUARDRAIL
- PROPOSED HOT-MIX ASPHALT SURFACE COURSE VARIABLE DEPTH
- 8 PROPOSED HOT-MIX ASPHALT BASE COURSE WIDENING 10 1/4"
- 9 PROPOSED HOT-MIX ASPHALT SHOULDERS VARIABLE DEPTH
- (10) PROPOSED GUARDRAIL

MIXTURE CHART


MIXTURE USE	SURFACE	BASE COURSE	SHOULDERS
AC/PG	PG 64-22	PG 64-22	PG 58-22
RAP % (MAX)	10%	15%	30%
DESIGN AIR VOIDS	4.0% @ Ndes=70	4.0% @ Ndes=70	2.0% @ Ndes=30
MIX COMPOSITION			
(GRADATION MIXTURE)			
FRICTION AGG	MIXTURE "D"	MIXTURE "B"	BAM

PLAN QUANTITIES FOR HOT-MIX ASPHALT SURFACE COURSE ITEMS ARE CALCULATED USING A UNIT WEIGHT OF 112 LB/SQ YD/IN.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	TELINOIS DELANTIMENT OF TRANSPORTATION
		TYPICAL SECTIONS
		FAP ROUTE 793
	1	SECTION 112BR-2
		BOND COUNTY
	_	SN 003-0035




STA 667+50 TO STA 669+36.65 STA 671+43.36 TO STA 673+50



PROPOSED SECTION

STA 668+50 TO STA 669+36.65 STA 671+43.36 TO STA 672+25



PROPOSED SECTION

* STA 667+81 TO STA 668+50 * STA 672+61 TO STA 673+99

STA 667+50 TO STA 668+50 STA 672+25 TO STA 673+50

** STA 668+31 TO STA 668+50 STA 672+25 TO STA 672+99

DATE = *DATE*
NAME = *FILEL*
SCALE = *SCALE*
RENCE = *REF*

CONTRACT NO. 76987 TOTAL SHEET SHEETS NO.

FED.	ROAD	DIST. NO.	ILLI	NOIS	FED.	AID	PROJEC	Г
STA	١.			TO	STA.			
79	3	112BR-	-2	BOND			52	6
RTE		SECTI	ON		COUN	ΤY	SHEETS	NO.

EARTHWORK SCHEDULE

					CHANNEL	EARTH	EARTH	EARTH	EMBANKMENT	EARTHWORK
LOCAT	ION				EXCAVATION	EXCAVATION	EXCAVATION	EXCAVATION		BALANCE
							(WIDENING)	ADJUSTED FOR		WASTE (+) OR
STATIO	ON	TO	S	TATION				SHRINKAGE (25%)		SHORTAGE (-)
					CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
MAINLI	INE									
STA	666+50	TO	STA	667+00		19.5		14.6	60.3	-45.6
STA	667+00	TO	STA	667+50		46.4	3.1	37.1	172.4	-135.3
STA	667+50	TO	STA	668+00		52.4	6.9	44.4	281.2	-236.8
STA	668+00	TO	STA	668+50		59.8	6.4	49.6	417.9	-368.2
STA	668+50	TO	STA	669+00		89.2	6.7	72.0	459.5	-387.4
STA	669+00	TO	STA	669+30		67.6	4.5	54.1	257.4	-203.4
STA	669+30	TO	STA	669+37		15.1	0.7	11.9	58.3	-46.4
UNDER	STRUCTU	RE.								
STA	669+40	TO	STA	669+50	21.5				39.0	-39.0
STA	669+50	TO	STA	670+00	167.5				147.2	-147.2
STA	670+00	TO	STA	670+50	267.7				83.8	-83.8
STA	670+50	TO	STA	670+90	233.3				60.8	-60.8
MAINLI	INE									
STA	671+43	TO	STA	671+50			0.6	0.5	66.2	-65.7
STA	671+50	TO	STA	672+00			4.5	3.3	467.1	-463.8
STA	672+00	ТО	STA	672+50			3.1	2.3	415.0	-412.7
STA	672+50	TO	STA	673+00			4.3	3.2	372.6	-369.4
STA	673+00	TO	STA	673+50			6.0	4.5	291.3	-286.9
STA	673+50	TO	STA	674+00			3.2	2.4	117.4	-115.0
STA	674+00	TO	STA	674+50					2.6	-2.6
ENTRA	NCE 672+2	25 L	Τ.							
STA	0+10	TO	STA	0+20					20.0	-20.0
STA	0+20	ТО	STA	0+30					79.1	-79.1
STA	0+30	TO	STA	0+40					114.9	-114.9
STA	0+40	TO	STA	0+50					119.4	-119.4
STA	0+50	то	STA	0+60					108.3	-108.4
STA	0+60	TO	STA	0+70					72.2	-72.3
STA	0+70	TO	STA	0+80					47.6	-47.6
STA	0+80	ТО	STA	0+90					33.4	-33.4
STA	0+90	TO	STA	1+00					21.2	-21.2
STA	1+00	ТО	STA	1+18					13.7	-13.7
SUBTO	TAL				690	350	50	300	4400	-4100

EROSION CONTROL SCHEDULE

					TEMPORARY	PERIMETER
LOCATION				RIGHT	DITCH	EROSION
				OR	CHECKS	BARRIER
STATION	то	ST	ATION	LEFT	EACH	F00T
STA 667+75				LT	1	
STA 669+30)			LT	1	
STA 668+20	T0	STA	669+35	RT		157
STA 671+45	ТО	STA	673+70	RT		290
STA 671+50	ΤO	STA	672+15	LT		143
STA 672+35	TO	STA	674+00	LT		230
TOTAL					2	820

TREE REMOVAL SCHEDULE

LOCATION		RIGHT OR	REMOVAL (6-15 UNITS DIA)	TREE REMOVAL (OVER 15 UNITS DIA)
STATION	OFFSET	LEFT	UNITS	UNITS
667+82.94	27	LT		30
668+26.99	23	LT	10	
668+78.25	29	LT	10	
668+93.27	27	LT	10	
670+80.23	86	LT		. 24
670+84.02	77	LT		. 48
669+33.24	48	RT	6	MANUSCHALL MANUSCHALL AND
669+35.24	43	RT	12	
669+45.20	57	RT	12	
669+51.05	42	RT	10	
669+53.39	40	RT	8	
669+57.23	52	RT	10	
669+57.30	49	RT	6	
669+59.82	39	RT		16
669+60.25	45	RT	8	
669+63.14	33	RT	6	
670+05.65	40	RT		24
670+08.23	47	RT	6	
670+14.37	41	RT	10	
670+28.91	43	RT	8	
670+34.07	41	RT	6	
670+35.63	45	RT	6	
670+40.57	59	RT	6	
670+41.88	34	RT	8	
670+43.15	42	RT	8	
670+60.92	37	RT	10	
670+74.76	44	RT	8	
607+88.47	55	RT		36
671+38.13	48	RT		30
671+39.69	47	RT		24
671+44.26	47	RT		16
671+50.82	.47	RT	8	
671+54.42	51	RT		16
671+58.08	48	RT		18
671+62.42	55	RT		18
671+88.84	52	RT		18
671+91.41	50	RT	10	
671+94.41	53	RT	-	18
672+73.13	32	RT	14	
672+87.15	35	RT	12	
673+05.73	30	RT	10	
673+15.64	43	RT	6	
TOTA			244	336

		····			
REVISIONS	-	TI I TMOTS	REDADTMENT	ΛE	TRANSPORTATION
NAME	DATE	ILLINOIS	DEFARIMENT	UF	I LWINSL OV LY LTON
		1			

	SCHEDULE OF QUANTITIES
	FAP ROUTE 793

FAP ROUTE 793 SECTION 112BR-2 BOND COUNTY SN 003-0035

PLOT DATE = 4/38/2887 FILE NAME = c:\pro,ects\ed03785\plan\pln83785a.dc PLOT 5CALE = 58.0808 / IN. REFERENCE = sREF\$

PAVEMENT MARKING SCHEDULE

		PAV	EMENT MARKING	REMOVAL		THERMO	PLASTIC PAVEM	ENT MARKI	NG	POLYUREA P	AVEMENT N	MARKING	TEMPORARY	SHORT-TERM	WORK ZONE	RAISED REFLECTIVE	REPLACEMENT	RAISED REFLECTIVE	RAISED REFLECTIVE
LOCATION		SOLID	SKIP-DASH	EDGE	LINE	SOLID	SKIP-DASH	EDGE	LINE	SKIP-DASH	EDGE	LINE	PAVEMENT	PAVEMENT	PAVEMENT	PAVEMENT MARKER	REFLECTOR	PAVEMENT MARKER	PAVEMENT MARKER
		CENTERLINE	CENTERLINE	4" W	VHITE	CENTERLINE	CENTERLINE	4" V	VHITE	CENTERLINE	4" ¥	VHITE	MARKING	MARKING	MARKING	REMOVAL			(BRIDGE)
		4" YELLOW	4" YELLOW	LT	RT	4" YELLOW	4" YELLOW	LT	RT	4" YELLOW	LT	RT.	LINE - 4"		REMOVAL		2-WAY AMBER	2-WAY AMBER	2-WAY AMBER
STATION TO STATI	N	SQ FT	SQ FT	SQ FT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	EACH	EACH	EACH	EACH
STA 666+47.00 TO STA 6	69+36.65		23	96.5	96.5		80	289.7	289.7	·			659	28	229	4	3	1	
STA 669+36.65 TO STA 6	71+43.36			69.0						50	207	207	464	16	160	2			2
STA 671+43.36 TO STA 6	74+33.00	49	27	96.5	96.5	146	70	289.8	289.8				796	28	275	4	3	1	
SUB-TOTAL		49	50	262	193	146	150	579.5	579.5	50	207	207							
TOTAL			554				1455				464		1919	72	664	10	6	2	2

RESURFACING SCHEDULE

					BITUMINOUS	AGGREGATE	HOT-MIX ASPHALT	HOT-MIX ASPHALT	HOT-MIX ASPHALT
LOCA	TION				MATERIALS	(PRIME COAT)	SURFACE COURSE	SURFACE REMOVAL -	SHOULDERS
					(PRIME COAT)	-		BUTT JOINT	
STAT	ION	то	STAT	TION	TON	TON	TON	SQ YD	TON
STA	668+50.0	ТО	STA	668+90.0	0.05	0.24	10	106.5	2.3
STA	668 +9 0.0	то	STA	669+36.7	0.05	0.27	18		4.4
STA	671+43.4	ТО	STA	671+85.0	0.05	0.25	16		4.0
STA	671+85.0	то	STA	672+25.0	0.05	0.24	. 10	106.5	2.3
TOTA	L				0.2	1	54	213	13

STAGING SCHEDULE

LOCATION	HOT-MIX ASPHALT	TRAFFIC BARRIER	TEMPORARY	RELOCATE	TEMPORARY	TEMPORARY	IMPACT	IMPACT
	BASE COURSE	TERMINAL, TYPE 1	CONCRETE	TEMPORARY	RUMBLE	PAVEMENT	ATTENUATOR.	ATTENUATOR,
	WIDENING, 10 1/4"	SPECIAL (TANG)	BARRIER	CONCRETE	STRIP	MARKING	TEMPORARY	RELOCATE
				BARRIER		LINE - 6"	(NON-REDIRECTIVE)	(NON-REDIRECTIVE
	SQ YD	F00T	FOOT	FOOT	EACH	FOOT	EACH	EACH
STAGE I	262	2	390		6	390	2	
STAGE II			20	390	-	410		2
TOTAL	262	2 *	410	390	6	800	2	2

* NOT A TOTAL QUANITITY - SEE GUARDRAIL SCHEDULE.

GUARDRAIL SCHEDULE

	GUARDRAIL	STEEL PLATE	TRAFFIC BARRIER	REMOVE AND RE-ERECT	TRAFFIC	TRAFFIC	GUARDRAIL	BARRIER WALL	TERMINAL
LOCATION	REMOVAL	BEAM	TERMINAL, TYPE 1,	TRAFFIC BARRIER	BARRIER	BARRIER	MARKERS,	MARKERS,	MARKER -
		GUARDRAIL,	SPC (TANGENT)	TERMINAL, TYPE 1	TERMINAL,	TERMINAL,	TYPE A	TYPE C	DIRECT
		TYPE A			TYPE 6A	TYPE 2			APPLIED
	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH
EASTBOUND							5	3	
WESTBOUND							8	3 .	
NW QUADRANT	140	62.5		1	1				1
NE QUADRANT	190	75	1	1	1	1			2
SW QUADRANT	100	12.5	1		1				1
SE QUADRANT	150	62.5	1		1				1
TOTAL	580	212.5	3 *	2	4	1	13	. 6	5

• NOT A TOTAL QUANITITY - SEE STAGING SCHEDULE.

TEMPORARY RAMP SCHEDULE


LOCA	TION	WIDTH	LENGTH	TEMPORARY RAMP
		FOOT	FOOT	SQ YD
STA	669+36.65	32	10	36
STA	671+43.36	32	10	36
TOTA	L			72


ROW MARKERS SCHEDULE

				FURNISHING &
LOCA	TION			ERECTING
		RIGHT-OF-WAY		
		MARKERS		
STAT	ION	OFFSET	SIDE	EACH
STA	665+75.07	49.29	LT	1
STA	667+50.04	50.76	RT	1
STA	668+00.08	84.23	LT	1
STA	668+50.04	60.79	RT	1
STA	669+25.78	84.19	LT	1
STA	670+77.74	118.05	LT	1
STA	671+65.07	59.12	LT	1
STA	673+50.04	60.94	RT	1
STA	673+50.07	59.09	LT	1
STA	674+50.04	40.97	RT	. 1
STA	674+50.07	39.03	LT	1
TOTAL		1		11

REVISIONS NAME	DATE	ILLINOIS DEPARTMENT OF TRANSPORTATION
		SCHEDULE OF QUANTITIES

FAP ROUTE 793 SECTION 112BR-2 BOND COUNTY SN 003-0035






MAG NAIL IN END OF GUARDRAIL POST € IL 143 137.63 MAG NAIL IN END OF GUARDRAIL POST

51.39' ¢ IL 143 EXPANSION EXPANSION JOINT JOINT SN 003-0035

TIE POINT MAG NAIL STA 663+80

TIE POINT MAG NAIL STA 667+00

TIE POINT MAG NAIL STA 670+40.15



CHISELED "X" ON EAST END MAG NAIL IN OF HEADWALL POWER POLE ¢ IL 143 CHISELED "X" ON CENTER OF HEADWALL

TIE POINT MAG NAIL STA 674+00

TIE POINT MAG NAIL STA 676+69.07


TEMPORARY BENCHMARKS

TBM 13 - CHISELED SQUARE ON TOP OF CONCRETE HEADWALL ON NW CORNER OF IL RT 127 AND IL RT 143. ELEV = 486.687


CHISELED SQUARE ON TOP CENTER OF CONCRETE HEADWALL OF BOX CULVERT WITH GUARDRAIL ON THE NORTH SIDE OF IL RT 143, 1.2 MILES WEST OF IL RT 127. ELEV = 473.183


TBM 15 - CHISELED SQUARE ON TOP OF NW CONCRETE WINGWALL FOR BRIDGE SN 003-0035 OVER BEAVER CREEK.


NOTE: ALL TIES PULLED DIRECT



TIE POINTS AND BENCHMARKS FAP ROUTE 793 SECTION 112BR-2 BOND COUNTY SN 003-0035








LEGEND

IMPACT ATTENUATOR

TEMPORARY CONCRETE BARRIER

BARRELS OR BARRICADES WITH STEADY BURNING LIGHT

TYPE III BARRICADE



SAND MODULE IMPACT ATTENUATOR LAYOUT (IF OPTION USED)




CONTRACT NO. 76897 COUNTY TOTAL SHEET NO.

SECTION

STA. 665+50

793 112BR-2 BOND 52 12

TO STA, 671+50 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT



SEQUENCE OF CONSTRUCTION - STAGE I:

EARTHWORK NECESSARY FOR GUARDRAIL PLACEMENT MUST BE COMPLETED PRIOR TO STAGE I.

PLACE "HOT-MIX ASPHALT BASE COURSE WIDENING 10 1/4 INCH" AND "TBT, TYPE I SPEC (TANG)" ON BOTH ENDS OF THE STRUCTURE AS A PRE-STAGE TO STAGE I. BOTH TBT, TYPE I SPECIALS WILL BE REMOVED AND RE-ERECTED IN THEIR FINAL LOCATION DURING STAGE II CONSTRUCTION.

PLACE STOP BARS AS SHOWN ON PLANS.

REMOVE CONFLICTING PAVEMENT MARKINGS.

PLACE 390 FT TEMPORARY CONCRETE BARRIER, AND 2 EACH IMPACT ATTENUATORS, TEMPORARY, (NON-REDIRECTIVE).

SEE STANDARD 701321 FOR DETAILS NOT SHOWN ON PLANS.


PERFORM ALL NECESSARY BRIDGE WORK IN STAGE I WORK ZONE.

REMOVE EXISTING GUARDRAIL ON SOUTH SIDE AND REPLACE WITH PROPOSED STEEL PLATE BEAM GUARDRAIL, TYPE A, TBT, TYPE 6A, AND TBT,TYPE 1 (SPECIAL) TANGENT IN SW AND SE QUADRANTS.



ILLINOIS DEPARTMENT OF TRANSPORTATION		REVISIONS	DTATION
TELINOIS DEPARTMENT OF TRANSPORTATION	DATE	NAME	MINITON
STAGE I CONSTRUCTION			ΩN
OTAGE 1 CONSTRUCTION			011
FAP ROUTE 793			
SECTION 112BR-2			
SECTION TIZER-Z			
BOND COUNTY			
SN 003-0035			
011 000 0000	L		

. DATE = 6/12/2007 NAME = c:\projects\ed03 SCALE = 20.0000 '/ IN. RENCE = \$REF\$



LEGEND

IMPACT ATTENUATOR


TEMPORARY CONCRETE BARRIER

\rightarrow

BARRELS OR BARRICADES WITH STEADY BURNING LIGHT

E


TYPE III BARRICADE



SAND MODULE IMPACT ATTENUATOR LAYOUT (IF OPTION USED)



N (8)



SEQUENCE OF CONSTRUCTION - STAGE II:

PLACE 10' TEMPORARY RAMP ON BOTH ENDS OF STRUCTURE.

RELOCATE 390 FT AND PLACE ADDITIONAL 20 FT TEMPORARY CONCRETE BARRIER. RELOCATE 2 EACH IMPACT ATTENUATORS.

SEE STANDARD 701321 FOR DETAILS NOT SHOWN ON PLANS.


PERFORM ALL NECESSARY BRIDGE WORK IN STAGE II WORK ZONE.

REMOVE EXISTING GUARDRAIL ON NORTH SIDE.

CONSTRUCT ENTRANCE AT STA 672+25 LT.

IN NW QUADRANT PLACE PROPOSED TBT, TYPE 6A, STEEL PLATE BEAM GUARDRAIL, TYPE A, AND REMOVE & RE-ERECT TBT,TYPE 1 (SPECIAL) TANGENT.

IN NE QUADRANT, PLACE TBT, TYPE 6A, STEEL PLATE BEAM GUARDRAIL, TYPE A, TBT,TYPE 2 WEST OF ENTRANCE AND TBT,TYPE 1 (SPECIAL) TANGENT, STEEL PLATE BEAM GUARDRAIL, TYPE A, AND REMOVE & RE-ERECT TBT,TYPE 1 (SPECIAL) TANGENT EAST OF ENTRANCE.




REVISIO	NS	ī
NAME	DATE	1
	<u> </u>	
		l .

ILLINOIS DEPARTMENT OF TRANSPORTATION STAGE II CONSTRUCTION

FAP ROUTE 793 SECTION 112BR-2 BOND COUNTY SN 003-0035

LOT DATE = 6/12/2007 TILE NAME = chro.jects/sed83705/plen/stg83705s LOT SCALE = 20,0008 / IN. FEFRENCE = 8FEF 8



THE FOLLOWING PLAN IS ESTABLISHED AND INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM SEWER WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE UNDER NPDES.

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE CONSTRUCTION SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONABLE AMOUNT OF TIME.

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES. TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS.

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIME FRAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEER, THEREFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS, WHICH ARE NOT INCLUDED IN THIS PLAN, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN IN STANDARD 280001 OF THE PLANS.

SITE DESCRIPTION DESCRIPTION OF CONSTRUCTION ACTIVITY:

- 1. THE PROJECT CONSISTS OF SUPERSTRUCTURE REPLACEMENT OF THE STRUCTURE CARRYING IL ROUTE 143 OVER BEAVER CREEK
- 2. CONSTRUCTION WILL ALSO INCLUDE WIDENING FOR STAGE CONSTRUCTION, GUARDRAIL. EARTH EXCAVATION AND EMBANKMENT,

DESCRIPTION OF INTENDED SEQUENCE FOR MAJOR CONSTRUCTION ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE:

- TREE REMOVAL WITHIN CONTRUCTION LIMITS DUE TO PROPOSED DITCHES. TREES TO REMAIN WILL BE PROTECTED AGAINST DAMAGE.
- 2. EXCAVATION AND EMBANKMENT TO GRADE OUT FOR PROPOSED GUARDRAIL AND DITCHES.
- 3. CHANNEL EXCAVATION AND RIPRAP PLACEMENT.
- PLACEMENT, MAINTENANCE, REMOVAL AND PROPER CLEAN-UP OF TEMPORARY EROSION CONTROL, SUCH AS PERMITER EROSION BARRIER, TEMPORARY DITCH CHECKS, TEMPORARY SEEDING, ETC.
- 5. FINAL GRADING, PAVING, AND OTHER MISCELLANEOUS ITEMS.
- 6. PLACEMENT OF PERMANENT EROSION CONTROL, SUCH AS RIPRAP, EROSION CONTROL BLANKET, SEEDING, ETC.

TOTAL SHEET SHEETS NO. COUNTY SECTION

793 112BR-2 BOND 52 16 TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

AREA OF CONSTRUCTION SITE:

THE TOTAL AREA OF THE CONSTRUCTION SITE IS ESTIMATED TO BE 1.86 ACRES OF WHICH 1.48 ACRES WILL BE DISTURBED BY EXCAVATION, GRADING, AND OTHER ACTIVITIES.

OTHER REPORTS, STUDIES AND PLANS WHICH AID IN THE DEVELOPMENT OF THE STORM WATER POLLUTION PREVENTION PLAN AS REFERENCED DOCUMENTS:

- 1. INFORMATION OF THE SOILS AND TERRAIN WITHIN THE SITE WAS OBTAINED FROM TOPOGRAPHIC SURVEYS AND SOIL BORINGS THAT WERE UTILIZED FOR THE DEVELOPMENT OF THE PROPOSED TEMPORARY EROSION CONTROL SYSTEMS.
- 2. PROJECT PLAN DOCUMENTS, STANDARD SPECIFICATIONS, AND PLAN DRAWINGS INDICATING DRAINAGE PATTERNS AND APPROXIMATE SLOPES ANTICIPITATED AFTER GRADING ACTIVITIES WERE UTILIZED FOR THE PROPOSED PLACEMENT OF THE TEMPORARY EROSION CONTROL SYSTEMS.

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE:

BEAVER CREEK

CONTROLS * EROSION CONTROLS AND SEDIMENT CONTROL

DESCRIPTION OF STABILIZATION PRACTICES AT THE BEGINNING OF CONSTRUCTIONS

- 1. THE DRAWINGS, SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE: TEMPORARY SEEDING, PERMANENT SEEDING, MULCHING, PROTECTION OF TREES. PRESERVATION OF MATURE VEGETATION. AND OTHER APPROPRIATE MEASURES AS DIRECTED BY THE ENGINEER. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED.
- (a.) AREAS OF EXISTING VEGETATION (WOOD AND GRASSLANDS) OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE IDENTIFIED BY THE ENGINEER FOR PRESERVING AND SHALL BE PROTECTED FROM CONSTRUCTION ACTIVITIES.
- (b.) DEAD, DISEASED, OR UNSUITABLE VEGETATION WITHIN THE SITE SHALL BE REMOVED AS DIRECTED BY THE ENGINEER,
- (c.) AS SOON AS REASONABLE ACCESS IS AVAILABLE TO ALL LOCATIONS WHERE WATER DRAINS AWAY FROM THE PROJECT, TEMPORARY DITCH CHECKS, INLET AND PIPE PROTECTION, AND PERIMETER EROSION BARRIER SHALL BE INSTALLED AS CALLED OUT IN THIS PLAN AND DIRECTED BY THE ENGINEER.
- (d.) BARE AND SPARSELY VEGETATED GROUND IN HIGHLY ERODIBLE AREAS AS DETERMINED BY THE ENGINEER SHALL BE TEMPORARILY SEEDED AT THE BEGINNING OF CONSTRUCTION WHERE NO CONSTRUCTION ACTIVITIES ARE EXPECTED
- (e.) IMMEDIATELY AFTER TREE REMOVAL IS COMPLETED, AREAS WHICH ARE HIGHLY ERODIBLE AS DETERMINED BY THE ENGINEER, SHALL BE TEMPORARILY SEEDED WHEN NO CONSTRUCTION ACTIVITIES ARE EXPECTED WITHIN SEVEN DAYS.
- (f.) AT LOCATIONS WHERE A SIGNIFICANT AMOUNT OF WATER DRAINS INTO THE CONSTRUCTION ZONE FROM OUTSIDE AREAS (ADJACENT LANDOWNERS), TEMPORARY DITCH CHECKS WILL BE UTILIZED TO LOCALLY DIVERT WATER, REDUCE FLOW RATES, AND COLLECT OUTSIDE SILTATION INSIDE THE RIGHT-OF-WAY LINE.
- ESTABLISHMENT OF THESE TEMPORARY EROSION CONTROL MEASURES WILL HAVE ADDITIONAL BENEFITS TO THE PROJECT. DESIRABLE GRASS SEED WILL BECOME ESTABLISHED IN THESE AREAS AND WILL SPREAD SEEDS ONTO THE CONSTRUCTION SITE UNTIL PERMANENT SEEDING/MOWING AND OVERSEEDING CAN BE COMPLETED.

THIS PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NPDES PERMIT NUMBER ILR10. ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES.

I CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT QUALIFIED PERSONNEL PROPERLY GATHERED AND EVALUATED THE INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION. THE INFORMATION SUBMITTED IS. TO THE BEST OF MY KNOWLEDGE AND BELLEE, TRUE, ACCURATE AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT

Man Jame 5/9/07
DEPUTY DIRECTOR OF HIGHWAYS DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION STORM WATER POLLUTION PREVENTION PLAN

> FAP ROUTE 793 SECTION 112BR-2 BOND COUNTY SN 003-0035

DATE NAME SCALE RENCE

DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION:

- DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE
 PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIRECTED BY THE ENGINEER), PARKING OF VEHICLES OR CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION RELATED ACTIVITIES.
- (a.) WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSION.
- (b.) EARTH STOCKPILES SHALL BE TEMPORARILY SEEDED IF THEY ARE TO REMAIN UNUSED FOR MORE THAN FOURTEEN DAYS.
- (c.) AS CONSTRUCTION PROCEEDS, THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER:
- I. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS.
- II. TEMPORARILY SEED ERODABLE BARE EARTH ON A WEEKLY BASIS TO MINIMIZE THE AMOUNT OF ERODABLE SURFACE AREA WITHIN THE CONTRACT LIMITS.
- III. CONSTRUCT ROADSIDE DITCHES AND PROVIDE TEMPORARY EROSION CONTROL SYSTEMS.
- IV. TEMPORARILY DIVERT WATER AROUND PROPOSED CULVERT LOCATIONS.
- V. BUILD NECESSARY EMBANKMENT AT CULVERT LOCATIONS AND THEN EXCAVATE AND PLACE CULVERT.
- VI. CONTINUE BUILDING UP THE EMBANKMENT TO THE PROPOSED GRADE WHILE AT THE SAME TIME, PLACING PERMANENT CONTROL SUCH AS RIPRAP DITCH LINING AND CONDUCTING FINAL SHAPING TO THE SLOPES.
- (d.) EXCAVATED AREAS AND EMBANKMENT SHALL BE PERMANENTLY SEEDED IMMEDIATELY AFTER FINAL GRADING. IF NOT, THEY SHALL BE TEMPORARILY SEEDED IF NO CONSTRUCTION ACTIVITY IN THE AREA IS PLANNED FOR 7 DAYS.
- (e.) CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS. ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OF OTHER POLLUTANT IN ACCORDANCE WITH EPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE.
- (f.) THE RESIDENT ENGINEER SHALL INSPECT THE PROJECT DAILY DURING CONSTRUCTION ACTIVITIES. INSPECTION SHALL ALSO BE DONE WEEKLY AND AFTER RAINS OF 1/2 INCH OR GREATER OR EQUIVALENT SNOWFALL AND DURING THE WINTER SHUTDOWN PERIOD. THE PROJECT SHALL ADDITIONALLY BE INSPECTED BY THE CONSTRUCTION FIELD ENGINEER ON A BI-WEEKLY BASIS TO DETERMINE THAT EROSION CONTROL EFFORTS ARE IN PLACE AND EFFECTIVE AND IF OTHER EROSION CONTROL WORK IS NECESSARY.
- (g) SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON THE SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE INCLUDED IN THE UNIT BID PRICE FOR EARTH EXCAVATION.
- (h) THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCLUDED IN THE UNIT BID PRICE FOR TEMPORARY EROSION CONTROL SYSTEM.

			CONTRA	ACT NO.	76987
F.A.P. RTE.	SECTIO	N	COUNTY	TOTAL SHEETS	SHEET NO.
793	112BR-	2	BOND	52	17
STA.		TO	STA.		
FED. ROA	D DIST. NO.	ILLINOIS	FED. AIC	PROJECT	

DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING:

- 1. TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS SEEDED AND ESTABLISHED.
- 2. ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RESEEDED.

MAINTENANCE AFTER CONSTRUCTION:

1. CONSTRUCTION IS COMPLETE AFTER ACCEPTANCE BY I.D.O.T. FINAL INSPECTION. MAINTENANCE UP TO THIS DATE WILL BE BY THE CONTRACTOR.

MISCELLANEOUS:

- 1. ALL EROSION CONTROL PRODUCTS FURNISHED SHALL BE SPECIFICALLY RECOMMENDED BY THE MANUFACTURER FOR THE USE SPECIFIED IN THE EROSION CONTROL PLAN. PRIOR TO THE APPROVAL AND USE OF THE PRODUCT, THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A NOTARIZED CERTIFICATION BY THE PRODUCER STATING THE INTENDED USE OF THE PRODUCT AND THAT THE PHYSICAL PROPERTIES REQUIRED FOR THIS APPLICATION ARE MET OR EXCEEDED. THE CONTRACTOR SHALL PROVIDE MANUFACTURER INSTALLATION PROCEDURES TO FACILITATE THE ENGINEER IN CONSTRUCTION INSPECTION.
- 2. STRAW BALES, HAY BALES, PERIMETER EROSION BARRIER AND SILT FENCES WILL NOT BE PERMITTED FOR TEMPORARY OR PERMANENT DITCH CHECKS. DITCH CHECKS SHALL BE COMPOSED OF AGGREGATE, SILT PANELS, ROLLED EXCELSIOR, URETHANE/GEOTEXTILE (SILT WEDGES), EARTH MEDIAN AND/OR OTHER MATERIAL APPROVED BY THE EROSION AND
- 3. TEMPORARY DITCH CHECKS SHALL BE LOCATED AT EVERY 1.5 FT. FALL/RISE IN DITCH GRADE.
- 4. TEMPORARY DITCH CHECKS, AGGREGATE USE GRADING NO. 3, REMOVE AT END OF CONSTRUCTION.
- 5. CONSTRUCT PERIMETER EROSION CONTROL AT BEGINNING OF CONSTRUCTION. REMOVE AT END OF CONSTRUCTION.
- 6. TEMPORARY EROSION CONTROL SEEDING SHALL BE APPLIED AT A RATE OF 100 LBS/ACRES.
- 7. TEMPORARY SEEDING SHALL BE COMPLETED ON A WEEKLY BASIS ON EXPOSED GROUND AND SHALL BE IN ACCORDANCE WITH SECTION 280 OF THE STANDARD SPECIFICATIONS. THIS WORK SHALL BE PAID FOR AS "TEMPORARY EROSION CONTROL SEEDING", WHICH WILL INCLUDE MULCH. IF NEEDED. FOR CALCULATION PURPOSES, THREE APPLICATIONS OF TEMPORARY SEEDING WAS ASSUMED.
- 8. EARTH STOCKPILES SHALL BE TEMPORARILY SEEDED IF THEY ARE TO REMAIN UNUSED FOR MORE THAN FOURTEEN DAYS.
- 9. FINAL SEEDING SHALL BE PERFORMED AS SOON AS POSSIBLE WITH CLASS 2 SEEDING.

LEGEND

 \oplus

TEMPORARY DITCH CHECK- ROLLED EXCELSIOR, SILT WEDGES/PANELS 1000 TEMPORARY DITCH CHECK- AGGREGATE


EROSION CONTROL BLANKET

PERIMETER EROSION BARRIER- SILT FILTER FENCE OR OTHER AS APPROVED BY THE ENGINEER


> INLET AND PIPE PROTECTION- STRAW BALES, FILTER FABRIC, AGGREGATES

ILLINOIS DEPARTMENT OF TRANSPORTATION STORM WATER POLLUTION PREVENTION PLAN

> FAP ROUTE 793 SECTION 112BR-2 BOND COUNTY SN 003-0035




PLOT DATE = 6.712/2807 FILE NAWE = cathrogests/ad03705/plon/pln03705s PLOT SCAME = 20.8000 / IN. REFERENCE = #REF®




FAP ROUTE SECTION 793 112BR-2 BOND STA N/A TO STA. N/A CONTRACT NO.: 76897


MONUMENT RECORD SECTION CORNER CONTROL TIES




FOUND STATE OF ILL. SURVEY MARKER 22 27 APPROXIMATE ¢ ILL. 143 SET
I.P. & CAP
'BACON" SET I.P. & CAP "BACON"



PROPOSED CENTERLINE OF CONSTRUCTION CONTROL TIES



BEGIN OF PROJECT P.O.T. STA. 664+00.00 PROPOSED ¢ OF CONSTRUCTION FAP ROUTE 793 / IL RT. 143 SET MAGNAIL



END OF PROJECT P.O.T. STA. 676+69.07 PROPOSED ¢ OF CONSTRUCTION FAP ROUTE 793 / IL RT. 143 SET MAGNAIL

STATE OF KENTUCKY)) SS COUNTY OF MCCRACKEN

I, RONALD S. BACON, AN ILLINOIS PROFESSIONAL LAND SURVEY CERTIFY THAT I HAVE SURVEYED THE PLAT OF HIGHWAY SHOWN HEREON AND THAT THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT ILLINOIS MINIMUM STANDARDS FOR A BOUNDARY SURVEY FOR THE PROPOSED PARCELS TO BE AAQUIRED BY THE STATE OF ILLINOIS, DEPARTMENT OF TRANSPORTATION

DATED JOE 17, ZUZ RONALD S. BACON, PLS NO. 035-003586

LICENSE EXPIRATION DATE: 11/30/2008



500 South 17th Street Paducah, Kentucky 42003 Phone: (270) 443-1995 Fax: (270) 443-1904

REGISTRATION NO. 184-003258

ILLINOIS DEPARTMENT OF TRANSPORTATION PLAT OF HIGHWAYS

FAP ROUTE 793 (IL ROUTE 143) SECTION 112BR-2 BOND COUNTY JOB NO. R-98-007-06


TIE SHEET

ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS/DISTRICT 8 1102 EASTPORT PLAZA DRIVE


COMPLETION DATE OF FIELD WORK PERFORMED LAND SURVEY: 8/29/06

RIGHT OF WAY STAKING: 11/1/06

SPACE RESERVED FOR RECORDING OFFICER







EDGE OF PAVEMENT


EDGE OF SHOULDER

NOTES:


- 1. CONSTRUCT ACCORDING TO STANDARD 631011 FOR TRAFFIC BARRIER TERMINAL TYPE 2, EXCEPT DELETE END SECTION AND SPLICE INTO RADIUS GUARDRAIL.
- 2. STEEL PLATE BEAM GUARDRAIL TYPE A, TYPE B, OR TRAFFIC BARRIER TERMINAL AS SPECIFIED.
- FOR THE 8'-6" RADIUS, THE RAIL IS NOT BOLTED TO THE POST LOCATED AT THE MIDPOINT OF THE CURVE.

PLAN VIEW SHORT RADIUS GUARDRAIL DETAIL

NOT TO SCALE



INSTALLATION CHARACTERISTICS PER DESIGN RADIUS							
R	NO. OF WOOD POSTS	Х	Y				
8'-6''	5 (NOTE 3)	25′	15′				
17'-0"	6	30′	15′				
25′-6″	8	40′	20′				
35′-0"	11	50′	20′				



EXISTING PAVEMENT

BUTT JOINT DETAIL

WIDTH, AS REQUIRED

DETAIL

DETECTOR LOOP INSTALLED IN TRENCH

INSTALLATION IS TO BE DONE IN CONFORMANCE WITH THE REQUIREMENTS OF THE PLANS AND SECTION 886 OF THE STANDARD SPECIFICATIONS WITH THE FOLLOWING EXCEPTIONS:

2. THIS WORK SHALL NOT BE PAID FOR SEPERATELY BUT SHALL BE INCLUDED IN THE COST OF TEMPORARY BRIDGE TRAFFIC SIGNALS - 1 EACH.

1. SLOTS ARE TO BE TRENCHED INSTEAD OF SAWED.

EXISTING AGGREGATE SURFACE

EXISTING AGGREGATE SURFACE, TYPE B

DETECTOR LOOP CONDUCTORS
IN PLASTIC TUBING

6" DEEP SAND BACKFILL

NOTE: BUTT JOINT WIDTH SHALL INCLUDE SHOULDERS.

REVISIONS
NAME DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

MISCELLANEOUS DETAILS

FAP ROUTE 793 SECTION 112BR-2 BOND COUNTY SN 003-0035

PLOT DATE = 5/1/2007 FILE NAME = c:\projects\edg3705\plan\pln8378 PLOT SCALE = 50.0000 // IN. .

 CONTRACT
 NO.
 76987


 COUNTY
 TOTAL SHEET NO.

 BOND
 52
 25
 F.A.P. RTE. 793 SECTION 112BR-2 TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

PIPE CULVERT D = PIPE DIAMETER

ENTRANCE CULVERT BEVELED END SECTION DETAIL


THE BEVELED END PORTION SHALL BE INCLUDED IN THE UNIT PRICE PER FOOT FOR THE PIPE CULVERT




PROPOSED ENTRANCE DETAIL STA 672+25 LT


> ILLINOIS DEPARTMENT OF TRANSPORTATION MISCELLANEOUS DETAILS FAP ROUTE 793

SECTION 112BR-2 BOND COUNTY SN 003-0035







END VIEW
(WITHOUT WIRE ROPE LOOPS)




ALTERNATE CONNECTING PINS



ELEVATION




PLAN



TYPICAL INSTALLATION WITH STYROFOAM PADS

TEMPORARY CONCRETE BARRIER
NJ SHAPE DESIGN



DOWEL BARS

NOTES:
NEW JERSEY (NJ) SHAPE BARRIER SHALL NOT
BE PRODUCED AFTER OCTOBER 1, 2002.
HOWEVER, NEW JERSEY SHAPE BARRIER
PRODUCED PRIOR TO OCTOBER 1, 2002 MAY
BE USED UNTIL JANUARY 1, 2008.

THE NJ SHAPE BARRIER UNITS SHALL BE SEATED ON STYROFOAM PADS EXCEPT WHEN THEY ARE ANCHORED.

NJ SHAPE DOWEL BARS SHALL BE EMBEDDED
AT LEAST 8 INCHES INTO THE PAVEMENT, AND
SHALL NOT PROJECT ABOVE THE OUTER SURFACE
OF THE BARRIER. THE CONNECTION, MAY BE
NJ SHAPE PIN AND LOOP CONNECTION, MAY BE
EITHER A PLAIN 7/8 INCH DIAMETER OR A DEFORMED
NO. 7 BAR MEETING THE REQUIREMENTS OF
ARTICLE 1006.10(b) EXCEPT GRADE 60 BARS
SHALL BE USED.

ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SHOWN.


REVISIONS	TII	
NAME	DATE	1

ILLINOIS DEPARTMENT OF TRANSPORTATION


MISCELLANEOUS DETAILS

FAP ROUTE 793 SECTION 112BR-2


BOND COUNTY SN 003-0035




BEARING PLATE K





<u>PLAN</u>




WOOD POST









SEE STANDARD 630001 FOR DETAILS OF GUARDRAIL NOT SHOWN.


GENERAL NOTES


THE BEARING PLATE K SHALL BE HELD IN POSITION BY TWO (2) EIGHT PENNY NAILS DRIVEN INTO THE POST AND BENT OVER THE TOP OF THE PLATE.

ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SHOWN.

REVISIONS	ILLINOIS DEPARTMENT OF TRANSPORTATION					
NAME DATE	LECTION DEL ANTIMENT OF TRANSPORTATION					
	_					
	MISCELLANEOUS DETAILS					
	FAP ROUTE 793					
····	SECTION 112BR-2					
	BOND COUNTY					
	→ SN 003-0035					
· · · · · · · · · · · · · · · · · · ·						

TRAFFIC BARRIER TERMINAL, TYPE 2






E = ci\projects\ed03705\plan\pln03705a LE = 20.0000 '/ IN,

Bench Mark: Right of way marker 41.58 ft. Right of Sta. 669+48.55, Elevation 464.15. Existing Structure: S.N. 003-0035 was rebuilt in 1978 as FA Route 793, Section 112-BR-1 at Sta. 670+40. The structure consists of 4 spans of PPC deck beams on pile bent abutments and piers. The bk. to bk. of abutments measures 206'-8'2" while the out to out width measures 33'-0". Bridge superstructure shall be removed and replaced with new beams and reinforced concrete wearing surface. Partial road closure with a signalized one lane crossing will

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

TOTAL SHEETS SHEET NO. SHEET NO. 1 F.A.P. RTE. 793 BOND 52 29 *15* **SHEETS**

Contract #76897



PROFILE GRADE (along € roadway)

be used during construction. No salvage of existing deck beams.

> LOADING HS20-44 No allowance for future wearing surface.

DESIGN SPECIFICATIONS

2002 AASHTO $f_c' = 5,000 \text{ psi}$

 $f'_c = 5,000$ psi (concrete wearing surface)

 $f_{h}^{2} = 3,500 \text{ psi (concrete structures)}$ = 60,000 psi (reinforcement)

= 36,000 psi (structural steel)

PRECAST PRESTRESSED UNITS

féi = 4,000 psi

 $f_s'=270,000$ psi (l_2 " ϕ low lax. strands) $f_{sl}=201,960$ psi (l_2 " ϕ low lax. strands)

STATE OF ILLINOIS FAP ROUTE 793 - SEC 112BR-2 LOADING HS20 STR. NO. 003-0035

> NAME PLATE See Std. 515001





GENERAL PLAN & ELEVATION IL ROUTE 143 OVER BEAVER CREEK F.A.P. ROUTE 793 - SECTION 112BR-2 BOND COUNTY STA. 670+40 STRUCTURE NO. 003-0035

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

Contract #76897

GENERAL NOTES

Plan dimensions and details relative to existing plans are subject to routine variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished based upon the unit price bid for the work.

Reinforcement bars shall conform to the requirements of ASTM A706 Gr 60 (IL Modified). See special provisions.

Attach new Name Plate to the backside of 8" rail element. Existing Name Plate is to be removed, cleaned and relocated adjacent to new Name Plate. Cost included in the cost of Name Plates.

The cut strands at each beam end shall be given two coats of zinc dust spray or paint meeting the requirements of ASTM A 780. The zinc dust spray or paint shall be applied before corrosion appears and allowed to dry according to the manufacturer's specifications prior to another coat of zinc. A concrete sealer meeting the requirements of Section 587 of the Standard Specifications shall be applied to the exterior face and 9" in on the underside of the fascia beams. The sealer shall be applied after visible crack growth has subsided. This work shall be performed by the producer and included with the cost of the beam.

Repair of the substructure shall be completed prior to placement of the new deck beams.

The contractor is advised that the existing PPC Deck Beams are in a deteriorated condition with reduced load carrying capacity. It is the Contractor's responsibility to account for the condition of the beams when developing construction procedures for removal and replacement of the superstructure.

If the Contractor's procedure for existing beam removal or placement of new beams involves placement of cranes or other heavy equipment on new beams, a detailed procedure shall be submitted to the Engineer for approval. The procedure shall include calculations, prepared and sealed by an Illinois Licensed Structural Engineer, verifying that the equipment and procedure used will not overstress the new beams. To distribute load to multiple beams and protect the concrete, in all cases a double layer mat of heavy timbers shall be used at all times under crane tracks or wheels and any outriggers in the down position. If necessary, shims shall be used under the crane mat to ensure uniform contact with the underlying beams. Prior to placement of the timber mats the following shall be done: placement and tightening of transverse tie assemblies, grouting and curing the dowels rods 24 hours minimum and grouting and curing the shear keys. A temporary means of lateral restraint will be required for fascia beams at expansion ends of beams to prevent movement of the beams.

Any damage done to the bridge during beam removal shall be repaired by the Contractor. Cost to be included in the cost of Removal of Existing Superstructures.

Layout of slope protection system may be varied in the field to suit ground conditions as directed by the Engineer.


Joint openings shall be adjusted according to Article 520.04 of the Std. Specs. when the deck is poured at an ambient temperature other than 50° F.

The minimum thickness of concrete overlay shall be 5" and varies as required to adjust for the new profile grade and camber.

Reinforcement bars designated (E) shall be epoxy coated.

TOTAL BILL OF MATERIAL

ITEM	UNIT	SUPER	SUB	TOTAL
Stone Riprap, Class A5	Sq. Yd.	_	3,500	3,500
Filter Fabric	Sq. Yd.		3,500	3,500
Removal of Existing Superstructures	Each	1		1
Bridge Deck Grooving	Sq. Yd.	705		705
Concrete Wearing Surface, 5"	Sq. Yd.	753		753
Structural Repair of Concrete (Depth Equal to or Less Than 5")	Sq. Ft.		82	82
Precast Prestressed Concrete Deck Beams (21" Depth)	Sq. Ft.	6,769		6,769
Reinforcement Bars, Epoxy Coated	Pound	9,450		9,450
Steel Railing, Type SM	Foot	413		413
Name Plates	Each	1		1
Preformed Joint Strip Seal	Foot	66		66
Asbestos Bearing Pad Removal	Each	96		96
Bar Splicers	Each	207		207
Protective Coat	Sq. Yd.	753	MARKET STATE	753



SECTION A-A

(Typical along both Upstream and Downstream sides of Riprap Treatment)

GENERAL NOTES, DETAILS &

TOTAL BILL OF MATERIALS

IL ROUTE 143 OVER BEAVER CREEK

F.A.P. ROUTE 793 - SECTION 112BR-2

BOND COUNTY


STA. 670+40

STRUCTURE NO. 003-0035

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COL	INTY	TOTAL SHEETS	BHEET NO.	SHEET NO. 3
F.A.P. RTE. 793		BOND		52	31	<i>1</i> 5 sheets
EED BOAT DIST	. NO. 7	ILLINOIS	FED. ATO PR	DJECT-		

Contract #76897




STAGE I REMOVAL

(Looking East)

STAGE II REMOVAL

(Looking East)



STAGE I CONSTRUCTION


(Looking East)

P.P.C. Dk. Bms.

-- @ Beam & Span

8 - 12" x 12" x 1" Steel Plates at 3'-0" cts. Top and Bott., Each Span

PLAN



SHEAR KEY CLAMPING DETAILS AT STAGE CONST. JT.

STAGE II CONSTRUCTION

(Looking East)

1 1/8 ′ Ф Hole

6"

CLAMPING PLATE

(1) For quantity of Temporary Concrete Barrier, see roadway plans.

(2) For details of Temporary Concrete Barrier, see sheet 4 of 15.

(3) Cost of shear key clamps is included with Precast Prestressed Concrete Deck Beams.

(4) See Special Provisions for Stage Construction of Precast Prestressed Concrete Deck Beams.


STAGE CONSTRUCTION DETAILS IL ROUTE 143 OVER BEAVER CREEK F.A.P. ROUTE 793 - SECTION 112BR-2 BOND COUNTY STA. 670+40

STRUCTURE NO. 003-0035

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY		TOTAL SHEETS	SHEET NO.	SHEET NO.	4
F.A.P. RTE. 793	112BR-2	В	OND	52	32	15 знеета	
FED. ROAD DIST		ILLINOIS	FED. AID PRO	DJECT-			


Contract #76897




NEW SLAB

EXISTING SLAB

SECTIONS THRU SLAB



** Wood blocks may be omitted when required to provide minimum stage traffic lane width. When the wood blocks are omitted, the concrete barrier shall be in direct contact with the steel retainer plate.



NOTES

Cost of anchorage is included with Temporary Concrete Barrier.

screwed to coupler at approximate & of

Connect one (1) 1"x7"x10" steel P to the concrete slab with $2^{-5}8'' \phi$ Expansion Anchors

The 1" x 7" x 10" plate shall not be removed until stage II construction forms and all reinforcement bars are in place and the concrete is ready

or cast in place inserts spaced between the

top layer of reinforcement at approximate € of

Detail I - With Bar Splicer or Couplers:
Connect one (1) 1''x7''x10'' steel 12 to the
top layer of couplers with 2-5₈'' \$\phi\$ bolts

each barrier panel. Detail II - With Extended Reinforcement Bars:

each barrier panel.

to be placed.


STEEL RETAINER P 1" x 7" x 10"

* Required only with Detail II

TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION IL ROUTE 143 OVER BEAVER CREEK F.A.P. ROUTE 793 - SECTION 112BR-2 BOND COUNTY STA. 670+40


STRUCTURE NO. 003-0035


when "A" is greater than 3'-6".



i\projects\ed03705\plan\0035-02-gennotesht.dgn

FILE NAME = c:\projects\e PLOT SCALE = 0:1.0294 ':'\ USER NAME = owenbj





CROSS SECTION

(Looking East)

© Brg. W. Abut. — © Span 1 — © Span 2 — Pier 2 — Pier 3 — © Span 4 — © Brg. E. Abut.

and 7 thru 11. Thickness for Beam 6 will vary

from those shown at beam edges to 4"

SECTION THRU PIERS 1 & 3

Fabric bearing pad


2 - 9" x 4" x 2'-1" or 1'-02"


REINFORCED CONCRETE WEARING SURFACE PROFILE Note: Thicknesses shown are for Beams 1 thru 5

additional at & Roadway.


 $\frac{l_4'' \times 3_4'' \text{ Sawed joint with}}{\text{concrete joint sealer without}}$ $\frac{l_4'' \times 3_4'' \text{ Sawed joint with}}{\text{concrete ioint sealer without}}$ $\frac{l_2'' \times 6'' \text{ PJF}}{\text{Full width}}$ $\frac{l_2'' \times 6'' \text{ PJF}}{\text{Full width}}$

SECTION THRU PIER 2





FABRIC BEARING PAD



a(E)

al(E)

14'-2"

18'-2"

a(E) & a1(E) BARS

FABRIC BEARING PAD
(Interior)

FABRIC BEARING PAD
(Exterior)

EXPANSION

(Interior)

FABRIC BEARING PAD

<u>FIXED</u>

SUPERSTRUCTURE BILL OF MATERIAL

Bar	No.	Size	Length	Shape
a(E)	207	#4	14'-8"	
a1(E)	207	#4	18'-8"	
b(E)	136	#4	26'-10"	
b1(E)	102	#4	35'-3"	
	Wearing Su	Sq. Yd.	753	
Reinforce Epoxy Co	ment Bars, ated	Pound	9,450	

Notes :

- (1) After beams have been erected, holes shall be drilled into substructure and anchor dowels placed. Dowel holes shall be filled with non-shrink grout to top of beam and allowed to cure min. 24 hrs. prior to grouting the shear keys.
- ② Dowel rods drilled in cap are included in the cost of Precast Prestressed Concrete Deck Beams (21" depth).
- 3 Concrete wearing surface to be poured after grouting the shear keys.
- 4 1" Jt. shall be filled with non-shrink grout. 1" dimension may vary to accommodate tolerance in beam lengths.

SUPERSTRUCTURE DETAILS
IL ROUTE 143 OVER BEAVER CREEK
F.A.P. ROUTE 793 - SECTION 112BR-2
BOND COUNTY

<u>STA. 670+40</u> <u>STRUCTURE NO. 003-0035</u>

4" x 4" x 2" P Full Thread Sleeve Washer - 8 required 3" long – 16 required Stage I


TYPICAL TRANSVERSE TIE ASSEMBLY

-3" ♦ Opening

!" \$ x 2'-11" Rods

(Thread each end 4")

44 required total




* TRANSVERSE STRAND PLACEMENT GUIDELINES

Nut for 1" \$

Rod - 8 required


- Place strands symmetrically about centerline of beam.
- 2. The minimum distance from center to center of strands in all directions shall be 2".
- The minimum clearance from strand to dowel hole shall be 2.
- 4. The minimum clearance from stand to void shall be 1_2^l .

Vertical placement of strands shall not be adjusted to satisfy the above quidelines.




LIFTING LOOP DETAIL

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION




TOTAL SHEET NO. SHEET NO. 8RTE. 793 112BR-2 BOND 52 36 *15* SHEETS


Contract #76897



SPECIAL TRANSVERSE TIE ASSEMBLY AT STAGE CONSTRUCTION JOINT



12" \$\phi\$ Strands, Each Strand Stressed to 30,900 Lbs. 6-Strands 1^{3}_{4} " up, 8-Strands 3^{l}_{4} " up, 2-Strands 9" up



SECTION THRU EXTERIOR BEAMS

** May need to tilt D(E) bar to miss bottom rail anchorage. (See sheet 9 of 15 for rail anchorage details.)

NOTES

- (1) Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270. (2) The nominal diameter shall be ${}^{l}_{2}$ " and the nominal cross-sectional area shall be 0.153 sq. in. (3) Lifting loops shall be $2 {}^{l}_{2}$ " ϕ -270 ksi strands, as shown. (4) The 1" ϕ rods in the transverse tie assembly shall be tightened to a snug fit and the threads
- Top of Beam
 - set. Pockets that receive transverse tie bar on outside shall be filled with grout after transverse tie assembly is in place.
 - Non prestressing steel shall conform to ASTM A 706 (IL MOD), Grade 60.
 - $\stackrel{(6)}{6}$ The bearing seat surfaces shall be adjusted by shimming to assure firm and even bearing. Two $^{\prime}8^{\prime\prime}$ fabric adjusting shims of the dimensions of the Exterior Bearing Pad shall be provided for each bearing.
 - (7) Keyway surfaces shall be cleaned to remove form oil or other bond breaking material prior to shipment of the beams. Cleaning shall be done by sandblasting the keyway areas between top of the beam and the bottom edge of the key.
 - (8) Corrosion Inhibitor, per Article 1020.05(b)(12) of the Standard Specifications, shall be used in the concrete for precast prestressed concrete deck beams.

 - Formwork necessary for the wearing surface may be secured utilizing the bottom rail anchorage inserts and/or additional inserts cast into the beam. Drilling into the beam will not be permitted.
 - (1) See sheets 9 & 10 of 15 for remaining superstructure details.
 (2) See sheet 9 of 15 for rail post spacing.

BILL OF MATERIAL

Precast Prestressed Concrete Sq. Ft. 6,769 Deck Beams (21" Depth)

SUPERSTRUCTURE DETAILS IL ROUTE 143 OVER BEAVER CREEK F.A.P. ROUTE 793 - SECTION 112BR-2 BOND COUNTY STA. 670+40 STRUCTURE NO. 003-0035

ANTICIPATED INITIAL CAMBER DIAGRAM

(See Table of Beam Dimensions for dimension E.)


End to End of Beam


Top of Concrete Wearing Surface

12"

Span			Dimensio	on		
	Α	В	С	D	Ε	
1	2'-0"	23'-4"	22'-6"	2'-10"	51'-6"	
2	2'-10"	22'-44"	23'-24"	2'-0"	51'-212"	
3	2'-0"	23'-1"	22'-3"	2'-10"	51'-0"	
4	2'-10"	22'-512"	23'-312"	2'-0"	51'-5"	

TABLE OF BEAM DIMENSIONS






SHEET NO. 9 TOTAL SHEETS 52 37 BOND 112BR-2

15 SHEETS

Contract #76897




- ① Retainer angles are to be used at the expansion ends of deck beams only. After block-outs are poured and cured the retainer angles shall be removed. Anchor bolts may be left in place.
- 2) Approved threaded rod shall be placed in drilled holes and grouted in place. Cost of retainer and accessories are included with Precast Prestresed Concrete Deck Beams (21" Depth).
- (3) Cost of ${}^{l_{2}}$ " ϕ Standard pipe shall be included in the cost of the Precast Prestressed Concrete Deck Beams (21" Depth).
- (4) Retainer assembly shall not be installed until all adjacent partial depth concrete repair work is completed.
- (5) The rail anchorage shall be cast with the beam and the wearing surface shall be cast in the field. Formwork necessary for the wearing surface may be secured utilizing the bottom rail anchorage inserts and/or additional inserts cast into the beam. Drilling into the beam will not be permitted.

SUPERSTRUCTURE DETAILS IL ROUTE 143 OVER BEAVER CREEK F.A.P. ROUTE 793 - SECTION 112BR-2


BOND COUNTY STA. 670+40 STRUCTURE NO. 003-0035

RGUTE NO.	SECTION	cou	INTY	TOTAL SHEETS	SHEET NC.	SHEET NO. 10
F.A.P. RTE. 793	112BR-2	В	DND	52	38	<i>1</i> 5 SHEETS
FED. ROAD DIST	. NO. 7	ILLINOIS	FED. AID PR	DJECT-		

Contract #76897



SECTION THRU STRIP SEAL JOINT FOR OVERLAY OVER DECK BEAMS



LOCKING EDGE RAIL

LOCKING EDGE RAIL SPLICE

* Omit weld at seal opening.

Notes:

The strip seal shall be made continuous and shall have a minimum thickness of ${}^{l}_{4}$ ". The configuration of the strip seal shall match the configuration of the Locking Edge Rails.

The height and thickness of the Locking Edge Rails shown are minimum dimensions. The actual configuration of the Locking Edge Rails and matching strip seal may vary from manufacturer to manufacturer. Flanged edge rails will not be allowed.

The inside of the Locking Edge Rail groove shall be free of weld residue.

Locking Edge Rails may be spliced at slope discontinuities and stage construction joints.

The manufacturer's recommended installation methods shall be followed.

BILL OF MATERIAL

11em	Unit	l ota
Preformed Joint Strip Seal	Foot	66

PREFORMED JOINT STRIP SEAL

IL ROUTE 143 OVER BEAVER CREEK

F.A.P. ROUTE 793 - SECTION 112BR-2

BOND COUNTY

STA. 670+40


STRUCTURE NO. 003-0035

Contract #76897

		€ W. Abut.			
"O -,1 [1'-O"]			, T0"	3′-0"	

EAST FACE OF WEST ABUTMENT

(Looking West)



WEST FACE OF EAST ABUTMENT

(Looking East)

BILL OF MATERIAL

Structural Repair of Concrete (≤5") Sq. Ft. 4

Note

Hatched area indicates approximate area of Structural Repair of Concrete. Exact repair area to be determined by Engineer.

ABUTMENT STRUCTURAL REPAIR OF CONCRETE

IL ROUTE 143 OVER BEAVER CREEK

F.A.P. ROUTE 793 - SECTION 112BR-2


BOND COUNTY

STA. 670+40

STRUCTURE NO. 003-0035


ROUTE NO.	SECTION	cou	NTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 12
F.A.P. RTE. 793	112BR-2	ВС	BOND		40	15 SHEETS
FED. ROAD DIST	. NO. 7	ILL. ENOTE	FED. AZO PRI	DJECY-		

Contract #76897



WEST SIDE PIER 1

(Looking East)



EAST SIDE PIER 1

(Looking West)

BILL OF MATERIAL

Structural Repair of Concrete (≤5")	Sq. Ft.	22

No

Hatched area indicates approximate area of Structural Repair of Concrete. Exact repair area to be determined by Engineer.

PIER 1 STRUCTURAL REPAIR OF CONCRETE

IL ROUTE 143 OVER BEAVER CREEK

F.A.P. ROUTE 793 - SECTION 112BR-2


BOND COUNTY

STA. 670+40

STRUCTURE NO. 003-0035


ROUTE NO.	SECTION	ÇQL	RYTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 13
F.A.P. RTE. 793	112BR-2	ВС	OND	52	41	<i>1</i> 5 sheets
FED. ROAD DIST	r. NO. 7	ILLINGIS	FED. AID PA	JECT-		

Contract #76897



WEST SIDE PIER 2

(Looking East)



BILL OF MATERIAL

Structural Repair of Concrete (≤ 5")	Sq. Ft.	49

Note:

Hatched area indicates approximate area of Structural Repair of Concrete. Exact repair area to be determined by Engineer.

PIER 2 STRUCTURAL REPAIR OF CONCRETE

IL ROUTE 143 OVER BEAVER CREEK

F.A.P. ROUTE 793 - SECTION 112BR-2


BOND COUNTY

STA. 670+40

STRUCTURE NO. 003-0035


ROUTE NO.	SECTION	COL	NTY	TOTAL SKEETS	SHEET NO.	SHEET NO. 14
F.A.P. RTE. 793	112BR-2	ВС	BOND		42	<i>1</i> 5 sheets
FED. ROAD DIST	FED. ROAD DIST. NO. 7		FED. AID PR	QJECT-		

Contract #76897



WEST SIDE PIER 3

(Looking East)



EAST SIDE PIER 3

(Looking West)

BILL OF MATERIAL

Structural Repair of Concrete (≤5")	Sq. Ft.	7

Note

Hatched area indicates approximate area of Structural Repair of Concrete. Exact repair area to be determined by Engineer.

PIER 3 STRUCTURAL REPAIR OF CONCRETE


IL ROUTE 143 OVER BEAVER CREEK

F.A.P. ROUTE 793 - SECTION 112BR-2

BOND COUNTY

STA. 670+40

STRUCTURE NO. 003-0035



Contract #76897

NOTES

Bar splicer assemblies shall be of an approved type and shall develop in tension at least 125 percent of the yield strength of the lapped reinforcement bars.

Splicer rods shall be of minimum 60 ksi yield strength, threaded or coiled full length. All reinforcement bars shall be lapped and tied to the splicer rods or dowel bars. Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars.

Other systems of similar design may be submitted to the Engineer for approval. Approval shall be based on certified test results from an approved testing laboratory that the proposed bar splicer assembly satisfies the following requirements:


Minimum Capacity (Tension in kips) = 1.25 x fy x A_t

Minimum *Pull-out Strength = $0.66 \times fy \times A_t$ (Tension in kips)

Where fy = Yield strength of lapped reinforcement bars in ksi.

 A_t = Tensile stress area of lapped reinforcement bars. * = 28 day concrete

BAR SPLICER ASSEMBLIES							
		Strength Requirements					
Bar Size to be Spliced	Splicer Rod or Dowel Bar Length	Min. Capacity kips - tension	Min. Pull-Out Strength kips - tension				
#4	1'-8''	14.7	7.9				
#5	2'-0"	23.0	12.3				
#6	2'-7''	33.1	17.4				
#7	3′-5″	45.1	23.8				
#8	4'-6''	58.9	31.3				
#9	5′-9″	75.0	39.6				
#10	7′-3′′	95.0	50.3				
#11	9′-0′′	117.4	61.8				



BAR SPLICER ASSEMBLY ALTERNATIVES

WELDED SECTIONS

The diameter of this part is

equal or larger than the

diameter of bar spliced.

** Heavy Hex Nuts conforming to ASTM A 563, Grade C, D or DH may be used.

ROLLED THREAD DOWEL BAR

** ONE PIECE


-Wire Connector

111111111111

The diameter of this part


of the bar spliced.

is the same as the diameter




INSTALLATION AND SETTING METHODS


"A": Set bar splicer assembly by means of a template bolt. "B": Set bar splicer assembly by nalling to wood forms or cementing to steel forms. (E): Indicates epoxy coating.



FOR INTEGRAL OR SEMI-INTEGRAL ABUTMENTS

	Bar Splicer for #5 bar
Min.	Capacity = 23.0 kips - tension
Min.	Pull-out Strength = 12.3 kips - tension
No.	Required =






STANDARD

Bar Size	No. Assemblies Required	Location
#4	207	Conc. Wearing Surf.

BAR SPLICER ASSEMBLY DETAILS IL ROUTE 143 OVER BEAVER CREEK F.A.P. ROUTE 793 - SECTION 112BR-2 BOND COUNTY STA. 670+40

STRUCTURE NO. 003-0035



FOR INFORMATION ONLY

REVISIONS	ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME DATE	LECINOIS BELANTIMENT OF TRANSFORMATION
	EXISTING STRUCTURE PLAN
	EAD DOUTE 707
	FAP ROUTE 793
	SECTION 112BR-2
	BOND COUNTY
	SN 003-0035
	

01 DATE = 5/1/2007 E NAME = en'projects/ed03705\plan\pln83795e TSCALE = 50.8000 / IN. FERENCE = 8REF4

