INDEX OF SHEETS

DESCRIPTION SHEET NO.

- **COVER SHEET**
- INDEX OF SHEETS, LEGEND, GENERAL NOTES,
- SUMMARY OF QUANTITIES
- TYPICAL SECTIONS

- 11-12 ENTRANCE SIGN PLANS
- 13-14 **ENTRANCE SIGN DETAILS**
- TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS

GENERAL NOTES

FIELD OFFICE

THE CONTRACTOR WILL NOT BE REQUIRED TO SET UP A FIELD OFFICE

THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE USED, ONE (1) WEIGHTED SANDBAG ACROSS EACH BOTTOM RAIL

SAW CUTTING

THE CONTRACTOR SHALL SAW CUT ASPHALT PAVEMENT AND DRIVEWAY PAVEMENT AS INDICATED ON THE PLANS TO SEPARATE THE EXISTING PAVEMENT TO BE REMOVED BY APPROVED MEANS OR AN APPROVED CONCRETE SAW TO A DEPTH AS DIRECTED BY THE ENGINEER. SUITABLE GUIDELINES OR DEVICES SHALL BE USED TO ASSURE CUTTING A NEAT. STRAIGHT LINE AS SHOWN ON THE PLANS. CARE SHALL BE TAKEN BY THE CONTRACTOR AS NOT TO DAMAGE THE REMAINING PAVEMENT DIRECTLY ADJACENT TO THE PAVEMENT TO BE REMOVED. ANY DAMAGE TO THE EXISTING PAVEMENT RESULTING FROM PAVEMENT REMOVAL OPERATIONS SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE. THE COST OF SAW CUTTING SHALL BE INCLUDED IN THE ITEM BEING REMOVED.

I.D.O.T. STANDARD DRAWINGS

STANDARD NO.

TITLE OR DESCRIPTION

000004 04	ATAMBABB SWIPS & ABBBERGATIONS AND BATTERNS
000001-04	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS

606001-0:3 CONCRETE CURB TYPE B AND COMBINATION CONCRETE

701501-03 URBAN LANE CLOSURE, 2-LANE, 2-WAY, UNDIVIDED

701701-04 **URBAN LANE CLOSUREMULTILANE INTERSECTION**

LANE CLOSURE, MULTI-LANE, 1-WAY OR 2-WAY 701801-03 CROSSWALK OR SIDEWALK CLOSURE

702001-0.6 TRAFFIC CONTROL DEVICES

10000 - Just Vesto 6. 260.0000

STANDARDS

UNDERGROUND UTILITIES

THE CONTRACTOR'S EXPENSE.

ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARD OF THE ILLINOIS DEPARTMENT OF

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123

FOR FIELD LOCATIONS OF BURIED ELECTRICAL, TELEPHONE AND GAS FACILITIES. (48 HOURS NOTIFICATION IS REQUIRED).

OBTAINED BY FIELD SURVEYS AND SEARCHES OF AVAILABLE RECORDS. IT IS BELIEVED THAT THE DATA IS ESSENTIALLY CORRECT BUT THE VILLAGE OF BROOKEIELD. THE ILLINOIS

DEPARTMENT OF TRANSPORTATION AND/OR OTHER OFFICES AND AGENCIES ASSOCIATED WITH THE DEVELOPMENT OF THESE PLANS DO NOT GUARANTEE THEIR ACCURACY OR COMPLETENESS OF THIS INFORMATION. THE CONTRACTOR WILL BE REQUIRED TO VERIFY THE

EXACT LOCATION OF EACH FACILITY WITH THE RESPECTIVE UTILITY COMPANY, AND SHALL TAKE DUE CARE IN ALL PHASES OF THE CONSTRUCTION TO PROTECT ANY SUCH FACILITIES WHICH

MAY BE AFFECTED BY THE WORK. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED AT

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES

THE LOCATIONS OF THE UNDERGROUND UTILITIES IF SHOWN ON THE PLANS HAVE BEEN

TRANSPORTATION AS SHOWN ON THE INDEX OF SHEETS IN THE PLANS.

LEGEND OF SYMBOLS

(TO BE USED IN CONJUNCTION WITH I.D.Q.T. STANDARD 000001-04)

	EXISTING	PROPOSED	DESCRIPTION
	——— G ———		GAS LINE
	T		TELEPHONE LINE
			SANITARY SEWER
	w		WATER MAIN
			STORM SEWER
)>		COMBINATION SEWER
	Я		FIRE HYDRANT
	Ø		POWER POLE
	Carrier of the Carrie		WATER MAIN VALVE VAULT
	8		WATER MAIN VALVE BOX
	(a)		MANHOLE
			INLET
	Ø		BUFFALO BOX
	0 '		CATCH BASIN
	627.60 620.35		RIM ELEVATION (SANITARY) INVERT ELEVATION
	627.60 620.35		RIM ELEVATION (STORM) INVERT ELEVATION
	627.60 620.35		RIM ELEVATION (WATER MAIN) TOP OF WATER MAIN
*	633		ELEVATION
	*		PROPOSED CONCRETE PAVEMENT, SIDEWALK, OR DRIVEWAY
		235 27 0 7 3 4 3 2 7 5 2 5 1	PROPOSED BITUMINOUS SURFACE COUR BITUMINOUS DRIVEWAYS, OR INCIDENTAL BITUMINOUS SURFACING



TRANSPORTATION CORRIDOR **BEAUTIFICATION PROJECT VILLAGE OF BROOKFIELD, ILLINOIS**

INDEX OF SHEETS, LEGEND OF SYMBOLS, GENERAL NOTES, & I.D.O.T. STANDARD DRAWINGS

NONE RAWN BY LEV/MX/ECW/TSG SDR33 2-9-07

X 06-00121-00-LS COOK 15 2

ILLINGIS PROJECT TE-00D1(773)

VILLAGE SECTION 06-00121-00-LS