

FOR CONTAINERIZED MATERIAL SLASH 4-5, 1" DEEP CUTS THE LENGTH OF THE ROOT BALL PLANTING SOIL MIX:

4 PARTS TOPSOIL

1 PART MASONS SAND

1 PART PERLITE FINISH GRADE

F SHRUB PLANTING DETAIL NO SCALE - PRUNE BROKEN OR DAMAGED BRANCHES INSTALL 'AGRIFORM' 21 GRAM TABLETS, PLACE TABLETS 6" BELOW GRADE & EVENLY SPACE, USE ONE TABLET FOR EACH 1/2" TRUNK CALIPER TOPSOIL BACKFILL - 1/8 DEPTH OF ROOTBALL ABOVE GRADE -- 4" DEPTH SAUCER CUT BURLAP & ROPE AWAY FROM TOP OF ROOTBALL & BURY EDGES BELOW GRADE.

G PARKWAY TREE PLANTING DETAIL

NO SCALE

Acer miyabei 'State Street' MIYABEI MAPLE Celtie occidentalis 'Windy City' HACKBERRY coc 2 1/2" Ginkgo biloba 'Sentry' SENTRY GINKGO 1/2" Gymnocladus dioica 'Proirie Tital PRAIRIE TITAN COFFEETREE 1/2" Malus 'Cardinals Robe' F.A.P.THER FIALA CARDINALS ROBE CRABAPPL TREE FORM Malus 'Jewel cole' RED JEWEL CRABAPPLE MRJ MULTI-STEMMED MSE MULTI-STEMME Pyrus calleryana 'Chanticleer" CHANTICLEER FLOWERING PEAR PCC TREE FORM TCG 22 1/2" 2 1/2" 2 1/2" SHRUBS 18" RKO 72 Rosd x 'Knock Out'
DOUBLE KNOCKOUT HYBRID ROSE 18" PERENNIALS/ GROUNDCOVER Achillea millefolium 'Summerwine SUMMERWINE YARROW ACM 216 GAL. 18" O.C. 18" O.C. Calamagrastis acutifolic 'Karl Forster FEATHER REED GRASS 18" O.C. GAL. 18" O.C. ECM 216 GAL. 18" O.C. GAL. 18" O.C. 300 GAL. 18" O.C. RFG 324 Rubeckia fulgida 'Goldsturm' GOLDSTURM BLACK-EYED SUSAN 18" O.C. GAL. SLB 300 18" Q.C. GAL. GAL, 18" O.C. SPS 300 GAL. 18" O.C.

## **PLANTING NOTES**

INSTALL 'AGRIFORM' 21 GRAM TABLETS, PLACE TABLETS 6" BELOW GRADE & EVERLY SPACE, USE ONE TABLET FOR EACH 1/2" TRUNK CALIPER

SHREDDED BARK MULCH (3' DIA.x8'). 3" DEPTH @ PERIMETER -- 1" DEPTH @ TRUNK.

- Lightly compacted topsoil Mix to 48" & Wariable Depth, Mound Soil, to ±9" settled Heght At L. Proposed 18" Type A conc. Strip W/ 2 NO. 4 DIA REBRA AND 10x10 WML. SEE ENGINEERING PLANS FOR LOCATIONS (TYP.)

INSURE ADEQUATE CONTACT BETWEEN PLACED TOPSOIL AND SUBGRADE FOR PROPER DRAINAGE

EXIST. B-6.24 CURB & GUTTER

ASPHALT PAVEMENT

INSTALL, 'AGRIFORM' 21 GRAM TABLETS, PLACE TABLETS 6" BELOW GRADE & EVENLY SPACE, USE ONE TABLET FOR EACH 1/2" TRUNK CALIPER

SHREDDED BARK MULCH (3' DIA.x8'). 3" DEPTH @ PERIMETER - 1" DEPTH @ TRUNK.

LANDSCAPE CONTRACTOR (CONTRACTOR) SHALL VISIT SITE, INSPECT EXISTING CONDITIONS AND REVIEW PROPOSED PLANTING AND RELATED WORK.

2. CONTRACTOR SHALL VERIFY LOCATIONS OF ALL ON-SITE UTILITIES PRIOR TO BEGINNING CONSTRUCTION ON HIS PHASE OF PHASE OF WORK. ELECTRIC, GAS, TELEPHONE, AND CABLE TELEVISION, ETC. MAY BE LOCATED BY CALLING, JULILE. AT (1-800-892-0123), THE FOLOMING UTILITIES MAY BE LOCATED WITHIN THE PROVECT LIMITS AND ARE MEMBERS OF JULILE: CITY OF ROCKFORD, COM ED, VERIZON, NICOR GAS CO., ROCK RIVER WATER RECLAMATION DISTRICT, ATAT CO., SEC AMERTICE, INSIGHT COMMUNICATIONS, MALEOD USA. MY DAMAGE OR INTERRUPTION OF SERVICES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. CONTRACTOR TO COORDINATE ALL RELATED ACTIVITIES WITH OTHER TRADES ON THE JOB AND SHALL REPORT ANY UNACCEPTABLE JOB CONDITIONS TO OWNER'S REPRESENTATIVE PRIOR TO COMMENCING WORK.

4. ALL SHRUB BEDS AND TREES SHALL BE MULCHED WITH A 3" CONTINUOUS LAYER OF HARDWOOD, SHREDDED BARK ALL GROUND COVER AND PERENNIAL BEDS SHALL BE MULCHED WITH A 1" LAYER OF HARDWOOD SHREDDED BARK. ALL MEDIAN TREES TO BE MULCHED WITH TYPICAL 3" X 6" ELLIPTICAL MULCH RING, ORIENTED EAST—WEST, FOR EASE OF MOWING. ALL PARKWAY DECOUDOUS TREES SHALL BE MULCHED WITH A 3" DAWRIER CIRCLE OF MULCH. ALL EVERGREEN TREES SHALL BE MULCHED TO THE DRIP LINE. MULCHING OF TREES AND PLANTING BROCES SHALL BE INCIDENTAL TO HAVE THE SHALL BY AN TEXT OF THE ANTINE PROCEDURES AND RELATED COOLD PAY TIEMS.

6. EDGE ALL SHRUB BEDS THAT ABUT LAWNS WITH 4" WIDTH BY 4"DEPTH "V" SHAPED SPADED EDGE, CONTINUOUS AS SHOWN ON PLAN. EDGING OF TREES AND PLANTING BEDS SHALL BE INCIDENTAL TO PLANTING PROCEDURES AND RELATED COOLD PAY THEMS.

7. THE TOPSOIL CONDITION FOR THIS PROJECT SITE IS AS FOLLOWS: CONTRACTOR TO SUPPLY, PLACE AND FINISH GRADE TOPSOIL AT SPECIFIED DEPTHS IN PLANTING AND LWIN AREAS. PLANTING AREAS IN MEDIAN ISLANDS ±48 INCHES LIGHTLY COMPACTED DEPTH, CROWNED TO APPROPRIATE HEIGHTS, (SEE DETAILS, a-D-/8); ALL PARKWAY LAWN AREAS 6 INCHES, SEE ROADWAY PLANS AND NOTES SECTION 03-00520-00-WR. ALL TOPSOIL MUST BE FROM THE 'A' HORIZON (ZERO TO 2" DEPTH) OF SOIL PROFILES OF LOCAL SOILS. MEDIAN TOPSOIL MIX TO BE 4 PARTS SANDY LOWN TOPSOIL, IT PART MASONS SAND AND 1 PART PERLITE.

9. SOO TO BE APPROVED <u>IDOT 1A SALT TOLERANT LAWN MIXTURE</u>. NO PEAT SOD WILL BE ALLOWED. SOD GRASSES SHALL CONSIST OF THE FOLLOWING BLUEGRASS TYPES: 34% KENTUCKY BLUEGRASS, 33% FULTS PUCINNELLID BISTANS, 11% DAWSON RED FESCUE, 11% FESCUE, 11% PERENNILA, RYCEGRASS. SOD PIECES ARE TO FIT TIGHTLY TOGETHER SO THAT NO JOINTS ARE VISIBLE, ALTERNATE AND STAGGER COURSES AND TAMP OR ROLL FRINLY. ALL SOUBDE LAWN AREAS SHALL BE FERTILIZED AT FIRST CUTTING WIT 19—40-5 ANALYSIS TERTILIZER, AT A RATE OF 6 LBS. PER 1,000 S.F.. ACCEPTANCE AND GUARANTEE SHALL APPLY TO ALL SOD AREAS.


10. ACCEPTANCE OF GRADING AND SOD SHALL BE BY LANDSCAPE ARCHITECT AND/OR OWNER. THE CONTRACTOR SHALL ASSUME MAINTENANCE RESPONSIBILITIES FOR A MINIMUM OF THERTY (30) DAYS OR UNTIL SECOND CUITING, WHICHDEVER IS LONGER, MAINTENANCE SHALL INCLUDE WATERING, WEEDING, REPLACEMENT OF WASH-OFFS AND ANY OTHER OPERATIONS NECESSARY TO KEEP LAWN IN A THRIVING CONDITION. UPON FINAL ACCEPTANCE BY LANDSCAPE ARCHITECT AND/OR OWNER, THE OWNER SHALL ASSUME ALL MAINTENANCE RESPONSIBILITIES.

11. CONTRACTOR TO PROVIDE ALL LABOR AND MATERIALS NECESSARY TO INSTALL 18" WIDTH CAST IN PLACE EXPOSED ACCRECATE SURFACE AT THE BACK OF CURB, CONTINUIS, IN MEDIANS AS SHOWN ON PLANS, REFER TO ENGINEERING DRAWINGS. CONCRETE STRIP TO MEET BACK OF CURB, CONCRETE TO MAINTAIN CONTINUOUS "HEIGHT ABOVE CURB, REFER TO DETAILS A—D/B. SLOPE ADJACENT GRADES TO MEET PITCH OF CURB. CONCRETE SHALL INCLUDE TWO (2) #4 REBRA AND 6/6 10x10 WMM, CONTINUOUS. CONTRACTOR TO PROVIDE RISTA APPLICATION OF CIERAMING AND SEALANT. INSTALLATION OF WIRE MESH, REBEAR AND SEALANT SHALL BE INCIDENTAL TO CAST IN PLACE CONCRETE PROCEDURES AND RELATED CODED PAY ITEMS.

12. CONTRACTOR TO PROVIDE ALL LABOR AND MATERIALS NECESSARY TO INSTALL 6" PERFORATED RIGID PVC PIPE IN CENTER OF MEDIAN PLANTERS, CONTINOUS. INSTALL PIPE IN 8"x18" TRENCH BACKFILLED WITH CA-7 STONE AND WRAPPED WITH 6-12/W FILTER FA.P.BRIG, REFER TO DETAILS. A-D/B. PICH OF PIPE TO BE MINIMUM 1/4" PER FOOT. PROVIDE LATERAL DRAIN OUTLETS TO ADJACENT STORM INLETS AS SHOWN ON LANDSCAPING PLANS.

13. CONTRACTOR TO VERIFY IN FIELD ALL MEASUREMENTS TO C.L. OF TREES FROM BACK OF CURB AS SHOWN ON PLAN. ADJUST ACCORDINGLY THE LOCATION OF TREES IN PARKWAY (NORTH/SOUTH ALIGNMENT) BASED ON NEW DITCH/SWALE ALIGNMENTS, GAS OR OTHER UTILITY LOCATIONS AND RELOCATED OVERHEAD ELECTRICAL AND TELEPHONE WIRES. CONTRACTOR TO STAKE ALL TREES PRIOR TO INSTALLATION FOR APPROVAL BY OWNER AND/OR LANDSCAPE ARCHITECT.

14. CONTRACTOR TO REMOVE ALL VEGETATION AS DESIGNATED BY ENGINEER/LANDSCAPE ARCHITECT AND/OR LISTED IN TREE REMOVAL SCHEDULE. CONTRACTOR TO PROTECT ALL REMAINING TREES FROM DAMAGE DUE TO HIS OPERATIONS.



13'-0"

10'~0"

(TYP.)

A ISLAND CROSS SECTION @ 13' (BACK TO BACK)

7'-0"

1'-6"

(TYP.)

1'-6"

(TYP.)

SPILELS SSCALES SUSERS DATE NAME SCALE NAME P.C. SER

HARRISON LANDSCAPING PLANS