

## **SCHEDULE OF QUANTITIES**

STEEL RAILING (TEMPORARY) FEET 
 STATION
 TO
 STATION

 598+32
 599+20
 TOTAL

TEMPORARY CONCRETE BARRIER FEET 150 TO STATION 598+32 600+70 TOTAL 300

TEMPORARY BRIDGE TRAFFIC SIGNALS - 1 EACH

TEMPORARY RUMBLE STRIPS - 6 EACH

IMPACT ATTENUATORS, TEMPORARY - 2 EACH (NON-REDIRECTIVE), TEST LEVEL 3 TEMPORARY TRAFFIC BARRIER


- 2 EACH TERMINAL, TYPE 11

## **GENERAL NOTES**

- TRAFFIC CONTROL SHALL BE ERECTED AS SHOWN AND ACCORDING TO "TRAFFIC CONTROL AND PROTECTION, STANDARD 701321."
- 2. SEE SPECIAL PROVISIONS FOR ADDITIONAL TRAFFIC CONTROL REQUIREMENTS.
- 3. COORDINATE LOCATION OF SIGNALS WITH FINAL WORK AS DIRECTED BY THE ENGINEER.
- 4. CONSTRUCT TEMPORARY RUMBLE STRIPS AT LOCATIONS SHOWN ON STANDARD 701321.
- 5. STEEL RAILING (TEMPORARY) AND TEMPORARY CONCRETE BARRIER SHALL BE CONNECTED ACCORDING TO "TRAFFIC BARRIER TERMINAL TYPE 11, STANDARD 631051."

EX ROW

6. EXISTING TRAFFIC CONTROL PRESENT AT THE BRIDGE SITE IS TO REMAIN OPERATIONAL UNTIL STAGE I TC&P IS IMPLEMENTED. REMOVAL OF THE EXISTING TRAFFIC CONTROL WILL BE PAID FOR AS "TEMPORARY TRAFFIC CONTROL REMOVAL."



CONTRACT NO. 98997
COUNTY TOTAL SHEET NO.

WHITE 42 7

TO STA. 603+00

SECTION

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

328 (105X)BR

STA. 594+00

EX ROW