

| SHEET NO. | TITLE |
|-----------|---|
| 1 | TITLE SHEET |
| 2 | GENERAL NOTES, STATE STANDARDS AND INDEX OF SHEETS |
| 3-4 | SUMMARY OF QUANTITIES |
| 5 | TYPICAL SECTIONS |
| 6 | DETOUR PLAN |
| 7 | PLAN AND PROFILE |
| 8 | PAVEMENT MARKING PLAN |
| 9 | EROSION CONTROL PLAN |
| 10-23 | STRUCTURAL PLANS |
| 24 | FRAMES AND LIDS ADJUSTMENT WITH MILLING (BD-08) |
| 25 | PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT (BD-22) |
| 26 | BUTT JOINT AND HMA TAPER DETAILS (BD-32) |
| 27 | TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC-10) |
| 28 | RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-LOW RESISTANT) (TC-11) |
| 29 | DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13) |
| 30 | ARTERIAL ROAD INFORMATION SIGN (TC-22) |
| | HIGHWAY STANDARDS |

STATE STANDARDS

| SHEET NO. | TITLE |
|-----------|--|
| 000001-06 | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS |
| 001001-02 | AREAS OF REINFORCEMENT REBARS |
| 001006 | DECIMAL OF AN INCH AND OF A FOOT |
| 280001-06 | TEMPORARY EROSION CONTROL SYSTEMS |
| 420401-08 | BRIDGE APPROACH PAVEMENT CONNECTOR |
| 442201-03 | CLASS C AND CLASS D PATCHES |
| 515001-03 | NAME PLATE FOR BRIDGE |
| 604001-03 | FRAME AND LIDS TYPE 1 |
| 604091-02 | FRAME AND TRATE TYPE 24 |
| 606001-04 | CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER |
| 630001-10 | STEEL PLATE BEAM GUARDRAIL |
| 630301-05 | SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS |
| 631031-10 | TRAFFIC BARRIER TERMINAL, TYPE 6 |
| 635006-03 | REFLECTOR AND TERMINAL MARKER PLACEMENT |
| 635011-02 | REFLECTOR MARKER AND MOUNTING DETAILS |
| 701301-04 | LANE CLOSURE 2L, 2W SHORT TIME OPERATIONS |
| 701427 | LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS ≤ 40 MPH |
| 701606-06 | URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH MOUNTABLE MEDIUM |
| 701901-02 | TRAFFIC CONTROL DEVICES |
| 704001-07 | TEMPORARY CONCRETE BARRIER |
| 720001-01 | SIGN PANEL MOUNTING DETAILS |
| 720006-03 | SIGN PANEL ERECTION DETAILS |
| 720011-01 | METAL POSTS FOR SIGNS, MARKERS AND DELINEATORS |
| 729001-01 | APPLICATION OF TYPES A & B METAL POSTS (FOR SIGN & MARKERS) |
| 780001-03 | TYPICAL PAVEMENT MARKINGS |

GENERAL NOTES

DIMENSIONS ARE IN ENGLISH UNITS UNLESS OTHERWISE NOTED.

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES (48 HOUR NOTIFICATION IS REQUIRED).

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.

ANY REFERENCE TO STANDARDS IN THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT LISTED IN THE PLANS WITH THE LATEST NUMBERS.

THE RESIDENT ENGINEER SHALL CONTACT MS. PATRICE HARRIS, AREA TRAFFIC ENGINEER, AT (708) 597-9800 AT A MINIMUM OF 2 WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKING.

THE RESIDENT ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.


BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE DIRECTED BY THE ENGINEER.

WHEN MILLED PAVEMENT IS OPEN TO TRAFFIC, THE MAXIMUM GRADE DIFFERENTIAL BETWEEN PASSES OF THE MILLING MACHING SHALL NOT EXCEED 1/2". WITH WRITTEN APPROVAL FROM THE ENGINEER, A MAXIMUM GRADE DIFFERENTIAL FO 3" MAY BE ALLOWED IF THE EDGE OF THE MILLING IS SLOPED A MINIMUM 1:3 (V:H).

BUTT JOINTS WILL BE INSTALLED AT THE ENDS OF ALL RESURFACING (WHERE RESURFACING MEETS EXISTING PAVEMENT), IN ACCORDANCE WITH THE "BUTT JOINT AND HMA TAPER DETAILS" SHEET INCLUDED IN THE PLANS, UNLESS OTHERWISE SPECIFIED.

THE CONTRACTOR SHALL EXERCISE THE UTMOST CARE TO PREVENT ANY DEBRIS FROM THE BRIDGE REMOVAL WORK FROM DROPPING INTO JACKSON CREEK. THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST FOR REMOVAL OF EXISTING STRUCTURES PAY ITEM.

THE RESTRICTED START DATE FOR THIS PROJECT IS MAY 1, 2013. THE CONTRACTOR WILL NOT BE ALLOWED TO PROCEED WITH ANY WORK ON THIS PROJECT THAT REQUIRES A PERMANENT OR OVER-NIGHT LANE(S) OR SHOULDER(S) CLOSURE PRIOR TO MAY 1, 2013. TEMPORARY DAY-TIME LANE/SOULDER CLOSURES MAY BE ALLOWED BETWEEN THE HOURS OF 9:00 AM TO 3:00 PM WITH THE WRITTEN PERMISSION/APPROVAL OF THE ENGINEER AND THE BUREAU OF TRAFFIC OPERATIONS. THE COST TO COMPLY WITH THIS REQUIREMENT SHALL NOT BE PAID FOR DIRECTLY, BUT SHALL BE INCLUDED IN THE COST OF THE PROJECT AND THIS RESTRICTION SHALL NOT BE CONSIDERED A BASIS FOR A TIME EXTENSION.



| | |
|--------------------|-----------|
| DESIGNED - ST | REVISED - |
| DRAWN - ST | REVISED - |
| CHECKED - MJV, SLV | REVISED - |
| DATE - 03/29/2012 | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES, STATE STANDARDS AND INDEX OF SHEETS
PARK AVENUE OVER CALUMET UNION DRAINAGE DITCH

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 98+20 TO STA. 101+60

| | | | | |
|---|----------------|-------------|--------------------|-------------|
| F.A.P. RTE. 3597 | SECTION 0710 B | COUNTY COOK | TOTAL SHEETS 30 | SHEET NO. 2 |
| D-91-292-09 | | | CONTRACT NO. 60F95 | |
| FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | | | | |