

Add the following subparagraphs to this Article:

(n) One 1.2m x 1.8m (4 ft. x 6 ft.) chalkboard or dry erase board.

670.07 Basis of Payment. Revise the fourth sentence of the first paragraph of this Article to read:

The building or buildings fully equipped, will be paid for at the contract unit price per calendar month or fraction thereof for ENGINEER'S FIELD OFFICE TYPE A (SPECIAL), ENGINEER'S FIELD OFFICE TYPE B or ENGINEER'S FIELD LABORATORY.

DELIVERY OF SALVAGEABLE MATERIAL TO THE TOLLWAY

The plans, standard specifications and supplemental specifications require the contractor to deliver various items, which have been removed and deemed salvageable, to the Tollway's Maintenance facility. The following is a list of those references and the assigned location the material is to be delivered for this Contract, as applicable.

<u>Item</u>	<u>Location</u>
Guardrail	M-4 Maintenance Yard - I-94 at IL Rte. 132 (Grand Avenue) M.P. 8.5

Revised 07/27/12