

EARTHWORK SUMMARY BY STAGE	PRESTAGE		STAGE 1					STAGE 2					STAGE 3				
	EARTH EXCAVATION	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	EARTH EXCAVATION	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-)	EARTH EXCAVATION	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-)	EARTH EXCAVATION	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-)
LOCATION	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
MAINLINE I-94	-	-	14,568.73	-4,124.80	16,427.94	4,210.14	12,217.80	-	-	-	-	-	2,942.03	677.91	2,885.69	786.21	2,099.47
MAINLINE I-94 (NORTHBOUND)	-	-	3,568.19	-28,361.09	10,024.21	2,354.38	7,669.83	3,462.64	1,488.97	1,414.15	221.34	1,192.81	1,315.34	1,118.03	0.00	0.00	0.00
MAINLINE I-94 (SOUTHBOUND)	-	-	9,585.63	1,244.92	5,047.13	1,069.55	3,977.58	6,385.18	-2,117.94	3,248.50	766.69	2,481.81	2,248.94	1,911.60	0.00	0.00	0.00
IL-173	-	-	2,357.08	-49,058.34	7,687.31	1,951.65	5,735.66	4,118.55	-41,548.40	7,805.37	1,920.71	5,884.66	-	-	-	-	-
IL-173 - RAMP A	-	-	1,960.48	-656.83	1,712.53	487.21	1,225.32	-	-	-	-	-	-	-	-	-	-
IL-173 - RAMP B	-	-	1,598.99	-1,744.89	1,798.05	444.46	1,353.59	-	-	-	-	-	-	-	-	-	-
SB I-94 TO SB US-41	-	-	-	-	-	-	-	2,112.23	425.30	847.19	251.46	595.73	-	-	-	-	-
NB US-41 TO NB I-94	-	-	909.07	-6,108.09	2,078.02	631.23	1,446.79	-	-	-	-	-	-	-	-	-	-
OLD US-41 TO SB I-94	-	-	3,092.94	2,103.57	1,676.60	535.91	1,140.69	-	-	-	-	-	-	-	-	-	-
DETENTION BASIN	-	-	-	-	-	-	-	5,444.12	4,377.97	3,525.46	1,175.59	2,349.87	-	-	-	-	-
MAINTENANCE OF TRAFFIC	-	-816.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	0	-816	37,641	-86,706	46,452	11,685	34,767	21,523	-37,374	16,841	4,336	12,505	6,506	3,708	2,886	786	2,099

EARTHWORK SUMMARY	20200100	20400800	21101505
	EARTH EXCAVATION	FURNISHED EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT
STAGE	(CU YD)	(CU YD)	(CU YD)
PRESTAGE	0	816	0
STAGE 1	37,641	86,706	46,452
STAGE 2	21,523	37,374	16,841
STAGE 3	6,506	0	2,886
	65,670	124,896	66,178

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com



FILE NAME = \$FILES\$	USER NAME = default	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CIVIL SCHEDULE	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -			94	49-1-R-1	LAKE	677	50	
		CHECKED - RGR	REVISED -			CONTRACT NO. 60L77					
		DATE - 6/19/2012	REVISED -			SCALE: NA	SHEET NO. 7 OF 8 SHEETS	STA. NA	TO STA. NA	ILLINOIS FED. AID PROJECT	

S:\1101\95\CADD\60L77 IL 173\60L77 Sheets\160L77-ht-cv1 schedule.dgn