



INTERCONNECT SCHEDULE OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	1660
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	325
81400200	HEAVY-DUTY HANDHOLE	EACH	4
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	3096
87900200	DRILL EXISTING HANDHOLE	EACH	1
X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	3096
Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1

NOTES:

- REMOVAL OF THE WIRELESS INTERCONNECT SHALL BE CONSIDERED INCLUDED IN THE COST OF REMOVAL OF THE TEMPORARY SIGNALS. THE TEMPORARY WIRELESS SYSTEM SHALL BE RETURNED TO THE ILLINOIS DEPARTMENT OF TRANSPORTATION.

EJM ENGINEERING, INC.
 411 South Wells Street Suite 1000
 Chicago, Illinois 60607

FILE NAME =	USER NAME = grai	DESIGNED - GR	REVISED -
		DRAWN - GR	REVISED -
	PLOT SCALE = none	CHECKED - BKS	REVISED -
	PLOT DATE = 6/18/2012	DATE - 06/19/2012	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**INTERCONNECT SCHEMATIC
 IL RTE 173 - HUNT CLUB ROAD TO I-94 RAMP "A"**

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	49-1-R-1	LAKE	677	359
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60L77	

s:\projects\3021.us_41-usa-to-il-173-bba\project\work\disciplines\traffic_signals\sheet\0160L77-sht-ts-28.dgn