DETAIL A

25'-0" | 7'-6" | 10'-0" | 7'-6" | 25'-0"

TRAFFIC

ONE-WAY CRYSTAL MARKERS
2 EACH AT 100' CENTERS

PAVEMENT MARKING
WHITE STRIPE
(TYPICAL)

DETAIL B

25'-0" | 12'-6" | 12'-6" | 25'-0"

TRAFFIC

ONE-WAY CRYSTAL MARKER
1 EACH AT 50' CENTERS

PAVEMENT MARKING
WHITE STRIPE
(TYPICAL)

DETAIL C

2'-0" | 3'-0" | 3'-0" | 2'-0"

TRAFFIC

ONE-WAY CRYSTAL MARKER
1 EACH AT 48' CENTERS

PAVEMENT MARKING
WHITE STRIPE
(TYPICAL)

TYPICAL LANE DROP

SHOULDER

SHOULDER

2 EACH AT 100' CENTERS (CRYSTAL)

1 EACH AT 50' CENTERS (CRYSTAL)

DETAIL B

DETAIL A

P.C.

P.T.

600'

500'

TYPICAL TANGENT

TYPICAL CURVE

MAINLINE

NOTES:

1. FOR COLLECTOR DISTRUBUTOR, PLACE ONE-WAY CRYSTAL MARKER, 2 EACH AT 100' CENTERS. USE DETAIL A.

2. FOR MULTI LANE DIRECTIONAL RAMPS, PLACE ONE-WAY CRYSTAL MARKER, 1 EACH AT 50' CENTERS. USE DETAIL B.

3. FOR AUXILIARY LANES, PLACE ONE-WAY CRYSTAL MARKER, 1 EACH AT 48' CENTERS. USE DETAIL C.

RAISED PAVEMENT LANE MARKER DETAILS

APPROVED _Paul Kovacs_ DATE 7-1-2009
CHIEF ENGINEER

Illinois Tollway
Open Roads for a Faster Future

DATE	REVISIONS

RAISED PAVEMENT LANE MARKER

STANDARD D8-00

FILE NAME = $FILES$	USER NAME = default	DESIGNED -	REVISED -				
		DRAWN -	REVISED -	STATE OF ILLINOIS	TOLLWAY STANDARD DRAWING	F.A. RTE. 94	SECTION 49-1-R-1
	PLOT SCALE = H:1"=10' V:1"=5'	CHECKED - RGR	REVISED -	DEPARTMENT OF TRANSPORTATION			CONTRACT NO. 60L77
	PLOT DATE = 6/18/2012	DATE - 6/19/2012	REVISED -	SCALE:	SHEET NO. N/A OF N/A SHEETS STA. TO STA.	COUNTY LAKE	TOTAL SHEETS 677 SHEET NO. 654

ILLINOIS FED. AID PROJECT