

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE									
				90% FEDERAL, 10% STATE				100% ISTHA		100% LOCAL NTFPD			
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY		
44001980	CONCRETE BARRIER REMOVAL	FOOT	132						132				
44003100	MEDIAN REMOVAL	SQ FT	8,088	8,088									
44004000	PAVED DITCH REMOVAL	FOOT	1,584	500					1,084				
44004250	PAVED SHOULDER REMOVAL	SO YD	61,022	12,665					48,357				
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	5,777	5,777									
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	24,732						24,732				
48300410	PORTLAND CEMENT CONCRETE SHOULDERS 9 1/2"	SO YD	7,038	7,038									
48300505	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/4"	SO YD	3,779	3,779									
48300700	PORTLAND CEMENT CONCRETE SHOULDERS 12"	SO YD	18,051	17,703					348				
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		0.55					0.45			
50102400	CONCRETE REMOVAL	CU YD	149	149									
50104650	SLOPE WALL REMOVAL	SO YD	350	350									
50105220	PIPE CULVERT REMOVAL	FOOT	730	211					519				
50157300	PROTECTIVE SHIELD	SO YD	1,033		1,033								

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com



* SPECIALTY ITEMS

FILE NAME - #FILES#	USER NAME - default	DESIGNED - JMC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE. 94	SECTION 49-1-R-1	COUNTY LAKE	TOTAL SHEETS 677	SHEET NO. 7
		DRAWN - JMC	REVISED -		SCALE: NA	SHEET NO. 4 OF 29 SHEETS	STA. NA	TO STA. NA	CONTRACT NO. 60L77				
		CHECKED - RGR	REVISED -		ILLINOIS FED. AID PROJECT								
		DATE - 6/19/2012	REVISED -										

S:\BIB\95-CAD\60L77 IL 173\60L77 Sheets\CAD\60L77-INT-ROAD.DWG