

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				90% FEDERAL, 10% STATE				100% ISTHA		100% LOCAL NTFPD	
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY
50200100	STRUCTURE EXCAVATION	CU YD	1,348				700		648		
50300225	CONCRETE STRUCTURES	CU YD	<i>645.3</i>		<i>80.8</i>				<i>564.5</i>		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,776		1,736		40				
50300260	BRIDGE DECK GROOVING	SO YD	2,960		2,960						
50300280	CONCRETE ENCASEMENT	CU YD	30						30		
50300300	PROTECTIVE COAT	SO YD	4,825		4,825						
50400745	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 72"	FOOT	4,757						4,757		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	<i>485,890</i>		416,220		<i>5,320</i>	230	64,120		
50800515	BAR SPLICERS	EACH	1,322		1,220				102		
50901720	BICYCLE RAILING	FOOT	132				132				
50901735	BRIDGE FENCE RAILING (SIDEWALK)	FOOT	626		522						104**
50901750	PARAPET RAILING	FOOT	618		475						143**
51100100	SLOPEWALL 4 INCH	SO YD	1,566	87					1,479		
51201800	FURNISHING STEEL PILES HP14X73	FOOT	7,302						7,302		

** THIS ITEM IS 100% LCDOT, CCS CODE 010, BRIDGE SN 049-0535
 * SPECIALTY ITEMS

BOWMAN, BARRETT & ASSOCIATES INC.
 CONSULTING ENGINEERS
 Chicago, Illinois
 312.228.0100
 www.bbainc.com



FILE NAME - #FILES*	USER NAME - default	DESIGNED - JMG	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE. 94	SECTION 49-1-R-1	COUNTY LAKE	TOTAL SHEETS 677	SHEET NO. 8
		DRAWN - JMG	REVISED -		SCALE: NA	SHEET NO. 5 OF 29 SHEETS	STA. NA	TO STA. NA	CONTRACT NO. 60L77				
		CHECKED - RGR	REVISED -		ILLINOIS FED. AID PROJECT								
		DATE - 6/19/2012	REVISED -										

Rev.

S:\1181\05-CADD\60L77 IL 173\02-77 Sheet\0102L77-INT-000.dgn