

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				90% FEDERAL, 10% STATE				100% ISTHA			100% LOCAL NTFPD	
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY	
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	114	114								
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	406	68					338			
542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48"	FOOT	32	32								
542A1099	PIPE CULVERTS, CLASS A, TYPE 2 54"	FOOT	351	351								
542A1915	PIPE CULVERTS, CLASS A, TYPE 3 30"	FOOT	19						19			
542A5491	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	349						349			
542JA036	PIPE CULVERTS, CLASS A, 36" (JACKED)	FOOT	359	359								
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	12						12			
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	692	692								
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	260						260			
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	16						16			
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	126	126								
55100700	STORM SEWER REMOVAL 15"	FOOT	19						19			
55100900	STORM SEWER REMOVAL 18"	FOOT	87						87			

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



• SPECIALTY ITEMS

FILE NAME - #FILES	USER NAME - default	DESIGNED - JMC	REVISED -
		DRAWN - JMC	REVISED -
		CHECKED - RGR	REVISED -
		DATE - 6/19/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 7 OF 29 SHEETS STA. NA TO STA. NA

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	49-1-R-1	LAKE	677	10
CONTRACT NO. 60L77			ILLINOIS FED. AID PROJECT	

S:\110105_0000\508.27 IL 173V68.77 Sheets\1068L77-sht-09a.dgn