

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				90% FEDERAL, 10% STATE				100% ISTHA		100% LOCAL NTFPD		
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY	
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	2,455			2,455						
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	1,092			892					200	
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	80								80	
81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	1,103			1,103						
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	325			325						
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	463			463						
81200270	CONDUIT EMBEDDED IN STRUCTURE, 4" DIA., PVC	FOOT	401			207					194	
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	14			14						
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	20			20						
81300730	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 14" X 6"	EACH	2			2						
81400100	HANDHOLE	EACH	10			4					6	
81400200	HEAVY-DUTY HANDHOLE	EACH	13			13						
81400300	DOUBLE HANDHOLE	EACH	4			4						
81603081	UNIT DUCT, 600V (XLP-TYPE USE), 1 1/2" DIA. PIA POLYETHYLENE	FOOT	3,616			3,616						

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



• SPECIALTY ITEMS

FILE NAME = 4FILES4	USER NAME = default	DESIGNED - JMG	REVISED -
		DRAWN - JMG	REVISED -
		CHECKED - RGR	REVISED -
		DATE - 6/19/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 14 OF 29 SHEETS STA. NA TO STA. NA

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	49-1-R-1	LAKE	677	17
CONTRACT NO. 60L77			ILLINOIS FED. AID PROJECT	

S:\110104.CAD\049.R-17 IL 173-60L77 Section 10160L77.dwg