

DATE	
BY	
SAVED	
PRINTED	
NOTED	
TEMPERATURE	
WIND	
MOISTURE	
NO. OF SHEETS	
NO.	

DATE	
BY	
SAVED	
PRINTED	
NOTED	
TEMPERATURE	
WIND	
MOISTURE	
NO. OF SHEETS	
NO.	

SUMMARY OF QUANTITIES			URBAN 90% FED. 10% STATE		CONSTRUCTION CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0014 BRIDGE REPAIR FED STATE		
20200100	EARTH EXCAVATION	CU YD	198	198		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	170	170		
25100630	EROSION CONTROL BLANKET	SQ YD	170	170		
28000400	PERIMETER EROSION BARRIER	FOOT	291	291		
44000100	PAVEMENT REMOVAL	SQ YD	261	261		
48101200	AGGREGATE SHOULDERS, TYPE B	TONS	100	100		
50102400	CONCRETE REMOVAL	CU YD	40.4	40.4		
50157300	PROTECTIVE SHIELD	SQ YD	1767	1757		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	40.4	40.4		
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2100	2100		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3800	3800		
50800515	BAR SPLICERS	EACH	48	48		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	233	233		
59000200	EPOXY CRACK INJECTION	FOOT	87	87		

* SPECIALTY ITEM

FILE NAME = D:\BSP72-1\1-500.dgn
 PLOT DATE = 5/14/2012
 PLOT SCALE = 0.8000" = 1' IN.

CHRISTIAN ROSE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-6274

DESIGNED - E.J.M.	REVISED -
DRAWN - J.V.	REVISED -
CHECKED - G.F.L.	REVISED -
DATE - MAY 2012	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 I-94 AT TOURY AVENUE

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	0304.1 H8-1-2	COOK	44	3
CONTRACT NO. 60P72			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	