


DATE	
BY	
REVISIONS	
NO.	
DESCRIPTION	
DATE	
BY	
REVISIONS	
NO.	
DESCRIPTION	
DATE	
BY	
REVISIONS	
NO.	
DESCRIPTION	

DATE	
BY	
REVISIONS	
NO.	
DESCRIPTION	
DATE	
BY	
REVISIONS	
NO.	
DESCRIPTION	
DATE	
BY	
REVISIONS	
NO.	
DESCRIPTION	

SUMMARY OF QUANTITIES			URBAN 90% FED. 10% STATE		CONSTRUCTION CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0014 BRIDGE REPAIR FED STATE	
Z0001903	STRUCTURAL STEEL REMOVAL	POUND	2100	2100	
Z0012102	CONCRETE BRIDGE DECK SCARIFICATION (3/8 INCH)	SQ YD	2426	2426	
Z0012193	BRIDGE DECK THIN POLYMER OVERLAY 3/8"	SQ YD	2426	2426	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 6 INCHES)	SQ FT	325	325	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	2	2	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	2	2	
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	104	104	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	
Z0062456	TEMPORARY PAVEMENT	SQ YD	261	261	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1	
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	GAL DA	21	21	

* SPECIALTY ITEM

FILE NAME = D:\6072\11-SQ-01.dgn
 PLOT DATE = 5/14/2012
 PLOT SCALE = 50.0000' / 1"



DESIGNED - E.J.M.	REVISED -
DRAWN - J.V.	REVISED -
CHECKED - G.F.L.	REVISED -
DATE - MAY 2012	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 I-94 AT TOWHY AVENUE

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	0304.1 HB-1-2	COOK	44	5
CONTRACT NO. 60P72			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

Rev.