

INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS, LIST OF STATE STANDARDS, AND GENERAL NOTES
3-5	SUMMARY OF QUANTITIES
6	TYPICAL SECTIONS
7	ALIGNMENT, TIES, AND BENCHMARKS
8-9	SUGGESTED MAINTENANCE OF TRAFFIC PLAN
10	REMOVAL PLAN
11	ROADWAY PLAN AND PROFILE
12	BRACED EXCAVATION DETAILS
13-32	SIGN DETAILS
33-38	DETAILS
39-44	CROSS SECTIONS

LIST OF STATE STANDARDS

STANDARD NO.	DESCRIPTION
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
280001-06	TEMPORARY EROSION CONTROL SYSTEMS
482001-02	HMA SHOULDER ADJACENT TO FLEXIBLE PAVEMENT
635011-02	REFLECTOR MARKING AND MOUNTING DETAILS
642001-02	SHOULDER RUMBLE STRIPS, 16 INCH
643001-	SAND MODULE IMPACT ATTENUATORS
701101-02	OFF-RD OPERATIONS, MULTILANE 15' TO 24" FROM EDGE OF PAVEMENT
701400-05	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-06	LANE CLOSURE, FREEWAY/EXPRESSWAY
701411-08	LANE CLOSURE, MULTI LANE AT ENTRANCE OR EXIT RAMP, FOR SPEEDS ≥ 45MPH
701901-02	TRAFFIC CONTROL DEVICES
704001-07	TEMPORARY CONCRETE BARRIER
720001-01	SIGN PANEL MOUNTING DETAILS
720006-03	SIGN PANEL ERECTION DETAILS
720011-01	METAL POSTS FOR SIGNS, MARKERS, & DELINEATORS


GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION) AT 8-1-1 OR (800) 892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES (48 HOUR NOTIFICATION IS REQUIRED).
- WHEN ARTIFICIAL LIGHTING IS USED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
- SAW CUTTING OF PAVEMENTS, SIDEWALK, CURB & GUTTER, ETC. SHALL BE TO FULL DEPTH AND SHALL RESULT IN A CLEAN STRAIGHT EDGE ON THE PORTION REMAINING. ALL SAW CUTTING SHALL BE CONSIDERED INCLUDED IN THE COST OF THE ITEM REMOVED.
- DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
- THE CONTRACTOR SHALL USE CARE IN REMOVING OR EXCAVATING NEAR ALL EXISTING ITEMS WHICH WILL REMAIN. ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
- THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4151 A MINIMUM OF 72 HOURS PRIOR TO BEGINNING WORK.
- ALL DAMAGE TO EXISTING PAVEMENT MARKINGS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT THE CONTRACTORS EXPENSE.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING OWNERS OF ALL UTILITIES PRIOR TO CONSTRUCTION TO DETERMINE THE LOCATION OF ALL UTILITY EQUIPMENT. THE CONTRACTOR SHALL COOPERATE WITH ALL UTILITY OWNERS IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS IF UTILITY RELOCATION, ADJUSTMENT, OR PROTECTION IS NECESSARY.
- THE LOCATION OF EXISTING DRAINAGE STRUCTURES, STORM SEWERS, WATER MAINS, SANITARY SEWERS, AND ANY OTHER PUBLIC OR PRIVATE UTILITIES AS SHOWN ON THE PLANS IS APPROXIMATE AND THEIR EXACT LOCATION IS TO BE DETERMINED IN THE FIELD BY THE CONTRACTOR.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UNDERGROUND AND SURFACE UTILITIES EVEN THOUGH THEY MIGHT NOT BE SHOWN ON THE PLANS. ANY UTILITY PROPERTY DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED OR REPLACED TO THE SATISFACTION OF THE ENGINEER.
- ANY LOOSE MATERIAL DEPOSITED IN THE FLOW LINE OF DRAINAGE STRUCTURES, WHICH OBSTRUCTS THE NATURAL FLOW OF WATER SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. PRIOR TO ACCEPTANCE OF THE IMPROVEMENT, ALL DRAINAGE STRUCTURES SHALL BE FREE OF DIRT AND DEBRIS. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT.
- THE CONTRACTOR SHALL CONTACT IDOT ELECTRICAL MAINTENANCE FOR IDOT LIGHTING AND SURVEILLANCE LOCATES.

EARTH WORK SCHEDULE

IL 394				
STATION	EARTH EXCAVATION	FURNISHED EXC	PGES	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
121+00.00	0.0	0.0	0.0	0.0
121+50.00	3.0	0.6	0.0	1.8
122+00.00	2.3	1.2	0.0	0.6
122+50.00	4.3	0.6	0.0	2.8
123+00.00	10.3	0.0	0.0	8.2
123+29.13	9.1	0.0	0.0	7.3
123+50.00	6.5	0.0	0.0	5.2
124+00.00	13.1	0.0	0.0	10.5
124+50.00	6.4	22.8	0.0	-17.7
124+70.92	4.5	10.8	0.0	-7.1
125+00.00	6.6	9.5	0.0	-4.2
125+50.00	10.1	15.6	0.0	-7.6
126+00.00	9.5	15.7	0.0	-8.1
126+50.00	0.2	13.6	0.0	-13.5
127+00.00	4.8	0.6	0.0	3.2
127+34.15	3.8	2.2	0.0	0.8
128+00.00	1.2	3.7	0.0	-2.7
TOTALS	95.8	97.0	0.0	-20.3
	(CU YD)	(CU YD)	(CU YD)	(CU YD)

COMPANY NAME: HRGreen
 PROJECT CONTACT: HRGreen.com
 CLIENT: ILLINOIS
 DATE PLOTTED: 6/11/2012
 PLOT DRAFTER: J. GUERRIERO
 PLOT SCALE: 1"=50.000'



USER NAME: JGUERRI
 DESIGNED: C. HARTKE
 DRAWN: J. GUERRIERO
 CHECKED: T. HAMILTON
 DATE: 6/11/12

REVISED: -
 REVISED: -
 REVISED: -
 REVISED: -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS, LIST OF STATE STANDARDS, AND GENERAL NOTES
 ILLINOIS ROUTE 394

SCALE: 50.0000' SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	2011-073-T	COOK	44	2
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 60P93	