

<b>ROUTE</b>	<b>SECTION</b>	<b>COUNTY</b>	<b>TOTAL SHEETS</b>	<b>SHEET NUMBER</b>
VARIOUS	2012-042-1	COOK	20	6

CONTRACT: 60V31

LOCATION	COMB. CONC. C & G R&R (LF)	HMA SURF R&R VARIABLE DEPTH (SQYD)	SALT TOLERANT SODDING (SQYD)	SIDEWALK 5" R&R (SQFT) 18" CARRIAGE/ COURTESY	SIDEWALK 5" R&R (SQFT) 6' PARALLEL	SIDEWALK 8" R&R (SQFT) 6' PARALLEL	DRIVEWAY 8" R&R (SQFT)	DETECTABLE WARNINGS (ADA RAMPS) (SQFT)	REMARKS
6158 West 64th Street		0.0	0.0	22.5	1080.0	0.0			Replace 36 Front and Side Sidewalk Squares and Courtesy Walks
6241 West 64th Street		0.0	1.5	22.5	180.0	0.0	0.0		Replace 6 Sidewalk Squares and Courtesy Walk
3657 West 65th Place	20.0	3.4	0.0	45.0	930.0	0.0	30.0	20.0	Replace 31 Front and Side Sidewalk Squares , 1 Front and 1 Side Courtesy Walk, 1 Side Driveway Apron, and 2 ADA Ramps
3730 West 65th Place		0.0	0.0	0.0	90.0	0.0			Replace 3 Broken Sidewalk Squares
3732 West 65th Place		0.0	0.0	0.0	180.0	0.0			Replace 5 Broken Sidewalk Squares
3736 West 65th Place	2.0	0.4	0.0	3.0	150.0	0.0			Replace 5 Broken Sidewalk Squares and 2 Feet of Missing Curb
3738 West 65th Place		0.0	0.0	9.0	210.0	0.0			Replace 7 Broken Sidewalk Squares and 2 Courtesy Walk Squares
3740 West 65th Place		0.0	0.0	4.5	210.0	0.0			Replace 7 Broken Sidewalk Squares and 1 Courtesy Walk Square
3839 West 65th Place		0.0	0.0	18.0	180.0	0.0			Replace 6 Sidewalk Squares and 4 Courtesy Walk Squares
4525 West 65th Place		0.0	0.0	0.0	180.0	0.0			Replace 6 Sidewalk Squares
North Side of West 65th Street, from Lavergne (5000 West) to Latrobe (5232 West) Avenue		0.0	0.0	0.0	6000.0	4800.0			Install 1800 Feet of Sidewalk, from Lavergne (5000 West) to Latrobe (5232 West) Avenue, North Side of West 65th Street Only
5708 West 65th Street		0.0	0.0	0.0	180.0	0.0			Replace 6 Sidewalk Squares
3701 West 65th Street		0.0	0.0	0.0	0.0	180.0			Replace 6 Cracked Sidewalk Squares In Front of Garage On Lawndale Avenue Side of Home
3832 West 66th Place	8.0	1.4	0.4	9.0	0.0	0.0			Replace 8 Feet of Broken Curb In Front of Courtesy Walk
4501 West 66th Place		0.0	0.0	9.0	720.0	0.0			Replace Entire Sidewalk On Front and Side of Home
4508 West 66th Place	10.0	1.7	1.7	0.0	0.0	0.0			Replace Cracked Curb. There is a standing water issue here.
4509 West 66th Place	20.0	3.4	0.0	9.0	0.0	72.0			Replace 6 Sidewalk Squares and Sunken Driveway Apron
4517 West 66th Place	5.0	0.9	0.0	0.0	150.0	0.0			Replace 5 Sidewalk Squares
3825 West 66th Street		0.0	0.0	18.0	270.0	0.0			Replace 9 Sidewalk Squares and 4 Courtesy Walk Squares
3848 West 66th Street		0.0	0.0	0.0	0.0	270.0			9 Cracked Sidewalk Squares In Gangway Along Side of House Facing Alley
3650 West 67th Place		0.0	0.0	0.0	270.0	0.0			9 Sidewalk Squares
3859 West 67th Place/3858 West 68th Street	40.0	6.7	0.0	4.5	0.0	60.0	40.0	5.0	Repair Alley Return/Apron In its Entirety With Concrete and ADA Ramps Behind These Two Listed Addresses That Share This Alley Return/Apron
3801 West 68th Place		0.0	0.0	9.0	900.0	120.0	100.0		Replace 34 Front and Side Sidewalk Squares , 3 Driveway Apron Squares, and 2 Side Courtesy Walk Squares
<b>SUB-TOTAL</b>	<b>105.0</b>	<b>17.9</b>	<b>3.6</b>	<b>183.0</b>	<b>11880.0</b>	<b>5502.0</b>	<b>170.0</b>	<b>25.0</b>	

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**