


| CODE NO.   | ITEM   | UNIT  | TOTAL QUANTITY | CONST. CODE  | CONST. CODE   |
|------------|--|-------|----------------|--------------|---------------|
|            |  |       |                | 80% FED      | 100% OAK PARK |
|            |  |       |                | 20% OAK PARK | SAFETY        |
|            |  |       |                | 0031         | 0031          |
|            |  |       |                | URBAN        | URBAN         |
| * 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL        | CU YD | 65             | 65           |               |
| * 21101685 | TOPSOIL FURNISH AND PLACE, 24"                     | SQ YD | 20             | 20           |               |
| * 28000510 | INLET FILTERS                                      | EACH  | 4              | 4            |               |
| * 31101400 | SUBBASE GRANULAR MATERIAL, TYPE B 6"               | SQ YD | 350            | 350          |               |
| * 42001300 | PROTECTIVE COAT                                    | SQ YD | 350            | 350          |               |
| * 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH           | SQ FT | 1,400          | 1,400        |               |
| * 42400800 | DETECTABLE WARNINGS                                | SQ FT | 40             | 40           |               |
| * 44000100 | PAVEMENT REMOVAL                                   | SQ YD | 186            | 186          |               |
| * 44000600 | SIDEWALK REMOVAL                                   | SQ FT | 300            | 300          |               |
| * 50606701 | CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 1 | L SUM | 1              |              | 1             |
| * 50606702 | CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 2 | L SUM | 1              |              | 1             |
| * 60266600 | VALVE BOXES TO BE ADJUSTED                         | EACH  | 1              | 1            |               |
| 67100100   | MOBILIZATION                                       | L SUM | 1              | 1            |               |
| 70102640   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801    | L SUM | 1              | 1            |               |

\* SPECIALTY ITEM

FILE NAME = S:\JOL\6728--6795\6734\012\1\Access\Cadd Sheets\016372-ah-500.dgn



1170 SOUTH HOUBOLT ROAD  
JOLIET, ILLINOIS 60431  
(815) 744-4200  
USER NAME = emandoj  
PLOT SCALE = 1/8"=1'-0"  
PLOT DATE = 5/1/2012

DESIGNED - JDM  
DRAWN - JKP  
CHECKED - MTC  
DATE: 04/11/2012

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET OF SHEETS, STA. TO STA.

|                    |                |        |                           |           |
|--------------------|----------------|--------|---------------------------|-----------|
| F.A.U. RTE.        | SECTION        | COUNTY | TOTAL SHEETS              | SHEET NO. |
| 2783               | 11-00253-00-LS | COOK   | 24                        | 3         |
| CONTRACT NO. 63722 |                |        | ILLINOIS FED. AID PROJECT |           |