


SCALE: 1"= 3'-0"



DESIGNED

CHECKED

DRAWN

DATE

USER NAME = JStrzel

PLOT DATE = 5/25/2012

PLOT SCALE :

HRGreen.com


HRGreen

REVISED

REVISED

REVISED

REVISED



## NOTES:

- ALL REINFORCING STEEL SHALL BE GRADE 60, EPOXY COATED AND IN ACCORDANCE WITH SECTION 508 OF THE STANDARD SPECIFICATIONS.
- 2) ALL REINFORCING STEEL USED FOR THIS ITEM SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE UNIT COST OF PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH, SPECIAL
- 3) CONCRETE PAYER BED SHALL BE PLACED BELOW THE BRICK PAYERS AT AN ELEVATION SO THAT THE FINAL GRADE OF THE BRICK MATCHES FLUSH TO THE BACK OF CURB.
- 4) PAVERS WILL BE INSTALLED ON TOP OF THE SAND MIX/NEO-ASPHALT (ADHESIVE). INSTALLING ALL FULL STONES FIRST, SMALL CUT PIECES WILL THEN BE INSTALLED, CONTRACTOR SHALL COMPACT PAVING STONES INTO THE SAND MIX/NEO-ASPHALT (ADHESIVE) COURSE WITH A MECHANICAL PLATE COMPACTOR WITH A FORCE OF 2,500-3,500 LBS, POLYMERIC SAND IS THEN SWEPT INTO THE JOINTS AND VIBRATED UNTIL THE JOINTS ARE FULL.
- 5) THE PAVERS SHALL BE PLACED ACCORDING TO MANUFACTURED SPECIFICATIONS AND INTERLOCKING CONCRETE PAVEMENT INSTITUTE SPECIFICATIONS.
- 6) THE NEO-ASPHALT (ADHESIVE), SAND MIX ASPHALT AND FILTER FABRIC WILL BE INCLUDED IN THE CONTRACT UNIT COST FOR BRICK PAVER ACCENT STRIP.
- 7) THE CONCRETE PAVER BED AND DRILLING OF WEEP HOLES WILL BE INCLUDED IN THE CONTRACT UNIT COST FOR BRICK PAVER ACCENT STRIP.