INDEX OF SHEETS

1. COVER
2. INDEX OF SHEETS, GENERAL NOTES, AND HIGHWAY STANDARDS
3. SUMMARY OF QUANTITIES
4. TYPICAL SECTIONS
5. SCHEDULES
6. PLAN

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
DISTRICT 6

EXAMINED 5/22 20 12
ENGINEER OF OPERATIONS

EXAMINED 5-21 20 12
ENGINEER OF PROJECT IMPLEMENTATION

EXAMINED May 23 20 12
ENGINEER OF PROGRAM DEVELOPMENT

HIGHWAY STANDARDS

701001-02
701006-03
701301-04
701306-03
701311-03
701901-02
780001-03

GENERAL NOTES

1. THE CONTRACTOR SHALL GIVE IDOT OPERATIONS TWO WEEKS NOTICE PRIOR TO STARTING WORK IN ORDER FOR IDOT TO COMPLETE PATCHING.

2. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.

3. NO EXCAVATION IS ANTICIPATED ON THIS PROJECT. SHOULD ANY EXCAVATION BE REQUIRED, J.U.L.I.E. SHALL BE NOTIFIED A MINIMUM OF 48 HOURS IN ADVANCE (800) 892-0123.

4. ALL CONFLICTING EXISTING STRIPING SHALL BE REMOVED.

5. ALL PAVEMENT MARKINGS, AND NO PASSING ZONES SHALL BE FIELD VERIFIED BY DISTRICT 6 OPERATIONS (785-5312) 14 DAYS PRIOR TO FINAL PAVEMENT MARKINGS.

6. PAVEMENT MARKINGS SHALL NOT BE APPLIED UNTIL FINE AGGREGATE IS PROPERLY SEATED.

7. THE FINE AGGREGATE USED WITHIN THE A-1 TREATMENT SHALL BE CA-16.