









LEGEND

-  PROPOSED LIGHTING UNIT: 16 FT ALUMINUM POLE, FOUNDATION, LED LUMINAIRE, TYPE THREE DISTRIBUTION, 15 1/2 FT MOUNTING HEIGHT
-  PROPOSED UNIT DUCT, 600V, 2-1C NO.10, 1/C NO.10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE
-  UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA. (UNDRGRD C CMC 2 1/2)
-  EXISTING CONTROLLER
-  LUMINAIRE, METAL HALIDE, FLAGPOLE (POLE TOP MOUNTED) ARROW INDICATES LUMINAIRE AIMING DIRECTION
-  SAPLINGS
-  SHRUB
-  RUSTIC WOOD POST AND RAIL FENCE

GENERAL LIGHTING NOTES

1. SIDEWALK REMOVAL AND REPLACEMENT TO ACCOMMODATE CONDUIT OR UNIT DUCT INSTALLATION IS PROHIBITED.
2. CONTRACTOR SHALL BE RESPONSIBLE TO COORDINATE ELECTRICAL WORK WITH OTHER TRADES.
3. CONTRACTOR SHALL INSTALL LIGHT POLES AT THE LOCATIONS INDICATED ON THE PLANS, MAINTAINING ADEQUATE CLEARANCE FROM OVERHEAD UTILITY LINES. CONTRACTOR SHALL BE RESPONSIBLE TO VERIFY CLEARANCES PER THE NATIONAL ELECTRICAL SAFETY CODE AND/OR THE REQUIREMENTS OF THE UTILITY COMPANIES. THE LOCATION OF BURIED AND ABOVE GROUND UTILITIES SHOWN ARE APPROXIMATE AND ARE SHOWN FOR INFORMATION ONLY. REROUTING, DISCONNECTION, RELOCATION, PROTECTION ETC., OF ANY UTILITIES MUST BE COORDINATED BETWEEN THE CONTRACTOR, UTILITY COMPANY, AND OWNER. THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF ALL UNDERGROUND UTILITIES AND BURIED IDOT FACILITIES PRIOR TO CONSTRUCTION.
4. THE CONTRACTOR IS RESPONSIBLE FOR UNCOVERING OR HAND DIGGING AROUND UTILITIES AND BURIED I.D.O.T. FACILITIES AS NECESSARY. THE COST OF THIS WORK IS TO BE INCLUDED WITH THE UNIT DUCT PAY ITEM. ANY DAMAGE CAUSED BY THE CONTRACTOR SHALL BE REPAIRED OR REPLACED TO THE SATISFACTION OF THE ENGINEER AT NO COST TO THE DEPARTMENT.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE LIGHTING SYSTEM UNTIL IDOT HAS TAKEN ACCEPTANCE OF THE SYSTEM. ALL EXISTING CIRCUITS AND CABLES TO THE LIGHT POLES SHALL BE MAINTAINED AS NEEDED AND THIS WORK SHALL BE INCIDENTAL TO THE CONTRACT.
6. THE CONTRACTOR SHALL COORDINATE THE WORK WITH THE REST AREA MAINTENANCE PERSONNEL.
7. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKINGS OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. (1-800-892-0123 OR 811) OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY.
8. UTILITY INTERFERENCES ARE NOT ANTICIPATED ON THIS CONTRACT. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE THEIR CONSTRUCTION ACTIVITIES AND REMEDIAL ACTION PRIOR TO INTERRUPTION OF THE CONTRACTOR'S PROGRESS. NO ADDITIONAL COST SHALL BE ADDED TO CONTRACT RESULTING FROM UTILITY CONFLICTS.
9. PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE WILL NOT BE MEASURED FOR PAYMENT PER ARTICLE 201.1(C)(3) OF THE STANDARD SPECIFICATIONS.
10. REPAIR OR REPLACEMENT OF EXISTING PLANT MATERIAL SHALL BE PER ARTICLES 109.04 AND 201.07 OF THE STANDARD SPECIFICATIONS.

FILE NAME =	USER NAME = prestonne	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	POST OAK REST AREA LIGHTING LEGEND AND GENERAL NOTES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr:\pw_work\pvidot\prestonne\d0287033\d0287033-76f45-shr-light.dgn		DRAWN -	REVISED -			57	661-21RA-L	MARION	14	2	
PLOT SCALE = 48.8888 1 / in.		CHECKED -	REVISED -			CONTRACT NO. 76F45					
PLOT DATE = 5/7/2012		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		