SUMMARY OF QUANTITIES

100% STATE

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0021 NB REST AREA	SB REST AREA	
25000210	SEEDING, CLASS 2A	ACRE	0.4	0.2	0.2	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3.6	1.8	1.8	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3.6	1.8	1.8	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3.6	1.8	1.8	
25100105	MULCH, METHOD 1	ACRE	0.4	0.2	0.2	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	4	2	2	
67100100	MOBILIZATION	L SUM	1	0.5	0.5	
80300100	LOCATING UNDERGROUND CABLE	FOOT	1070	520	550	
81028760	UNDERGROUND CONDUIT, COILABLE	FOOT	120	50	70	
	NONMETALLIC CONDUIT, 2 1/2" DIA.					
81603010	UNIT DUCT, 600V, 2-1C NO. 10, 1/C NO. 10	FOOT	1270	620	650	
	GROUND, (XLP-TYPE USE), 3/4" DIA.					
	POLYETHYLENE					
X8250500	LIGHTING UNIT COMPLETE, SPECIAL	EACH	16	8	8	
X8210673	LUMINAIRE, METAL HALIDE, FLAGPOLE, 150 WATT	EACH	4	2	2	
Z0077700	WOOD FENCE TO BE REMOVED AND RE-ERECTED	FOOT	70		70	

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0021 NB REST AREA	SB REST AREA	

FILE NAME = c:\pw_work\pwidot\prestonme\d0207033\d76f45-sht-light.dgn	USER NAME = prestonme	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/7/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

POST OAK REST AREA LIGHTING
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(61-2)RA-L	MARION	14	3

CONTRACT NO. 76F45

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT