

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	CONSTRUCTION TYPE CODE 0014	
		UNIT	FUNDING 100% STATE
50157300	PROTECTIVE SHIELD	SQ YD	515
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2530
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12
52100530	ANCHOR BOLTS, 1 1/4"	EACH	24
67100100	MOBILIZATION	L SUM	1
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1

	PAY ITEM	CONSTRUCTION TYPE CODE 0014	
		UNIT	FUNDING 100% STATE
70106700	TEMPORARY RUMBLE STRIPS	EACH	3
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
86200300	UNINTERRUPTABLE POWER SUPPLY, EXTENDED	EACH	1
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	12
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	630
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	43.2
Z0021908	SILICONE JOINT SEALER, 2"	FOOT	97
Z0041895	POLYMER CONCRETE	CU FT	6.7