



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 26, 2012

SUBJECT: FAS 711 (CH 28)
Project BRS-0711(109)
Section 12-00124-00-BR
Fayette County
Contract No. 95691
Item 19
August 3, 2012 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

1. Revised page 3 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with the initials "P.E." written in a smaller font to the right.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

TREE REMOVAL, ACRES: Assorted pieces of concrete rubble, old riprap, and pipe culvert are located primarily in the northwest quadrant of the proposed improvements. Other pieces may also be located in the remaining portions of the proposed improvements. This debris material shall be removed and disposed of by the Contractor. The cost to remove and dispose of this debris material shall be included in the contract unit price per Acre for Tree Removal, Acres and no additional compensation will be allowed.

No tree removal shall be allowed or performed from April 1, 2012 through September 30, 2012 for this project.

POROUS GRANULAR EMBANKMENT: Porous Granular Embankment shall meet the applicable portions of Section 207 except the material under paragraph 207.02 Materials shall be gradation CA 16 as specified under Section 1004, paragraph 1004.01 Materials and paragraph 1004.05 (a)(b). Only crushed stone will be approved for use as Porous Granular Embankment on this project. Aggregate shall be placed in 6 inch (loose) lifts and compacted with a vibratory plate compactor with a minimum of 2 passes per lift. Excavation required for installation of the Porous Granular Embankment will be paid for separately under Structure Excavation to the limits shown on the plans. Method of measurement shall be according to the requirements of Article 311.08.

Method of Payment: This work will be paid for at the contract unit price per Ton for Porous Granular Embankment.

STONE DUMPED RIPRAP, CLASS A4: This work shall be performed according to Section 281, except as modified herein:

Article 281.02 Materials shall meet the requirement of Quality Designation "A" and Gradation Designation "RR4" as defined in Article 1005.01 of the Standard Specifications.

Article 281.04 Delete the requirement for bedding stone and filter fabric. The thickness of the riprap shall be 16 inches minimum.

Article 281.06 This work will be measured in tons as specified in Article 311.08(b) of the Standard Specifications.

Article 281.07 Any excavation required for installation will not be paid for separately but shall be included in the contract unit price per ton for the riprap and no additional compensation will be allowed.

Method of Payment: This work will be paid for at the contract unit price per Ton for Stone Dumped Riprap, Class A4 measured as specified herein.