

SUMMARY OF QUANTITIES

URBAN  
100% STATE  
1081

CODE NO.	ITEM	UNIT	TOTAL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	20
20100500	TREE REMOVAL, ACRES	ACRE	0.5
20200100	EARTH EXCAVATION	CU YD	995
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	50
20800150	TRENCH BACKFILL	CU YD	100
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	17,260
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	270
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	270
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	270
25000900	SEEDING, CLASS 1 (SPECIAL)	ACRE	1.7
25001750	SEEDING, CLASS 4 (SPECIAL)	ACRE	0.9
25001810	SEEDING, CLASS 5 (SPECIAL)	ACRE	0.4
25100110	MULCH, METHOD 1	TON	6.0
28000400	PERIMETER EROSION BARRIER	FOOT	1600
28000500	INLET AND PIPE PROTECTION	EACH	7
35100100	AGGREGATE BASE COURSE, TYPE A	TON	860
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	80
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	140
42000300	PORTLAND CEMENT CONCRETE PAVEMENT, 8"	SQ YD	15
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH	SQ FT	175
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	75
44000600	SIDEWALK REMOVAL	SQ FT	1970
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	25
44200280	PAVEMENT PATCHING TYPE IV	SQ YD	25
48101200	AGGREGATE SHOULDERS TYPE B	TON	40
50102400	CONCRETE REMOVAL	CU YD	5
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	52

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		COOK	17	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 44917				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL
56103000	DUCTILE IRON WATER MAIN 6"	FOOT	115
56108800	TAPPING VALVES AND SLEEVES 6"	EACH	1
671000100	MOBILIZATION	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
A2003120	TREE, CELTIS OCCIDENTALIS WINDY CITY (WINDY CITY HACKBERRY), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	1
B2001167	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 8' HEIGHT, BALLED AND BURLAPPED	EACH	1
B2001768	TREE, CRATAEGUS CRUS GALLI VAR. INERMIS "CRUSADER" (CRUSADER THORNLESS COCKSPUR HAWTHORN) 2" CALIPER, BALLED AND BURLAPPED	EACH	7
A2003920	TREE, FRAXINUS PENNSYLVANICA CIMARRON (CIMARRON <sup>GREEN</sup> ASH), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	4
A2005616	TREE, OSTRYA VIRGINIANA ( <sup>AMERICAN HOPHORNBEAM</sup> ), 2" CALIPER, BALLED AND BURLAPPED	EACH	5
C2001049	SHRUB, CARYOPTERIS X CLANDONENSIS "ARTHUR SIMMONDS" (ARTHUR SIMMONDS BLUEBEARD), 1-GALLON	EACH	77
C2001120	SHRUB, CEANOTHUS AMERICANUS (NEW JERSEY TEA), CONTAINER GROWN, 3-GALLON	EACH	43
C2003422	SHRUB, HIBISCUS SYRIACUS "BLUE BIRD" (BLUE BIRD ROSE OF SHARON) 2-1/2' HEIGHT, BALLED AND BURLAPPED	EACH	10
C2004126	SHRUB, KOLKWITZIA AMABILIS "PINK CLOUD" (PINK CLOUD BEAUTY BUSH) 2' HEIGHT, BALLED AND BURLAPPED	EACH	11
C2005226	SHRUB, POTENTILLA FRUITICOSA "PINK BEAUTY", (PINK BEAUTY BUSH CINQUEFOIL), CONTAINER GROWN, 2-GALLON	EACH	100
C2005864	SHRUB, RHUS AROMATICA "GRO-LOW", (GRO-LOW SUMAC), CONTAINER GROWN, 3-GALLON	EACH	201
C2010924	SHRUB, SYRINGA MEYERI PALIBIN (DWARF KOREAN LILAC), 2' HEIGHT, BALLED AND BURLAPPED	EACH	79
C2010726	SHRUB, SYMPHORICARPUS X CHENALTII "HANCOCK", (HANCOCK CORALBERRY), CONTAINER GROWN, 3-GALLON	EACH	52
C2011724	SHRUB, VIBURNUM DENTATUM, (ARROWWOOD VIBURNUM), 2' HEIGHT, BALLED AND BURLAPPED	EACH	20
C2012336	SHRUB, VIBURNUM LANTANA MOHICAN, (MOHICAN WAYFARING TREE VIBURNUM) 3' HEIGHT, BALLED AND BURLAPPED	EACH	21
K0030396	PERENNIAL PLANTS, ACHILLEA X "MOONSHINE", (MOONSHINE YARROW), 1-GALLON	EACH	70
K0030398	PERENNIAL PLANTS, AQUILEGIA CANADENSIS, (AMERICAN COLUMBINE), 1-GALLON	EACH	51

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY AND SCHEDULE OF QUANTITIES  
IDOT / IHPA  
PULLMAN STATE HISTORIC SITE

SCALE: VERT.  
HORIZ.  
DATE: 11/08/05

DRAWN BY: DJM  
CHECKED BY: PJM