


MAILBOX TURNOUT DETAILS

MAILBOX TURNOUTS IN THE CURB AND GUTTER SECTION SHALL BE CONSTRUCTED OF 6" PCC DRIVEWAY PAVEMENT. AGGREGATE BASE COURSE IS NOT REQUIRED FOR MAILBOX TURNOUTS CONSTRUCTED WITH PCC DRIVEWAY PAVEMENT. LAYOUT OF PCC MAILBOX TURNOUTS SHALL BE AS DIRECTED BY THE ENGINEER.



F.A.S. SECTION TOTAL SHEE SHEETS NO. COUNTY 1517(2)RS-3 (3)RS-4 MCLEAN 223 TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

66383

EDGE OF PROPOSED ENTRANCE APRON EDGE OF PROPOSED BITUMINOUS SHOULDER OR VARIES (SEE PLANS) MATCH EX. ENTRANCE BACK OF PROPOSED CURB ELEVATION (TYP.) SLOPE VARIES - EX. ENTRANCE (SEE CROSS-SECTIONS) 8" AGGREGATE SURFACE COURSE, TYPE B AGG. BASE COURSE TYPE B, 8" SECTION A-A


• 6" PCC DRIVEWAY PAVEMENT AND 8" PCC DRIVEWAY PAVEMENT SHALL BE USED IN THE CURB AND GUTTER SECTION FOR PRIVATE AND COMMERCIAL ENTRANCES, RESPECTIVELY. PCC DRIVEWAY PAVEMENT SHALL BE USED ON THE ENTIRE PROPOSED ENTRANCE AREA FOR THE ENTRANCES AT U.S. ROUTE 150 STA. 422+18 RT, STA. 432+67 RT, AND STA, 433+84 RT,


6" PCC DRIVEWAY PAVEMENT SHALL BE USED ON THE ENTIRE PROPOSED ENTRANCE AREA FOR THE PRIVATE ENTRANCES AT T.R. 2075 STA. 1300+73 RT AND STA. 1301+36 RT.

AGGREGATE BASE COURSE IS NOT REQUIRED FOR PCC DRIVEWAY PAVEMENT.

2" INCIDENTAL BIT. SURFACING*

PROFILE AT PRIVATE/COMMERCIAL ENTRANCES





PLAN AT PRIVATE/COMMERCIAL ENTRANCES

- 1. AGGREGATE SURFACE COURSE SHALL NOT BE USED ON COMMERCIAL ENTRANCES OR PRIVATE ENTRANCES THAT ARE ENTIRELY CONCRETE OR BITUMINOUS. IN THESE CASES THE CONCRETE OR BITUMINOUS PAVEMENT SECTION SHALL BE USED ON THE ENTIRE PROPOSED ENTRANCE AREA.
- 2. THE COST OF REMOVING BITUMINOUS CONCRETE AT EXISTING ENTRANCES SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR DRIVEWAY PAVEMENT REMOVAL. REMOVING AGGREGATE AT EXISTING ENTRANCES SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR EARTH EXCAVATION.

REVISED SHEETS

ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.S. 1517 (U.S. ROUTE 150)

MISCELLANEOUS DETAILS

SCALE: VERT.

DRAWN BY CHECKED BY

FIELD ENTRANCE DETAIL