

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(74-68)MRS	PIATT	10	4

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAI -72
Piatt County

Sta. 1348+00 to 1376+00

Rural-Multilane
100% State
1000
TOTAL
QUANTITY

CONSTRUCTION TYPE CODE:

CODE NO.	ITEM	UNIT	QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	514.0
40600300	AGGREGATE (PRIME COAT)	TON	11.0
44200525	CLASS A PATCHES, TYPE I, 8 INCH	SQ YD	16.0
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ YD	46.0
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQ YD	16.0
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SQ YD	27.0
44213000	PATCHING REINFORCEMENT	SQ YD	105.0
44213200	SAW CUTS	FOOT	606.0
67100100	MOBILIZATION	L SUM	1.0
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2.0
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.0
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	112.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	40.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,800.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	11.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	11.0
X4066528	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	288.0
X4066658	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	336.0
X4409420	BITUMINOUS SURFACE REMOVAL 3 1/4"	SQ YD	3,423.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	7.0
Z0075300	TIE BARS	EACH	20.0

* SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.I. ROUTE 72
SECTION (74-68)MRS
PIATT COUNTY

SCALE: NO SCALE
DATE: APRIL 20, 2006

DRAWN BY: CADD
CHECKED BY: