

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(74-68)MRS	PIATT	10	5

## SCHEDULE OF CLASS A PATCH QUANTITIES

STATION	DIRECTION	LENGTH ( FT )	WIDTH ( FT )	TYPE 1 44200525 ( SQ. YD. )	TYPE 2 44200529 ( SQ. YD. )	TYPE 3 44200533 ( SQ. YD. )	TYPE 4 44200535 ( SQ. YD. )	SAW CUTS 44213200 ( FT )	TIE BARS Z0075300 ( EACH )	PATCH REINF 44213000 ( SQ. YD. )
1375+50	WBDL	10.0	12.0		13.30			68.00		13.30
1375+00	WBDL	6.0	6.0	4.00				36.00		4.00
1374+60	WBDL	10.0	6.0		6.70			44.00		6.70
1374+40	WBDL	6.0	12.0		8.00			60.00		8.00
1372+46	WBDL	6.0	6.0	4.00				36.00		4.00
1371+30	WBDL	12.0	12.0			16.00		72.00		16.00
1364+47	WBDL	6.0	12.0		8.00			60.00		8.00
1363+22	WBDL	40.0	6.0				26.70	104.00	20.00	26.70
1362+17	WBDL	15.0	6.0		10.00			54.00		10.00
1353+58	WBDL	6.0	6.0	4.00				36.00		4.00
1352+92	WBDL	6.0	6.0	4.00				36.00		4.00
PAGE TOTALS				16.0	46.0	16.0	26.7	606.0	20.0	104.7
CLASS A PAVEMENT PATCH - 8 INCH TOTALS				16.0	46.0	16.0	26.7	606.0	20.0	104.7
USE				16.0	46.0	16.0	27.0	606.0	20.0	105.0

**NOTES:**

CLASS A PATCHING WILL BE PERFORMED AFTER MILLING IS COMPLETED AND THE EXISTING BITUMINOUS OVERLAY IS REMOVED TO EXPOSE THE EXISTING CONCRETE PAVEMENT SURFACE. PATCH LOCATIONS AND DIMENSIONS WILL BE DETERMINED BY THE ENGINEER AFTER MILLING IS COMPLETED.

ANY ADDITIONAL QUANTITY OF BITUMINOUS MATERIAL REMOVED DURING CLASS A PATCH WORK WILL NOT BE MEASURED FOR PAYMENT AND SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR BITUMINOUS SURFACE REMOVAL - 3 1/4".

( CLASS A PATCHES LOCATED ADJACENT TO THE WESTBOUND TRAVELED WAY CENTERLINE WILL REQUIRE REMOVAL OF ADDITIONAL BITUMINOUS OVERLAY MATERIAL BEYOND THE 11 FOOT WIDE BITUMINOUS SURFACE REMOVAL - 3 1/4" PAY ITEM. )

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 F.A.I. ROUTE 72  
 SECTION (74-68)MRS  
 PIATT COUNTY

SCALE: NO SCALE  
 DATE: APRIL 20, 2006  
 DRAWN BY: CADD  
 CHECKED BY: