F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	310	26
STA.		TO STA.		
CONTRACT NO. 74155				

* PARK ROADS
** SFWA PARK ROADS 2003-1
*** MOULTRIE AND SHELBY

SCHEDULES

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (CU YD)	FOR INFORMATION ONLY: EARTH EXCAVATION ADJUSTED FOR SHRINKAGE 25% (CU YD)	FOR INFORMATION ONLY: EMBANKMENT (CU YD)	FOR INFORMATION ONLY: BALANCE +/- (CU YD)	FURNISHED EXCAVATION (CU YD)	REMARKS
MARGARET GUZY POTHOLE WETLAND RESERVE	10	8	6	2		EXCESS MATERIAL TO BE WASTED
SUB-TOTAL =	10	8	6	2	0	
WEST OKAW FISH & WILDLIFE AREA						
LOOP ROAD TO PARKING LOT 30	122	97	9	88		12 CU YDS MATERIAL TO BE PLACED AS EMBANKMENT ON TR 117B EXCESS TO BE WASTED
TR 89 TO PARKING LOT 2	0	0	33	-33	33	
PARKING LOT 3	72	57	105	-48	47	
1 **[PARKING LOT 11B]**	**[29]**	**[22]**		**[22]**		**[EXCESS MATERIAL TO BE WASTED]**
PARKING LOT 14	53	43	17	26		26 CU YDS MATERIAL TO BE PLACED AS EMBANKMENT TR 99B TO PL 13
PARKING LOT 18	5	4	75	-71	71	
PARKING LOT 26	4	4	55	-51	51	
TR 24 TO PARKING LOTS 27 & 29	112	89	150	-61	61	
TR 107A TO PARKING LOTS 22 & 23	2	2	234	-232	233	
TR 117B TO PARKING LOT 30	1	1	13	-12		OBTAIN 12 CU YDS MATERIAL FROM LOOP ROAD TO PL 30
TR 99B	41	33	209	-176	150	OBTAIN 26 CU YDS ADDITIONAL MATERIAL FROM PL 14
1 SUB-TOTAL =	**[441]**	**[352]**	900	**[-548]**	646	
KASKASKIA FISH & WILDLIFE AREA						
PARKING LOT 51	13	10	35	-25	25	
PARKING LOT 53	10	8	6	2		EXCESS MATERIAL TO BE WASTED
PARKING LOT 60	165	132	35	97		EXCESS MATERIAL TO BE WASTED
PARKING LOT 63	63	51	12	39		EXCESS MATERIAL TO BE WASTED
PARKING LOT 67	187	149	201	-52		OBTAIN 52 CU YDS MATERIAL FROM TR 142A PL 64
PARK ROAD TO PARKING LOT 73	496	397	35	362		PLACE 86 CU YDS MATERIAL TO PARK RD TO 72 AND 74 EXCESS MATERIAL TO BE WASTED
PARK ROAD TO PARKING LOTS 72 & 74	25	20	106	-86		OBTAIN 86 CU YDS FROM ROAD TO PARK RD 73
TR 118E TO PARKING LOT 71	180	144	104	40		EXCESS MATERIAL TO BE WASTED
TR 131A TO PARKING LOT 66	4	3	91	-88	88	
TR 140 TO PARKING LOTS 54, 55, 56, 58, 58A & 58B	136	109	115	-6	6	
TR 142A TO PARKING LOT 64 AND TA-1	176	141	36	105		PLACE 52 CU YDS MATERIAL ROAD TO PL 67 EXCESS MATERIAL TO BE WASTED
TR 143A TO PARKING LOT 70	31	24	31	-7	7	
SUB-TOTAL =	1486	1188	807	381	126	
1 TOTAL =	**[1937]**	**[1548]**	1713	**[-165]**	772	
1 PAY TOTAL =	**[1940]**	**[1548]**	1710	**[165]**	775	

STONE LINED DITCH SCHEDULE

LOCATION (STATION)	SIDE	STONE LINED DITCHES (TON)
WEST OKAW FISH & WILDLIFE AREA		
TR 99B TO PARKING LOT 13		
STA 20+50.00 TO STA 21+17.00	RT	10
STA 21+85.00 TO STA 22+80.00	RT	15
STA 21+85.00 TO STA 22+80.00	LT	15
STA 24+32.00 TO STA 28+00.00	LT	57
STA 24+34.00 TO STA 28+00.00	RT	57
STA 35+35.00 TO STA 36+00.00	LT	10
TR 99 TO PARKING LOT 18		
STA 10+33.00 TO STA 10+50.00	RT	3
STA 13+25.00 TO STA 15+00.00	LT	27
STA 14+25.00 TO STA 14+75.00	RT	8
STA 17+00.00 TO STA 19+00.00	LT	31
STA 17+75.00 TO STA 18+25.00	RT	8
TR 24 TO PARKING LOTS 27 & 29		
STA 4+25.00 TO STA 6+50.00	RT	35
STA 4+25.00 TO STA 6+50.00	LT	35
STA 12+25.00 TO STA 15+00.00	RT	43
STA 12+25.00 TO STA 15+00.00	LT	43
STA 28+00.00 TO STA 29+75.00	LT	27
STA 28+00.00 TO STA 30+00.00	RT	31
STA 30+75.00 TO STA 32+25.00	LT	23
STA 31+00.00 TO STA 32+25.00	RT	19
SUB-TOTAL =		497
KASKASKIA FISH & WILDLIFE AREA		
TR 140 TO PARKING LOTS 54, 55, 56, 58, 58A & 58B		
STA 17+50.00 TO STA 18+25.00	RT	12
STA 17+50.00 TO STA 18+25.00	LT	12
STA 27+50.00 TO STA 29+00.00	RT	23
STA 27+50.00 TO STA 29+00.00	LT	23
TR 142A TO PARKING LOT 64 AND TA-1		
STA 6+00.00 TO STA 8+25.00	RT	35
STA 6+00.00 TO STA 8+25.00	LT	35
PARK ROAD TO PARKING LOT 60		
STA 3+00.00 TO STA 3+28.00	RT	4
STA 12+00.00 TO STA 12+75.00	RT	12
STA 12+00.00 TO STA 12+75.00	LT	12
TR 131A TO PARKING LOT 66		
STA 18+00.00 TO STA 18+34.00	LT	7
STA 19+00.00 TO STA 20+00.00	RT	16
STA 19+00.00 TO STA 20+00.00	LT	16
PARK ROAD TO PARKING LOT 67		
STA 10+00.00 TO STA 11+00.00	LT	16
STA 10+25.00 TO STA 11+00.00	RT	12
STA 26+50.00 TO STA 27+50.00	RT	16
STA 26+50.00 TO STA 27+50.00	LT	16
PARK ROAD TO PARKING LOT 70		
STA 1+65.00 TO STA 3+25.00	RT	25
STA 1+85.00 TO STA 3+25.00	LT	22
TR 118E TO PARKING LOT 71		
STA 10+62.00 TO STA 11+00.00	LT	6
STA 10+72.00 TO STA 11+00.00	RT	4
STA 15+50.00 TO STA 15+86.00	LT	6
SUB-TOTAL =		330
TOTAL =		827

1 NOTE:
EXCESS MATERIAL TO BE WASTED SHALL MEAN DELIVERED AND STOCK PILED AT AN ADJACENT DNR SITE AS REQUESTED BY THE SITE SUPERINTENDENT

REVISIONS	
NAME	DATE
1 FGI	11/23/2005

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES FOR SHELBYVILLE STATE FISH & WILDLIFE AREAS

SCALE:
DATE
DRAWN BY BANDY
CHECKED BY STEUART