EARTHWORK SCHEDULE (FOR INFORMATION ONLY)

			EARTH	EARTH	EARTHWORK
LOCAT	ION		EXCAVATION	EXCAVATION	BALANCE
			(WIDENING)	ADJUSTED FOR	WASTE (+) OR
STATI	ON TO	STATION		SHRINKAGE (25%)	SHORTAGE (-)
			CU YD	CU YD	CUYD
STA	100+75.00 TO	STA 101+28.00	7.5	5.6	+5.6
STA	110+10.48 TO	STA 111+00.00	12.5	9.4	+9.4
SUBTO	TAL		20	15	+15

NOTE: EARTHWORK IS INCLUDED IN THE COST OF PAVED SHOULDER REMOVAL

GUARDRAIL SCHEDULE

	GUARDRAIL	TRAFFIC	GUARDRAIL
LOCATION	REMOVAL	BARRIER	MARKERS,
		TERMINAL,	TYPE A
		TYPE 6	
	F00T	EACH	EACH
NW QUADRANT	31.25	1	1
NE QUADRANT	31.25	. 1	1
SW QUADRANT	31.25	1	1
SE QUADRANT	31.25	1	1
TOTAL	125 *	4	4

• GUARDRAIL REMOVAL IS NOT A TOTAL QUANTITY. SEE STAGING SCHEDULE FOR ADDITIONAL QUANTITY.

NOTE: SEE STAGING SCHEDULE FOR TRAFFIC BARRIER TERMINAL, TYPE 11 QUANTITY.

RESURFACING SCHEDULE

					BITUMINOUS	AGGREGATE	BITUMINOUS CONCRETE	BITUMINOUS CONCRETE	BITUMINOUS	PAVED
LOCATION			MATERIALS	(PRIME COAT)	SURFACE COURSE,	BASE COURSE WIDENING	SURFACE	SHOULDER		
					(PRIME COAT)		SUPERPAVE	SUPERPAVE 9 INCH	REMOVAL 1 1/2"	REMOVAL
STATIO	ON	то	STA	TION	TON	TON	TON	SQ YD	SQ YD	SQ YD
STA :	100+75.00	T0	STA	101+47.50	0.08	0.4	14.9	47.3	195.7	17.9
BRIDGE	E OMISSION									
STA	109+91.23	ТО	STA	111+00.00	0.12	0.6	22.3	79.7	284.3	30.1
TOTAL					0.2	1	37 **	127	480	48

** BITUMINOUS CONCRETE SURFACE COURSE IS NOT A TOTAL QUANTITY. SEE BRIDGE PLANS FOR ADDITIONAL QUANTITY.

TEMPORARY RAMP SCHEDULE

		WIDTH	LENGTH	TEMPORARY
LOCA	TION			RAMP
		FOOT	FOOT	SQ YD
STA	100+75	24	5	13.3
STA	101+47.50	24	5	13.2
STA	109+91.23	24	5	13.2
STA	111+00	24	5	13.3
TOTA	L	<u> </u>		53

PAVEMENT MARKING SCHEDULE

	PAVEMENT MARKI	ING REMOV	/AL	THERMOPLASTIC PAV	EMENT MA	ARKING	TEMPORARY	SHORT-TERM	WORK ZONE	RAISED REFLECTIVE	REPLACEMENT	RAISED REFLECTIVE	RAISED REFLECTIVE	BARRIE	R WALL .	BARRIE	R WALL
LOCATION	SKIP-DASH CENTERLINE	EDGE	LINE	SKIP-DASH CENTERLINE	EDGE	LINE	PAVEMENT	PAVEMENT	PAVEMENT	PAVEMENT MARKER	REFLECTOR	PAVEMENT MARKER	PAVEMENT MARKER	MARK	ERS,	MARI	KERS,
	4" YELLOW	4" V	WHITE	4" YELLOW	4" V	VHITE	MARKING	MARKING	MARKING	REMOVAL			(BRIDGE)	TYP	EВ	TYF	PE C
		LT	RT		LT	RT	LINE - 4"		REMOVAL		2-WAY AMBER	2-WAY AMBER	2-WAY AMBER	LT	RT	LT	RT
STATION TO STATION	SQ FT	SQ FT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
STA 99+07.30 TO STA 103+00.00	33.5	130.9	130.9	100	392.7	392.7	885	36	307	5	2	1	2	2	2	2	2
STA 103+00.00 TO STA 109+00.00	50.0	200.0	200.0	150	600.0	600.0	1350	56	468	1			8	8	8	8	8
STA 109+00.00 TO STA 112+82.90	33.5	127.6	127.6	100	382.8	382.8	866	36	301	3	2	1	1	1	1	1	1
SUB-TOTAL	117	458.5	458.5	350	1375.5	1375.5					-			11	11	11	11
TOTAL	1034	1	_k	3101			3101	128	1076	9	4	2	11	2	2	2	<u>2</u> 2

STAGING SCHEDULE

	TRAFFIC CONTROL &	TRAFFIC CONTROL &	TRAFFIC CONTROL &	WIDE	CHANGEABLE	TEMPORARY	TEMPORARY	RELOCATE	TEMPORARY	TRAFFIC	GUARDRAIL	IMPACT	IMPACT
LOCATION	PROTECTION FOR	PROTECTION	PROTECTION	LOAD	MESSAGE	PAVEMENT	CONCRETE	TEMPORARY	BRIDGE	BARRIER	REMOVAL	ATTENUATOR,	ATTENUATOR,
	TEMPORARY	STANDARD 701321	STANDARD 701316	SIGNING	SIGN	MARKING	BARRIER	CONCRETE	RAIL	TERMINAL,		TEMPORARY	RELOCATE
	DETOUR	(SPECIAL)				LINE 6"		BARRIER		TYPE 11		(NON-REDIRECTIVE)	(NON-REDIRECTIVE)
	EACH	EACH	EACH	L SUM	CAL MO	FOOT	FOOT	FOOT	FOOT	EACH	FOOT	EACH	EACH
STAGE I	1				4								
STAGE II		1		1		1000	1000					2	
STAGE III			1			162.5		162.5	844	2	21		2
TOTAL	1	1	1	1	4 .	1162.5	1000	162.5	844	2	21 *	2	2

GUARDRAIL REMOVAL IS NOT A TOTAL QUANTITY.
 SEE GUARDRAIL SCHEDULE FOR ADDITIONAL QUANTITY.

REVISIONS	;	_
NAME	DATE	
	-	

ILLINOIS DEPARTMENT OF TRANSPORTATION

 CONTRACT NO. 76899

 F.A.S. RTE.
 SECTION
 COUNTY SHEETS NO.

 1780
 24-BR-2
 CLINTON
 63
 5

TO STA.

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

STA.

SCHEDULE OF QUANTITIES

FAS ROUTE 1780 SECTION 24-BR-2 CLINTON COUNTY SN 014-0062