



TYPE A - CABLE SPLICE

FOR SPLICES IN HOMERUNS AND FOR EXTENSIONS TO EXISTING CABLES ONLY N.T.S.



TYPE B - CABLE SPLICE

FOR SPLICES FOR USE AT JUNCTION OF HOMERUN WITH LOOP CIRCUIT NOT TO SCALE




TYPE C AND D - CABLE SPLICE

FOR SPLICES AT RUNWAY/TAXIWAY LIGHTS AND SIGNS NOT TO SCALE

CABLE SPLICE NOTES

- INSIDE DIAMETER OF CONNECTOR SHALL PROPERLY MATCH THE OUTSIDE DIAMETER OF CABLE.
- 2. WRAP WITH AT LEAST ONE LAYER OF RUBBER OR SYNTHETIC RUBBER TAPE AND ONE LAYER OF PLASTIC TAPE, ONE—HALF LAPPED, EXTENDING AT LEAST 1--1/2 INCHES ON EACH SIDE OF JOINT.
- THE COST OF FURNISHING AND INSTALLING ALL SPLICE MATERIALS SHALL BE INCIDENTAL TO THE ASSOCIATED CABLE ITEMS.
- 4. THE CONTRACTOR SHALL HAVE A MINIMUM OF TWO (2) TYPE A SPLICE KITS ON THE JOB SITE AT ALL TIMES FOR EMERGENCY REPAIRS.




CABLE IN UNIT-DUCT-PLOWED

NO SCAL

NOTE

- TO FURTHER REDUCE THE POSSIBILITY OF WATER/MOISTURE ENTERING INTO THE CONNECTOR BETWEEN THE CABLE AND THE FIELD ATTACHED CONNECTOR, IT IS REQUIRED THAT A HEAT SHRINKABLE TUBING WITH INTERNAL ADHESIVE BE APPLIED OVER THE ENTIRE CABLE CONNECTOR.
- DUCT MARKERS SHALL BE INSTALLED AT EVERY NEW DUCT AND AT EVERY EXISTING DUCT USED FOR THIS PROJECT.
- CONTRACTOR SHALL HAVE THE OPTION TO TRENCH OR PLOW UNIT DUCT. NO ADDITIONAL PAYMENT SHALL BE MADE FOR TRENCHING.



TRENCH DETAIL NO SCALE

NOTE

OR GRS CONDUIT (TYP.)

- TRENCHES WITH MORE THAN 2 CABLES SHALL BE INCREASED 3" IN WIDTH FOR EACH ADDITIONAL CABLE. IF SPECIFIED ON PLANS, TWO PARALLEL TRENCHES MAY BE CONSTRUCTED.
- DEPTH OF TRENCHES SHALL BE AS SHOWN ABOVE UNLESS OTHERWISE SPECIFIED ON THE PLANS.
- 3. SAND BACKFILL SHALL BE USED IF THE EXISTING SOIL DOES NOT MEET THE BACKFILL REQUIREMENTS.
- 4. ALL DISTURBED SURFACES SHALL BE RESTORED TO THEIR ORIGINAL CONDITION. COST IS INCIDENTAL TO TRENCH RETURFING MATERIALS.

NOTE: AT CONTRACTOR'S OPTION, CABLE PLOWING MAY BE USED IN LIEU OF TRENCHING.

DUO74 K:\DupageAp\0425705\Draw\Sheets\ FILE: txy-elec-dtl.dwg LAYOUT: Layout1

FILE: txy-elec-dtl.dwg
LAYOUT: Layout1
UPDATE BY: johse
SURVEY BOOK #
DATE: Tue 6/13/06 10:13am
XREF DWG: tbclnt.dwg
tb.dwg

NUMBER	BY	DATE
HOMBER		DAIL
l		
		ļ
1		1

THIS BAR IS EQUAL TO 2"
AT FULL SCALE (34X22).

CHARLI DUPAGE AIRPORT WEST CHICAGO, ILLINOIS REHABILITATE TAXIWAYS ALPHA AND AIL DET RICAL SHEET C M DESIGN BY JRL JRO

CHECKED BY: CAL

APPROVED BY: DLP

DATE: 06/09/06

JOB No: 04257-05

ILLINOIS PROJECT: DPA-3454

A.I.P. PROJECT: 3-17-0017-B19

SHEET 18 OF 20 SHEETS