



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 26, 2023

SUBJECT: Pedestrian Overpass (IL 59)  
Section 21-00067-00-BR (Streamwood)  
Cook County  
Contract No. 61J67  
Item 008  
August 4, 2023 Letting  
Addendum (A)

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices**
- 2. Revised Plan Sheets 1, 2, 5, 6, 18, 21, 56, & 58**
- 3. Added Plan Sheet 78A**
- 4. Revised page ii to the Special Provisions Index**
- 5. Revised pages 17, 18, 44, & 109 of the Special Provisions**
- 6. Added page 88A to the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

ELECTRIC UTILITY SERVICE CONNECTION (COMED) .....	62
EXPOSED RACEWAYS.....	63
LUMINAIRE, LED, SPECIAL .....	66
LIGHT POLE, SPECIAL .....	68
GENERAL ELECTRICAL REQUIREMENTS .....	69
UNDERGROUND RACEWAYS .....	83
AESTHETIC LED LIGHTING ITEMS.....	84
PEDESTRIAN BRIDGE LIGHTING SYSTEM.....	86
EXPLORATION TRENCH, SPECIAL.....	88A
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING .....	89
LOCAL ROADS AND STREETS SPECIAL PROVISIONS .....	91
LR 107-4 – SPECIAL PROVISION FOR INSURANCE	
LR 1030-2 – SPECIAL PROVISION FOR LOCAL QUALITY ASSURANCE/QUALITY MANAGEMENT QC/QA	
STORM WATER POLLUTION PREVENTION PLAN AND NOI .....	94
IDNR, OWR FLOODWAY PERMIT .....	104
ARMY CORPS OF ENGINEERS (ACOE) PERMIT.....	107
LPC-662 Forms.....	110

Add the following sentence after the Holiday Period table in the fourth paragraph of Article 107.09:

“The Length of Holiday Period for Thanksgiving shall be from 5:00 AM the Wednesday prior to 11:59 PM the Sunday After”

Delete the fifth paragraph of Article 107.09 of the Standard Specifications:

“On weekends, excluding holidays, roadways with Average Daily Traffic of 25,000 or greater, all lanes shall be open to traffic from 3:00 P.M. Friday to midnight Sunday except where structure construction or major rehabilitation makes it impractical.”

### **TRAFFIC CONTROL PLAN**

Traffic Control shall be according to the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and State Standards contained in the plans, and the Special Provisions contained herein.

Special attention is called to Article 107.09 of the Standard Specifications and the following State Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall contact the District One Bureau of Traffic and Village of Streamwood at least 72 hours in advance of beginning work.

### **STANDARDS**

701001-02, 701006-05, 701101-05, 701106-02, 701301-04, 701311-03,  
701426-09, 701501-06, 701602-10, 701606-10, 701611-01, 701701-10,  
701801-06 and 701901-08

### **DETAILS**

TC-10

### **SPECIAL PROVISIONS**

SPECIAL PROVISIONS:

Vehicle and Equipment Warning Lights (BDE)  
Work Zone Traffic Control Devices (BDE)  
Public Convenience and Safety (D1)  
Temporary Information Signing  
Maintenance of Roadways  
Keeping Arterial Roadways Open To  
Traffic (With 15 Min Full Stops)  
Traffic Control and Protection (Arterials) (D1)

LOCAL ROADS

Work Zone Traffic Control Surveillance (LRS 3)

RECURRING SPECIAL PROVISIONS:

**KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (WITH 15 MIN FULL STOPS)**

Effective: January 22, 2003

Revised: August 10, 2017

The Contractor shall provide the necessary traffic control devices to warn the public and to delineate the work zone as required in these Special Provisions, the Standard Specifications, the State Standards, and the District Details.

Arterial lane closures shall be in accordance with the Standard Specifications, Highway Standards, District Details, and the direction of the Engineer. The Contractor shall request and gain approval from the Engineer seventy-two (72) hours in advance of all long-term (24 hrs. or longer) lane closures.

Arterial lane closures not shown in the staging plans will not be permitted during **peak traffic volume hours**.

Peak traffic volume hours are defined as weekdays (Monday through Friday) from **6:00 AM to 8:30 AM and 4:30 PM to 6:00 PM**.

Full closure of all arterial lanes in one or both directions will only be permitted for a maximum of 15 minutes at a time Sunday through Thursday between the hours of 9:00 pm and 5:00 am. During full roadway closures, the Contractor will be required to reduce the roadway to only one open traffic lane in the affected direction(s) of travel using the appropriate State Standard(s) and District Detail(s). Police forces shall be notified and requested to close the remaining lane to facilitate the necessary work activities, except that a flagger may be substituted for daytime closures with the approval of the Engineer. The Contractor shall notify the District One Arterial Traffic Control Supervisor at 847-705-4470 at least three (3) working days (weekends and holidays DO NOT count into this notification time) in advance of the proposed road closures.

Private vehicles shall not be parked in the work zone. Contractor's equipment and/or vehicles shall not be parked on the shoulders or in the median during non-working hours. The parking of equipment and/or vehicles on State right-of-way will only be permitted at locations approved by the Engineer in accordance with Articles 701.08 and 701.11 of the Standard Specifications.

Should the Contractor fail to completely open and keep open all the traffic lanes to traffic in accordance with the limitations specified above, the Contractor shall be liable to the Department for the amount of:

One lane or ramp blocked = \$ 1,000

Two lanes blocked = \$ 2,500

Not as a penalty but as liquidated and ascertained damages for each and every 15 minute interval or a portion thereof that a lane is blocked outside the allowable time limitations. Such

- B. Storage: Store materials in clean, dry area in accordance with manufacturer's instructions. Keep materials in manufacturer's original, unopened containers and packaging until installation.
- C. Handling: Protect materials and finish during handling and installation to prevent damage.

**1.6 WARRANTY**

- A. Warranty Information:  
Products will be free from defects in material and/or workmanship for a period of three years

**PART 2 PRODUCTS**

**2.2 TRASH AND RECYCLING RECEPTACLES:**

- A. MANUFACTURER: VICTOR STANLEY  
MODEL: S-45  
FINISH COLOR: POWDERCOATED BLACK  
OPTIONS: PROVIDE CUSTOMIZABLE ELEMENT FOR 'VILLAGE OF STREAMWOOD TEXT AND LOGO FEATURE' ARTWORK TO BE PROVIDED  
OPTIONS: PROVIDE SIGNAGE THAT DESIGNATES 'TRASH' AND 'RECYCLING'  
MOUNTING: SURFACE MOUNT PER MANUFACTURER'S RECOMMENDATIONS AND EQUIPMENT  
CONTACT: [WWW.VICTORSTANLEY.COM](http://WWW.VICTORSTANLEY.COM)
- B. MANUFACTURER: LANDSCAPE FORMS  
MODEL: CHASE PARK  
FINISH COLOR: POWDERCOATED BLACK  
OPTIONS: PROVIDE CUSTOMIZABLE ELEMENT FOR 'VILLAGE OF STREAMWOOD TEXT AND LOGO FEATURE' ARTWORK TO BE PROVIDED  
MOUNTING: SURFACE MOUNT PER MANUFACTURER'S RECOMMENDATIONS AND EQUIPMENT  
CONTACT: [WWW.LANDSCAPEFORMS.COM](http://WWW.LANDSCAPEFORMS.COM)
- C. MANUFACTURER: KEYSTONE RIDGE  
MODEL: MIDTOWN  
FINISH COLOR: POWDERCOATED BLACK  
OPTIONS: PROVIDE CUSTOMIZABLE ELEMENT FOR 'VILLAGE OF STREAMWOOD TEXT AND LOGO FEATURE' ARTWORK TO BE PROVIDED  
OPTIONS: PROVIDE SIGNAGE THAT DESIGNATES 'TRASH' AND 'RECYCLING'  
MOUNTING: SURFACE MOUNT PER MANUFACTURER'S RECOMMENDATIONS AND EQUIPMENT  
CONTACT: [WWW.KEYSTONERIDGEDESIGNS.COM](http://WWW.KEYSTONERIDGEDESIGNS.COM)

**PART 3 EXECUTION**

**3.1 EXAMINATION**

**EXPLORATION TRENCH, SPECIAL**

This work shall consist of constructing a trench for the purpose of verifying clearances and locations of existing utilities and storm sewers. The exploration trench shall be constructed at the locations directed by the Engineer.

The depth of the trench shall be variable. The width of the trench shall be sufficient to allow proper investigation of the entire trench.

After the trench has been inspected by the Engineer. The excavated material shall be used to backfill the trench in a manner satisfactory to the Engineer. Any excess materials shall be disposed of according to Article 202.03 of the Standard Specifications.

This work will be paid for at the contract unit price per foot (meter) for EXPLORATION TRENCH, SPECIAL.

This letter does not obviate the need to obtain all other required Federal, state, or local approvals before starting work. If you have any questions, please contact me by telephone at (773) 909-1628, or email at [Samantha.J.Chavez@usace.army.mil](mailto:Samantha.J.Chavez@usace.army.mil).

Sincerely,

Samantha J. Chavez

Digitally signed by Samantha J.  
Chavez  
Date: 2023.05.23 13:28:48 -05'00'