



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 21, 2023

SUBJECT FAP Route 333 (IL 120 (Belvidere Rd))  
Project HSIP-N6DK(011)  
Section FA 333 21 Intersection  
Lake County  
Contract No. 62R18  
Item No. 13, August 4, 2023 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 3-6 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

**MAINTENANCE OF ROADWAYS (D1)**

Effective: September 30, 1985

Revised: November 1, 1996

Beginning on the date that work begins on this project, the Contractor shall assume responsibility for normal maintenance of all existing roadways within the limits of the improvement. This normal maintenance shall include all repair work deemed necessary by the Engineer, but shall not include snow removal operations. Traffic control and protection for maintenance of roadways will be provided by the Contractor as required by the Engineer.

If items of work have not been provided in the contract, or otherwise specified for payment, such items, including the accompanying traffic control and protection required by the Engineer, will be paid for in accordance with Article 109.04 of the Standard Specifications.

**STATUS OF UTILITIES (D1)**

Effective: June 1, 2016

Revised: January 1, 2020

Utility companies and/or municipal owners located within the construction limits of this project have provided the following information regarding their facilities and the proposed improvements. The tables below contain a description of specific conflicts to be resolved and/or facilities which will require some action on the part of the Department's contractor to proceed with work. Each table entry includes an identification of the action necessary and, if applicable, the estimated duration required for the resolution.

**UTILITIES TO BE ADJUSTED**

Conflicts noted below have been identified by following the suggested staging plan included in the contract. The company has been notified of all conflicts and will be required to obtain the necessary permits to complete their work; in some instances, resolution will be a function of the construction staging. The responsible agency must relocate, or complete new installations as noted below; this work has been deemed necessary to be complete for the Department's contractor to then work in the stage under which the item has been listed.

LOCATION	TYPE	DESCRIPTION	RESPONSIBLE AGENCY	DURATION OF TIME
21+98 50' R To 24+40 29' L	Pedestals / Underground Fiber	In conflict with Proposed shared use path, and roadside regrading.	AT&T	5 Days after completion of ComEd relocation.

Revised 7/21/2023

FAP Route 333 (IL 120 (Belvidere Rd))  
 Project HSIP-N6DK(011)  
 Section FA 333 21 Intersection  
 Lake County  
 Contract No. 62R18

12+28 43' R, 14+00 43' R, 15+62 42' R, 16+75 42' R 17+33 32' L 17+41 43' R, 19+04 39' L, 21+05 38' L, 21+98 51' R, 22+47 31' L, 23+40, 28' L,	Utility Pole / Guys	In conflict with proposed widening, roadside regrading, and shared-use path.		<u>12</u> Days after completion of ComEd relocation.
12+28 43' R to 17+41 43' R  17+33 32' L to 23+40 28' L  22+47 31' L to 21+98 51' R	Aerial Lines	Attached to poles in conflict.		<u>45</u> Days after completion of ComEd relocation.
12+28 43' R to 17+41 43' R  17+33 32' L to 23+40 28' L  22+47 31' L to 21+98 51' R	Aerial Lines	Attached to poles in conflict.	Comcast	<u>15</u> Days after completion of ComEd relocation.
15+65 42' R	Splice Box / Underground Fiber	In conflict with proposed regrading.		<u>10</u> Days
16+54 33' L 17+28 33' L	Utility Pole / Guys	Utility Pole with attached aerial lines in conflict with proposed widening, roadside regrading, and shared-use path.		<u>20</u> Days
12+28 43' R to 17+41 43' R  17+33 32' L to 23+40 28' L  22+47 31' L to 21+98 51' R	Aerial Lines	Attached to poles in conflict.	ComEd	<u>40</u> Days
17+36 39' R 21+33 25' R	Gas Valves	In conflict with proposed Shared-Use path.	North Shore Gas	<u>5</u> Days

Revised 7/21/2023

14+66 41' R 18+96 41' R 20+73 43' R	Gas Line	In conflict with proposed MH/Culvert.		<u>  90  </u> Days
49+16 64' L	Handhole	In conflict with proposed curb, grading and paved shoulder removal.	Lumen (Century Link) Reference: P-404927 IL	<u>  5  </u> Days

The following contact information is what was used during the preparation of the plans as provided by the Agency/Company responsible for resolution of the conflict.

Agency/Company Responsible to Resolve Conflict	Name of contact	Phone	E-mail address
Lumen (Century Link)	Diane Murphy (Reference: P-404927 IL)		<a href="mailto:diane.murphy@lumen.com">diane.murphy@lumen.com</a>
AT&T	Hector Garcia (Reference: WK4202-2)	(630) 639-8372	<a href="mailto:hg2929@att.com">hg2929@att.com</a> <a href="mailto:g05256@att.com">g05256@att.com</a>
	Bradley Ruf	(847) 224-8972	<a href="mailto:br056t@att.com">br056t@att.com</a>
North Shore Gas	Jay Hammer	(847) 263-4678	<a href="mailto:Jay.hammer@northshoregasdelivery.com">Jay.hammer@northshoregasdelivery.com</a>
ComEd	Dan Mendez	(773) 799-6111	<a href="mailto:Daniel.Mendez@ComEd.com">Daniel.Mendez@ComEd.com</a>
Comcast	Daniel O'Shea	(847) 561-4220	<a href="mailto:daniel_oshea@comcast.com">daniel_oshea@comcast.com</a>

### **UTILITIES TO BE WATCHED AND PROTECTED**

The areas of concern noted below have been identified by following the suggested staging plan included for the contract. The information provided is not a comprehensive list of all remaining utilities, but those which during coordination were identified as ones which might require the Department's contractor to take into consideration when making the determination of the means and methods that would be required to construct the proposed improvement. In some instances, the contractor will be responsible to notify the owner in advance of the work to take place so necessary staffing on the owner's part can be secured.

LOCATION	TYPE	DESCRIPTION	OWNER
South of IL 120 West side of O'Plaine Road	Fiber Optic	Fiber Optic running behind the back of curb. Proposed work should be monitored carefully.	Lake Count DOT
11+38 36' R to 17+50 36' R	Communications Line	AT&T line running parallel to proposed bottom ditch.	AT&T
Eastside of O'Plaine and Northside of IL 120	Fiber Optic	Fiber Optic along the ditch and widening areas. Proposed work should be monitored carefully.	Lumen (Century Link)
Along on the Roadsides O'Plaine Road	Communications line	Communications line running behind the back of curb. Proposed work should be monitored carefully.	AT&T
Along O'Plaine Road on the east side	HDPE and PCCP Force Main	42-inch force main. District facilities are below proposed storm sewers	North Shore Water Reclamation District
NW corner of O'Plaine Road and Eastwood Ave.	Handhole and Underground Fiber Optic Cable	Existing Handhole placed behind the curb and proposed paved shoulder removal	MCI /Verizon

No facilities requiring extra consideration (*or listed as noted above*)

The following contact information is what was used during the preparation of the plans as provided by the owner of the facility.

Agency/Company Responsible to Resolve Conflict	Name of contact	Phone	E-mail address
North Shore Water Reclamation District	Nick Wolf	847-623-6060	niwolf@northshorewrd.org
MCI /Verizon	Joe B. Chaney Jr.	312-6177-2131	joe.chaney@verizon.com

The above represents the best information available to the Department and is included for the convenience of the bidder. The days required for conflict resolution should be considered in the bid as this information has also been factored into the timeline identified for the project when setting the completion date. The applicable portions of the Standard Specifications for Road and Bridge Construction shall apply.

Revised 7/21/2023