

SUMMARY OF QUANTITIES

LOCATION OF WORK: U.S. ROUTE 30 - STA. 716+77.10 TO STA. 846+13.54

PAY ITEM NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL / 20% STATE		100% SUNNYLAND SANITARY DIST. Y060	80% FEDERAL / 20% STATE	100% MUNICIPALITY	80% FEDERAL / 20% STATE
				ROADWAY I000-2A	ROCK RUN & SUNNYLAND DRAIN BOX CULVERTS Y007	RETAINING WALL Y007	TRAFFIC SIGNALS Y031-1F	TRAINING Y080	SAFETY SFTY-3N
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	12241	12241					
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	1620	1620					
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	3322	3322					
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	49	49					
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	55	55					
X4023000	TEMPORARY ACCESS (ROAD)	EACH	18	18					
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	708	708					
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	185	185					
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	3146	3146					
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	2222	2222					
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	39453	39453					
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE IL-4.75, N50	TON	2090	2090					
X4000008	BITUMINOUS SURFACE REMOVAL, 2 1/2"	SQ YD	32105	32105					
X5121800	PERMANENT STEEL SHEET PILING	SQ FT	17992			17992			
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	16	16					
X7240500	RELOCATE EXISTING SIGNS	EACH	4	4					
X6013600	PIPE UNDERDRAINS 4" (MODIFIED)	FOOT	2118	2118					
X60228500	MANHOLES, SPECIAL WITH SPECIAL FRAME AND CLOSED LID	EACH	14	14					
X61600317	UNIT DUCT, 2*6 XLP-USE, 1*6 GROUND 1 1/2" POLYETHYLENE	FOOT	341					341	
XX003653	SPECIAL STRUCTURE SP-1	EACH	1	1					
X0325058	SPECIAL STRUCTURE SP-2	EACH	1	1					
X0325059	SPECIAL STRUCTURE SP-3	EACH	1	1					
X0325060	SPECIAL STRUCTURE SP-4	EACH	1	1					
X0325061	SPECIAL STRUCTURE SP-5	EACH	1	1					
X0325062	SPECIAL STRUCTURE SP-6	EACH	1	1					
X0325063	SPECIAL STRUCTURE SP-7	EACH	1	1					
X4073136	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 12 3/4"	SQ YD	65534	65534					

L:\DOT\0006602\design\comp\Summary of Quantities\SunQuan008.dgn

LEGEND:
□ NON-PARTICIPATING WORK
* SPECIALTY ITEMS



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
US ROUTE 30
SHEET 8 OF 8

SCALE: N/A
DATE: 3/1/05

DRAWN BY: AMB
CHECKED BY: KDF/AMB

Rev. 7-26-05