




SECTIONAL PLAN







PREFABRICATED REINFORCED CONCRETE SLAB WHEN THE PRECAST REINFORCED CONCRETE SECTIONS ALTERNATE IS USED WITH SAND CUSHION

11/2" CL. (TYP.)

## ALTERNATE BOTTOM SLAB

## NOTES:

1) SEE DRAINAGE SCHEDULE FOR OTHER INVERT ELEVATIONS, PIPE DIAMETERS, AND RIM ELEVATION.

SECTION

STA.

COUNTY TOTAL SHEE SHEETS NO.


COOK

TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

62300 • (1818, ETC, 2324.6-1P)R-8

-SAND CUSHION

- 2) ALL DIMENSIONS ARE INSIDE DIMENSIONS.
  3) UTILIZE PIPE "T" SECTIONS WHENEVER AVAILABLE.
  4) PRESET PIPE OPENINGS IN PRECAST REINFORCED CONCRETE SECTIONS IF "T" SECTIONS AND SPECIAL FITTINGS ARE NOT AVAILABLE.
  5) ROTATE FLAT SLAB AND MANHOLE RISER SO STEPS
- AVOID STORM SEWER OPENINGS.
- 6) CAST IRON STEPS SHALL BE GRAY IRON CONFORMING TO THE REQUIREMENTS OF ARTICLE 1006.14 OF THE STANDARD SPECIFICATIONS. STEPS SHALL BE EMBEDDED INTO THE WALL A MINIMUM OF THREE (3) INCHES. STEPS SHALL NOT BE EXTENDED ON THE OUTSIDE.
- 7) JOINT CONFIGURATION AND DIMENSIONS OF FLAT SLAB TOP SHALL MATCH AND FIT THE RISER JOINT DETAIL.
- 8) LIFTING DEVICES SHALL BE APPROVED BY THE ENGINEER.
- 9) ALL WORK SHALL BE AS PER AASHTO REQUIREMENTS. ASTM IS LISTED AS SUPPLEMENTARY.



DROP MANHOLE 6' DIA.

REVISIONS

ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.I. 94/90 (DAN RYAN EXPRESSWAY) 31ST STREET TO 71ST STREET NB EXPRESS LANE RECONSTRUCTION DRAINAGE STRUCTURE DETAILS DROP MANHOLE (STRUCTURE 7-07)

SCALE: DATE: 7/7/05

DRAWN BY: JRW CHECKED BY: EL

AND KEICEY

ONE NORTH FRANKLIN CHICAGO, IL 60606

AND KEICEY

FAX: G122 251–300

FES: WWW.EKCORP.COI