

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2004-119 GRR	WILL	15	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO. 62885

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	URBAN WILL CO. I-55 STATE 100% SFTY-3J	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT								
X0324589	PIPE UNDERDRAIN OUTLET EXTENSION FOR 4" PIPE	EACH	18	18						
20200100	EARTH EXCAVATION	CU YD	844	844						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3407	3407						
20400800	FURNISHED EXCAVATION	CU YD	1716.6	1716.6						
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	12947	12947						
* 25000210	SEEDING, CLASS 2A	ACRE	2.7	2.7						
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	243	243						
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	243	243						
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	243	243						
* 25100630	EROSION CONTROL BLANKET	SQ YD	12947	12947						
48101100	AGGREGATE SHOULDERS, TYPE A 12"	SQ YD	8514	8514						
48202800	BITUMINOUS SHOULDERS SUPERPAVE 10"	SQ YD	55	55						
54248515	CONCRETE COLLAR	EACH	36	36						
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	2	2						
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	290	290						
63000145	STEEL PLATE BEAM GUARD RAIL, TYPE D (SPECIAL)	FOOT	11927	11927						
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1						
63304395	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 2	EACH	1	1						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4						
67100100	MOBILIZATION	L SUM	1	1						
78200405	GUARDRAIL MARKERS	EACH	35	35						
X0301508	REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE DRAIN	EACH	18	18						
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1						
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	3	3						
Δ Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1						

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	URBAN WILL CO. I-55 STATE 100% SFTY-3J	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT								
Δ Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1	1						
X6330105	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1 (SPECIAL)	EACH	1	1						

Δ SFTY-3N
* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAI 55 (INTERSTATE 55)
SOUTH OF IL 126 TO RENWICK

PLOT DATE: 5/26/2005

5/26/2005
10:00 AM
C:\PROJECTS\2004-119 GRR\GRR\GRR.dwg