| F.A RTE. | SECTION | COUNTY | ′ | TOTAL SHEETS | SHEE NO. | | |
|-----------------|----------------|------------|-------|-----------------|-------------|--|--|
| VAR. | 2005-019] | COOL | < | 9 | 3 | | |
| STA TO STA | | | | | | | |
| FED. ROA | D DIST. NO ILL | INOIS FED. | AID F | ROJECT | | | |

INDEX OF SHEETS

- TITLE SHEET
- LOCATION MAP
- 3. INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES
- 4. SUMMARY OF QUANTITIES
- 5.-7. LOCATION DETAILS
- 8. PERMANENT PROTECTIVE SHIELD DETAILS
- TRAFFIC CONTROL FOR PARTIAL RAMP AND SHOULDER CLOSURES

LIST OF STATE STANDARD

701400-02 APPOROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-03 LANE CLOSURE, FREEWAY/EXPRESSWAY
701446 TWO LANE CLOSURE, EXPRESSWAY
702001-05 TRAFFIC CONTROL DEVICES

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 OR "C.U.A.N" AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES.

48 HOUR NOTIFICATION PRIOR TO START OF WORK IS REQUIRED.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISON AT (847) 705-4151 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE CONTRACTOR SHALL BE AWARE THAT SOME LOCATIONS HAVE UTILITY CONDUITS. ANY DAMAGE TO THE CONDUITS CAUSED BY THE CONTRACTOR'S OPERATIONS SHALL BE REPLACED OR REPAIRED BY THE CONTRACTOR AT THEIR EXPENSE. THE CONTRACTOR SHALL ADJUST THE PROTECTIVE SHIELDING TO FIT AROUND THE CONDUITS. DETAILS SHALL BE APPROVED BY THE ENGINEER BEFORE INSTALLATION. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING STRUCTURES HAVE BEEN TAKEN

EXISTING PLANS AND ARE SUBJECT TO NOMINAL VARIATIONS FROM WHAT IS ACTUALLY EXISTING. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO VERIFY SUCH DIMESNIONS AND DETAILS IN THE FIELD AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF THE WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

WHEN ARITIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.

THE CONTRACTOR SHALL ADJUST THE PROTECTIVE SHIELDING TO RIDE ABOVE THE EXISTING LIGHTING FIXTURES IN ORDER TO MAINTAIN THE EXISTING LEVEL OF LIGHTING OF THE ROADWAY UNDERNEATH. DETAILS SHALL BE APROVED BY THE ENGINEER BEFORE INSTALLATION.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECIEVED FROM BRIDGE INSPECTORS

| REVISIO | | ILLINOIS DEPARTMENT OF TRANSPORTATION | | | |
|---------|------|---------------------------------------|----------------------------|----------------|--|
| NAME | DATE | 1001 | IOIS DEL ARTIMEN | | |
| | | IN | DEX OF SHEETS, STATE ST | GENERAL NOTES, | |
| | | SCALE: VE | RT. | DRAWN BY | |
| | | DATE | N12. | CHECKED BY | |

NAME = cryprojects/dil8305/dil8305ac.dgn