

F.A. P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	22BR-1	STEPHENSON	30	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	X080-2A 80% FED/ 20% STATE	SFTY-3N 80% FED/ 20% STATE
20400800	FURNISHED EXCAVATION	CU YD	338	338	
25000750	MOWING	ACRE	0.2	0.2	
25100630	EROSION CONTROL BLANKET	SQ YD	911	911	
28000400	PERIMETER EROSION BARRIER	FOOT	559	559	
28000500	INLET AND PIPE PROTECTION	EACH	1	1	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	18	18	
20200100	EARTH EXCAVATION	CU YD	89	89	
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	5	5	
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	114	114	
44200108	PAVEMENT PATCHING, TYPE II, 9 INCH	SQ YD	210	210	
44200112	PAVEMENT PATCHING, TYPE III, 9 INCH	SQ YD	209	209	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	98	98	
48201400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	791	791	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1	
50300260	BRIDGE DECK GROOVING	SQ YD	114	114	
50301200	CONCRETE WEARING SURFACE	SQ YD	115	115	
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	45	45	
50301250	FORMED CONCRETE REPAIR (DEPTH GREATER THAN 5 INCHES)	SQ FT	12	12	
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	1084	1084	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1400	1400	
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	146	146	
51500100	NAME PLATES	EACH	1	1	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	56	56	
54213450	END SECTION 15"	EACH	2	2	

\* SPECIALITY ITEMS

⓪NON-PARTICIPATING

SUMMARY OF QUANTITIES