

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	22BR-1	STEPHENSON	32	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

63200310 GUARDRAIL REMOVAL

EQOI	LOCATION			
87	US 20			
87	LT	9+30	-	10+16
87	RT	9+30	-	10+16
87	LT	10+87	-	11+74
87	RT	10+87	-	11+74
<u>348</u>	TOTAL			

63500105 DELINEATORS

EACH	LOCATION			
	US 20			
1	LT	8+33		
1	RT	8+83		
1	LT	12+83		
1	RT	13+33		
<u>4</u>	TOTAL			

70400100 TEMPORARY CONCRETE BARRIER

EQOI	LOCATION			
240	US 20			
320	RT	9+13	-	11+53
<u>560</u>	TOTAL	9+48	-	12+68

78001110 PAINT PAVEMENT MARKING - LINE 4" (TWO COATS)

EQOI	LOCATION			
37	US 20			
292	STA.	10+15	-	10+88 (YELLOW SKIP DASH)
<u>329</u>	TOTAL	10+15	-	10+88 (WHITE EDGE LINE)

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION			
1	US 20			
<u>1</u>	TOTAL			

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION			
1	US 20			
<u>1</u>	TOTAL			

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION			
4	US 20			
4	LT	8+82	-	9+82
4	RT	9+33	-	9+83
4	LT	11+20	-	12+82.5
4	RT	11+20	-	12+32.5
<u>16</u>	TOTAL			

78201000 TERMINAL MARKER - DIRECT APPLIED

EACH	LOCATION			
1	US 20			
1	LT	8+33		
1	RT	8+83		
1	LT	12+83		
1	RT	13+33		
<u>4</u>	TOTAL			

X4066414 BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX "C" N50

TON	LOCATION			
12	US 20			
18	LT	8+19	-	10+16
34	RT	8+63	-	10+16
25	LT	10+87	-	14+12
25	RT	10+87	-	13+18
<u>705</u>	TOTAL			

GOOD NEIGHBOR POLICY
TO BE DETERMINED BY ENGINEER

794

XX005322 BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX D, N70

TON	LOCATION			
7	US 20			
7	LT&RT	9+96	-	10+16
7	LT&RT	10+87	-	11+07
<u>14</u>	TOTAL			

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION			
1	US 20			
1	RT	9+13		
1	LT	9+48		
1	RT	11+53		
1	LT	12+68		
<u>4</u>	TOTAL			