

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION



* Section 22 BR-1

Contract #64B04





~ £ 5"x7"x6"

Tack weld to post & plate

HSS 6" x 3" x 4" x 32" long

NOTES

SECTIONS AT RAIL SPLICE

See bridge sheet 3 of 5 for railing connection to the existing approach slabs.

Hollow structural sections shall conform to the requirements of ASTM designation A 500 Grade B Structural Steel Tubing and shall meet the longitudinal CVN requirements of 15 ft-lbs at 0° F.

All other steel shapes and plates shall conform to the requirements of AASHTO M 270 Grade 36 except posts and angles shall conform to AASHTO M 270, Grade 50.

Bolts, cap screws, and nuts shall conform to the requirements of ASTM designation A 307 except for high strength bolts, nuts and washers noted which shall conform to AASHTO M 164.

All bolts, nuts, cap screws, washers and lock washers shall be galvanized according to AASHTO M 232.

All posts, railing, rail splices, anchor devices and angles shall be galvanized after shop fabrication according to AASHTO M 111 and ASTM A 385. Galvanized rail shall not be painted.

Railing shall be according to Section 509 of the Standard Specifications, except as noted, and will be paid for at the contract unit price per foot for Steel Bridge Rail, Type SM.

All field drilled holes shall be coated with an approved zinc rich paint before erection.

For multi-span bridges, sufficient $\frac{1}{4}$ " x 6" x 1'-2" galvanized steel shims shall be provided to align rail between adjacent spans. Cost included with Steel Bridge Rail, Type SM.

The $\frac{1}{2}$ " x 7" x 6" plates that come in contact with concrete shall receive two coats of asphalt paint conforming to Section 1060.07 Type II or place 18" fabric bearing pads between the plates and concrete.


The $^34''$ ϕ high strength bolts used to connect the 7 x 4 x 34 angles to the post shall be tightened according to Article 505.04(f)(2) of the Standard Specifications. The $1'' \phi$ high strength bolts connecting the angles to the concrete shall be tightened to a snug fit and given an additional $^{l}_{8}$ turn. The $^{5}_{8}$ $^{\prime\prime}$ ϕ cap screws in bottom of posts shall be tightened to a snug fit only.

BILL OF MATERIAL

Item	Unit	Quantity
Steel Bridge Rail, Type SM	Foot	146

TYPE SM STEEL BRIDGE RAIL SIDE MOUNTED

F.A.P. 301 (U.S. 20) OVER YELLOW CREEK SECTION 22BR-1 STEPHENSON COUNTY STR. NO. 089-0002



2-⁵8″ \$ x 5³4″ Cap Screws

with flat washer.

(Main Span Only) * Threaded areas shall be plugged or blocked off during casting of beam. Galvanized after fabrication.

ANCHOR DEVICE

** Whenever the lower insert assemblies interfere with strand locations, the #3 bars shall be cut and adjusted in order to allow raising or lowering of the lower inserts. Maximum adjustment not to exceed 12".

Roadway

VIEW B-B

53₄"

12

1'-7"

334" 334"

VIEW C-C

Side

<u>€ 1′8′′</u> ø

10-22-04 (6'-3" Maximum Post Spacing)

13₁₆ " x 3" Slotted Holes -

SECTION A-A