CONTRACT NO. 76954

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2	202-2RS-1	MADISON	9	3
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: URBAN 1000-1A 90% FED. 10% STATE		
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.3	1.3		
	40600300	AGGREGATE (PRIME COAT)	TON	6.1	6.1		
	40600990	TEMPORARY RAMP	SQ YD	371	371		
	44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	4079	4079		
	67100100	MOBILIZATION	L SUM	1	1		
	70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1		
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	258	258		
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	62.4	62.4		
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2322	2322		
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	176	176		
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	384	384		
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1702.7	1702.7		
	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	62.4	62.4		
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2322	2322		
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	176	176		
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	384	384		
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	45	45		
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	45	45		
*	88600100	DETECTOR LOOP, TYPE I	FOOT	1227.5	1227.5		
	X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	342	342		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		

* SPECIALTY ITEMS

PLOT DATE = 5/17/2005
FILE NAME = c:\projects\ed076505\plan\sin076505s.dgn
PLOT SCALE = 50.0000 ' / IN.
REFERENCE = $REF4