ORIGINAL SURVEY		BY	DATE
NOTE BOOK	SURVEYED		
	PLOTTED		
	TEMPLATE		
NO.	AREAS		
	AREAS CHECKED		

FINAL SURVEY		BY	DATE
NOTE BOOK	SURVEYED		
	PLOTTED		
	TEMPLATE		
NO.	AREAS		
	AREAS CHECKED		

FARNSWORTH GROUP, INC. CONSULTING ENGINEERS - EFFINGHAM, ILLINOIS

CRAWFORD COUNTY - C.H.1

90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90

505
500

EX. R.O.W.
501.14
498.1
498.4
EX. R.O.W.
C=0.0
F=0.0
159+00.00

IMPROVEMENT ENDS
STA 158+00

510
505
500

EX. R.O.W.
501.53
1:2.5
1:2.5
1:2.5
1:3
498.2
498.2
EX. R.O.W.
158+00.00
C=3.7
F=10.0

SEE PLAN & PROFILE SHEETS
FOR DETAILS OF CULVERT
REPLACEMENT WORK UNDER 1350N

510
505
500

EX. R.O.W.
501.65
TR 1350N
1:2.5
1:2.5
498.2
EX UT
157+16.04
C=4.8
F=8.3

510
505
500

EX. R.O.W.
501.59
1:2.5
1:2.5
498.1
EX UT
157+00.00
C=5.2
F=8.5

505
500
495

EX. R.O.W.
501.20
1:2.5
1:2.5
498.0
1:2.5
497.8
EX. R.O.W.
EX UT
EX WATER
156+00.00
C=2.2
F=7.6

UTILITY LOCATIONS SHOWN ON THE CROSS SECTIONS ARE BASED UPON APPROXIMATE LOCATIONS SUPPLIED BY THE UTILITY COMPANY. THE CONTRACTOR SHALL VERIFY UTILITY LOCATIONS PRIOR TO CONSTRUCTION.

CRAWFORD COUNTY C.H. 1

10
5
0
10
20
SCALE IN FEET

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
694	03-00088-00-WR	CRAWFORD	56	56

FED. ROAD INST. NO. ILLINOIS FED. AID PROJECT
CONTRACT NO. 75433

STA. 156+00 TO STA. 159+00