

SUMMARY OF QUANTITIES


ITEM NO.	DESCRIPTION	UNIT	STATE/LOCAL QUANTITY	LOCAL ONLY QUANTITY	RECORD QUANTITY
AR108108	1/C #8 5KV UG CABLE	LF	600		
AR110202	2" PVC DUCT, DIRECT BURY	LF	500		
AR110504	4-WAY CONCRETE ENCASED DUCT	LF	45		
AR110714	ELECTRICAL MANHOLE 4'	EACH	2		
AR125100	ELEVATED RETROREFLECTIVE MARKER	EACH	28	5	
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	2		
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	1		
AR150510	ENGINEER'S FIELD OFFICE	LS	1		
AR152540	SOIL STABILIZATION FABRIC	SY	7,925	2,400	
AR156510	SILT FENCE	LF	3,000		
AR156520	INLET PROTECTION	EACH	24		
AR162506	CLASS E FENCE 6'	LF	650		
AR162900	REMOVE CLASS E FENCE	LF	420		
AR162964	RELOCATE GATE	EACH	1		
AR163000	TEMPORARY CONSTRUCTION FENCE	LF	750		
AR201610	BITUMINOUS BASE COURSE	TON	905	265	
AR208515	POROUS GRANULAR EMBANKMENT	CY	800		
AR209607	CRUSHED AGG. BASE COURSE - 7"	SY	7,925	2,400	
AR401610	BITUMINOUS SURFACE COURSE	TON	905	265	
AR501900	REMOVE PCC PAVEMENT	SY	290		
AR602510	BITUMINOUS PRIME COAT	GAL	3,160	950	
AR603510	BITUMINOUS TACK COAT	GAL	1,200	400	
AR620520	PAVEMENT MARKING - WATERBORNE	SF	3,950	280	
AR620525	PAVEMENT MARKING - BLACK BORDER	SF	5,130	400	
AR620900	PAVEMENT MARKING REMOVAL	SF	350		
AR701512	12" RCP, CLASS IV	LF	210		
AR701515	15" RCP, CLASS IV	LF	575		
AR701518	18" RCP, CLASS IV	LF	86		
AR701536	36" RCP, CLASS IV	LF	475		
AR701900	REMOVE PIPE	LF	10		
AR705526	6" PERFORATED UNDERDRAIN W/ SOCK	LF	2,050		
AR705640	UNDERDRAIN CLEANOUT	EACH	3		
AR705900	REMOVE UNDERDRAIN	LF	140		
AR751411	INLET - TYPE A	EACH	4		
AR751560	MANHOLE 6'	EACH	3		
AR751567	MANHOLE 7'	EACH	3		
AR751570	MANHOLE - SPECIAL	EACH	1		
AR751943	ADJUST MANHOLE	EACH	1		
AR751983	RECONSTRUCT MANHOLE	EACH	3		
AR800001	TYPE 1 INLET	EACH	6		
AR800028	SLOPE BOX INLET 18"	EACH	2		
AR800053	SOIL GUARD	SY	3,250		
AR800103	EMBANKMENT FILL	CY	24,497		
AR800104	SHOULDER FILL	CY	2,459		
AR901510	SEEDING	ACRE	10.0		
AR905510	TOPSOILING (FROM ON SITE)	CY	4,313		
AR908510	MULCHING	ACRE	9.0		
AR910915	REMOVE ROADWAY SIGN	EACH	2		


FILE: QTY.dwg
 LAYOUT: Layout1
 UPDATE BY: mkatz
 SURVEY BOOK #
 DATE: Wed 6/29/05 3:05pm
 XREF DWG: tblnt.dwg

REVISIONS		
NUMBER	BY	DATE

0 1 2
 THIS BAR IS EQUAL TO 2'
 AT FULL SCALE (34X22).

**PALWAUKEE MUNICIPAL AIRPORT
 WHEELING / PROSPECT HEIGHTS ILLINOIS
 NORTHEAST QUADRANT SITEWORK
 SUMMARY OF QUANTITIES**

© Copyright CMT, Inc.

CMT
 CRAWFORD, MURPHY & TILLY, INC.
 CONSULTING ENGINEERS
 License No. 844-000513



DESIGN BY: ARM
 DRAWN BY: JRL
 CHECKED BY:
 APPROVED BY:
 DATE: 06/28/05
 JOB No: 03290-02
 ILLINOIS PROJECT: PWK-3471