

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				ROADWAY HSIP 90% FED 10% STATE	PED SIGNAL 50% STATE 25% COUNTY	SIDEWALK 80% STATE 20% CITY	TREE REPLACEMENT 100% CITY
				0005	0021	0021	0031
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	240		240	-	-
* 81400100	HANDHOLE	EACH	1		1	-	-
* 81603200	UNIT DUCT, 600V, 3-1C NO.2, 1/C NO.4 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	430		430	-	-
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	650		650	-	-
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2		2	-	-
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	475		475	-	-
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4	-	4	-	-
* 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1	-	1	-	-
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	97	97	-	-	-
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	6	-	6	-	-
* 89502376	REBUILD EXISTING HANDHOLE	EACH	1	-	1	-	-
* 89502380	REMOVE EXISTING HANDHOLE	EACH	1	-	1	-	-
* A2000118	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	3	-	-	-	3
Δ X5539700	STORM SEWERS TO BE CLEANED	FOOT	144	144	-	-	-
X6061460	PAVED DITCH (SPECIAL)	FOOT	166	166	-	-	-
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	-	-	-
* X8360120	LIGHT POLE FOUNDATION, SPECIAL	EACH	2	2	-	-	-
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	1223	1223	-	-	-
Z0013302	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	575	575	-	-	-
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	-	-	-
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	2	2	-	-	-
Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	18	18	-	-	-
Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	2	2	-	-	-
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	104	104	-	-	-
* Z0033024	MAINTAIN EXISTING LIGHTING SYSTEM	L SUM	1	1	-	-	-
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	-	-	-

Δ Non-participating (100% State)

* SPECIALTY ITEM

FILE NAME = P:\2009\ME\090806_Ver-Var-Phil\CADD\W022.US34\Sheet\03-500.sht-ht-US34.dgn
 USER NAME = M. Williams Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
 630.785.0110 voice, 630.839.2566 fax
 www.mps-ill.com

MILLENNIA PROFESSIONAL SERVICES

DESIGNED -	CJD	REVISED -	
DRAWN -	CJD	REVISED -	
CHECKED -	TVN	REVISED -	
DATE -	6/1/2011	REVISED -	

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**US ROUTE 34
 AT NORTH AURORA ROAD /RAYMOND DRIVE**

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	652X-N-3	DUPAGE	34	4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60L22	

SCALE: NTS SHEET NO. 1 OF 2 SHEETS STA. TO STA.