



**EROSION CONTROL NOTES:**

1. TEMPORARY EROSION CONTROL SEEDING TO BE PROVIDED AT ALL ERODIBLE BARE EARTH AREAS, REFER TO SPECIAL PROVISION.
2. NPDES PERMIT IS REQUIRED FOR THE PROJECT.
3. THE CONTRACTORS SHALL PROVIDE & MAINTAIN INLET PROTECTION AT ALL PROPOSED DRAINAGE STRUCTURES AND AT OTHER LOCATIONS DIRECTED BY THE ENGINEER AND/OR SHOWN ON THE PLANS. INLET PROTECTION SHALL BE PLACED PRIOR TO ANY AREA DISTURBANCE.
4. ALL EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE STANDARD SPECIFICATION AND THE APPLICABLE STATE STANDARDS SPECIFICATION AND OF THE APPLICABLE STATE STANDARDS FOR THE ENTIRE DURATION OF THE CONTRACT OR UNTIL SUCH A TIME AS DIRECTED BY THE ENGINEER.
5. AT ANY AREA WHERE THERE IS NO PROPOSED GRADING, THE EXISTING GROUND COVER SHALL REMAIN.
6. EROSION CONTROL BLANKET SHALL BE PLACED SOON AFTER DISTURBANCE OF AREA IS COMPLETED.
7. STRAW BALES WILL NOT BE USED FOR SEDIMENTATION CONTROL IN THIS PROJECT.

**LEGEND**

- PERIMETER EROSION BARRIER
- SEDIMENT CONTROL DRAINAGE STRUCTURE INLET FILTER

FILE NAME =	USER NAME = midyja	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL. RTE.19 (IRVING PARK RD.) AT BARRINGTON RD. EROSION &amp; SEDIMENT CONTROL PLAN</b>	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw_work\pwi\dot\midyja\20156246\14180	sht-eros.dgn	DRAWN -	REVISED -			1321	2010-048-N	COOK	53	12	
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 60L23					
	PLOT DATE = 5/12/2011	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					