## **GENERAL NOTES**

- 1. ALL CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH THE DETAILS IN THE PLANS, THE SPECIAL PROVISIONS INCLUDED IN THE CONTRACT DOCUMENTS, AND THE LATEST EDITION OF THE FOLLOWING STATE OF ILLINOIS SPECIFICATIONS: "THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" (REFERED TO AS THE "STANDARD SPECIFICATIONS", THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS", THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" AND THE "MANUAL OF TEST PROCEDURES FOR MATERIALS".
- 2. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. 48 HOUR NOTIFICATION REQUIRED.
- 3. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT THE WRITTEN PERMISSION OF THE DEPARTMENT.
- 4. THE CONTRACTOR SHALL COORDINATE ALL CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, IMPROVEMENT LOCATED WITHIN THE VILLAGE OF PLAINFIELD, VILLAGE OF ROMEOVILLE, VILLAGE OF BOLINGBROOK, CITY OF DARIEN, VILLAGE OF LEMONT, AND THE VILLAGE OF BURR RIDGE.
- 5. THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO INSTALLATION OF TEMPORARY TRAFFIC CONTROL DEVICES.
- 6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL DIMENSIONS AND EXISTING CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING
- 7. ANY SIGNS OR MAIL BOXES THAT ARE IN CONFLICT WITH THE IMPROVEMENTS SHALL BE REMOVED AND REPLACED IN ACCORDANCE WITH DEPARTMENT STANDARDS AND INCLUDED IN THE COST OF EXCAVATING AND GRADING EXISTING SHOULDERS.
- 8. ANY SOIL DISTURBED AS A RESULT OF THIS PROJECT SHALL BE DISPOSED OF ONSITE AND NEATLY GRADED TO THE SATISFACTION OF THE ENGINEER AND INCLUDED IN THE COST OF EXCAVATING AND GRADING EXISTING SHOULDERS.
- 9. BEFORE STARTING ANY EXCAVATION THE STATE ELECTRICAL MAINTENANCE CONTRACTOR AND THE IDOT BURBAU OF TRAFFIC SHALL BE CONTACTED FOR LOCATIONS OF IDOT LIGHTING, SURVEILLANCE AND TRAFFIC SIGNAL UNDERGROUND EQUIPMENT.
- 10. BEFORE STARTING ANY EXCAVATIONS THE CONTRACTOR CURRENTLY INSTALLING THE NEW SURVELILLANCE SYSTEM UNDER CONTRACT 60E01 SHALL BE CONTACTED TO LOCATE PORTIONS OF THEIR SYSTEM ALREADY INSTALLED BUT NOT YET UNDER THE STATE MAINTENANCE AGREEMENT.

## COMMITMENTS

NO COMMITMENTS

## **HIGHWAY STANDARDS**

STANDARD NO.	DESCRIPTION
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
630001 <i>-09</i>	STEEL PLATE BEAM GUARDRAIL
630301 <i>-05</i>	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
631011 <b>- 07</b>	TRAFFIC BARRIER TERMINAL, TYPE 2
635001-01	DELINEATORS
635006 <i>-03</i>	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011- <i>02</i>	REFLECTOR MARKER AND MOUNTING DETAILS
664001 <i>-02</i>	CHAIN LINK FENCE
701001- <i>02</i>	OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY
701006- <i>03</i>	OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
701011- <i>02</i>	OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY
701101 <i>-02</i>	OFF-RD OPERATIONS, MULTILANE, 15' (4.5m) TO 24" (600 mm) FROM PAVEMENT EDGE
701201- <i>04</i>	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS > 45 MPH
701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701306 <i>-03</i>	LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS $\geq$ 45 MPH
701311 <i>-03</i>	LANE CLOSURE, 2L, 2W, MOVING OPERATIONS DAY ONLY
701326-04	LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING, FOR SPEEDS > 45 MPH
701901-0/	TRAFFIC CONTROL DEVICES
720001 <i>-01</i>	SIGN PANEL MOUNTING DETAILS
720006 <i>-02</i> .	SIGN PANEL ERECTION DETAILS

## **INDEX OF SHEETS**

SHEET NO.	DESCRIPTION
. 1	TITLE SHEET
2	INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES AND COMMITMENTS
3	SUMMARY OF QUANTITIES
4	GENERAL LAYOUT
5 - 15	ROADWAY PLANS
16	DETAILS FOR DEPRESSED CURB AND GUTTER AND SHOULDER TREATMENT AT TBT TY 1 SPL (BD-34
17	TRAFFIC CONTROL DETAILS FOR FREEWAY SINGLE & MULTI-LANE WEAVE (TC-09)
18	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC-10)
19	TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES (TC-17)

DESIGNED - DJS REVISED -5-23-11 PER IDOT REVIEW REVISED DRAWN - UKB CHECKED - LDH REVISED FILE - 100153\_W024-GEN-NOTE.sht

STATE OF ILLINOIS

INTERSTATE 55 - US 6 TO WEST OF INTERSTATE 294 **GUARDRAIL IMPROVEMENTS** INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES AND COMMITMENTS

STA.

COUNTY TOTAL SHEE NO. SECTION DUPAGE/WILL 19 2 CONTRACT NO. 60P47

**DEPARTMENT OF TRANSPORTATION**